
pyexcel Documentation

Release 0.6.0

Onni Software Ltd.

Aug 08, 2018

Contents

1	Introduction	3
2	Installation	5
3	Usage	7
4	Tutorial	9
4.1	One liners	9
4.2	Stream APIs for big file : A set of two liners	15
4.3	Pyexcel-io Plugin guide	19
4.4	For web developer	20
4.5	Pyexcel data renderers	21
4.6	Sheet	22
4.7	Book	32
4.8	Working with databases	38
5	Cook book	41
5.1	Recipes	41
5.2	Loading from other sources	45
6	Real world cases	49
6.1	Questions and Answers	49
6.2	How to inject csv data to database	49
7	API documentation	53
7.1	API Reference	53
7.2	Internal API reference	113
8	Developer's guide	121
8.1	Developer's guide	121
8.2	How to log pyexcel	123
8.3	Packaging with PyInstaller	124
8.4	How to write a plugin for pyexcel	124
9	Change log	127
9.1	Migrate away from 0.4.3	127
9.2	Migrate from 0.2.x to 0.3.0+	127
9.3	Migrate from 0.2.1 to 0.2.2+	129

9.4	Migrate from 0.1.x to 0.2.x	130
9.5	Change log	131
10	Indices and tables	141
	Bibliography	143

Author

3. Wang

Source code <http://github.com/pyexcel/pyexcel.git>

Issues <http://github.com/pyexcel/pyexcel/issues>

License New BSD License

Development 0.6.0

Released 0.5.7

Generated Aug 08, 2018

Note: The documentation of pyexcel v0.6.0 is under review and rewrite. If you have missed some information, please read [v0.5.3](#)

CHAPTER 1

Introduction

pyexcel provides single application programming interface(API) to read, write and manipulate data in different excel file formats, in different storage media(disk, memory, database) and in different python data structures. Its loosely coupled architecture makes it extremely extensible.

The idea originated from the common usability problem: when an excel file driven web application is delivered for non-developer users (ie: team assistant, human resource administrator etc). The fact is that not everyone knows (or cares) about the differences between various excel formats: csv, xls, xlsx are all the same to them. Instead of training those users about file formats, this library helps web developers to handle most of the excel file formats by providing a common programming interface. To add a specific excel file format type to you application, all you need is to install an extra pyexcel plugin. Hence no code changes to your application and no issues with excel file formats any more. Looking at the community, this library and its associated ones try to become a small and easy to install alternative to Pandas.

Installation

You can install pyexcel via pip:

```
$ pip install pyexcel
```

or clone it and install it:

```
$ git clone https://github.com/pyexcel/pyexcel.git
$ cd pyexcel
$ python setup.py install
```

For individual excel file formats, please install them as you wish:

Table 1: A list of file formats supported by external plugins

Package name	Supported file formats	Dependencies	Python versions
pyexcel-io	csv, csvz [#f1]_, tsv, tsvz [#f2]_		2.6, 2.7, 3.3, 3.4, 3.5, 3.6 pypy
pyexcel-xls	xls, xlsx(read only), xlsm(read only)	xlrd, xlwt	same as above
pyexcel-xlsx	xlsx	openpyxl	same as above
pyexcel-ods3	ods	pyexcel-ezodf, lxml	2.6, 2.7, 3.3, 3.4 3.5, 3.6
pyexcel-ods	ods	odfpy	same as above

Table 2: Dedicated file reader and writers

Package name	Supported file formats	Dependencies	Python versions
pyexcel-xlsxw	xlsx(write only)	XlsxWriter	Python 2 and 3
pyexcel-xlsxr	xlsx(read only)	lxml	same as above
pyexcel-odsr	read only for ods, fods	lxml	same as above
pyexcel-htmlr	html(read only)	lxml,html5lib	same as above

Table 3: Other data renderers

Package name	Supported file formats	Dependencies	Python versions
pyexcel-text	write only:rst, mediawiki, html, latex, grid, pipe, orgtbl, plain simple read only: ndjson r/w: json	tabulate	2.6, 2.7, 3.3, 3.4 3.5, 3.6, pypy
pyexcel-handsontable	handsontable in html	handsonstable	same as above
pyexcel-pygal	svg chart	pygal	2.7, 3.3, 3.4, 3.5 3.6, pypy
pyexcel-sortable	sortable table in html	csvtotable	same as above
pyexcel-gantt	gantt chart in html	frappe-gantt	except pypy, same as above

In order to manage the list of plugins installed, you need to use pip to add or remove a plugin. When you use virtualenv, you can have different plugins per virtual environment. In the situation where you have multiple plugins that does the same thing in your environment, you need to tell pyexcel which plugin to use per function call. For example, pyexcel-ods and pyexcel-odsr, and you want to get_array to use pyexcel-odsr. You need to append get_array(..., library='pyexcel-odsr').

For compatibility tables of pyexcel-io plugins, please click [here](#)

Table 4: Plugin compatibility table

pyexcel	pyexcel-io	pyexcel-text	pyexcel-handsontable	pyexcel-pygal	pyexcel-gantt
0.6.0+	0.4.0+	0.2.6+	0.0.1	0.0.1	0.0.1
0.5.0+	0.4.0+	0.2.6+	0.0.1	0.0.1	0.0.1
0.4.0+	0.3.0+	0.2.5			

Table 5: a list of support file formats

file format	definition
csv	comma separated values
tsv	tab separated values
csvz	a zip file that contains one or many csv files
tsvz	a zip file that contains one or many tsv files
xls	a spreadsheet file format created by MS-Excel 97-2003 [#f1]
xlsx	MS-Excel Extensions to the Office Open XML SpreadsheetML File Format. [#f2]
xlsm	an MS-Excel Macro-Enabled Workbook file
ods	open document spreadsheet
fods	flat open document spreadsheet
json	java script object notation
html	html table of the data structure
simple	simple presentation
rst	rStructured Text presentation of the data
mediawiki	media wiki table

Suppose you want to process the following excel data :

Here are the example usages:

```
>>> import pyexcel as pe
>>> records = pe.iget_records(file_name="your_file.xls")
>>> for record in records:
...     print("%s is aged at %d" % (record['Name'], record['Age']))
Adam is aged at 28
Beatrice is aged at 29
Ceri is aged at 30
Dean is aged at 26
>>> pe.free_resources()
```


4.1 One liners

This section shows you how to get data from your excel files and how to export data to excel files in **one line**

4.1.1 One liner to get data from the excel files

Get a list of dictionaries

Suppose you want to process the following coffee data (data source [coffee chart](#) on the center for science in the public interest):

Let's get a list of dictionary out from the xls file:

```
>>> records = p.get_records(file_name="your_file.xls")
```

And let's check what do we have:

```
>>> for record in records:
...     print("%s of %s has %s mg" % (
...         record['Serving Size'],
...         record['Coffees'],
...         record['Caffeine (mg)']))
venti(20 oz) of Starbucks Coffee Blonde Roast has 475 mg
large(20 oz.) of Dunkin' Donuts Coffee with Turbo Shot has 398 mg
grande(16 oz.) of Starbucks Coffee Pike Place Roast has 310 mg
regular(16 oz.) of Panera Coffee Light Roast has 300 mg
```

Get two dimensional array

Instead, what if you have to use `pyexcel.get_array()` to do the same:

```
>>> for row in p.get_array(file_name="your_file.xls", start_row=1):
...     print("%s of %s has %s mg" % (
...         row[1],
...         row[0],
...         row[2]))
venti(20 oz) of Starbucks Coffee Blonde Roast has 475 mg
large(20 oz.) of Dunkin' Donuts Coffee with Turbo Shot has 398 mg
grande(16 oz.) of Starbucks Coffee Pike Place Roast has 310 mg
regular(16 oz.) of Panera Coffee Light Roast has 300 mg
```

where *start_row* skips the header row.

Get a dictionary

You can get a dictionary too:

Now let's get a dictionary out from the spreadsheet:

```
>>> my_dict = p.get_dict(file_name="your_file.xls", name_columns_by_row=0)
```

And check what do we have:

```
>>> from pyexcel._compact import OrderedDict
>>> isinstance(my_dict, OrderedDict)
True
>>> for key, values in my_dict.items():
...     print(key + " : " + ','.join([str(item) for item in values]))
Coffees : Starbucks Coffee Blonde Roast,Dunkin' Donuts Coffee with Turbo Shot,
↵Starbucks Coffee Pike Place Roast,Panera Coffee Light Roast
Serving Size : venti(20 oz),large(20 oz.),grande(16 oz.),regular(16 oz.)
Caffeine (mg) : 475,398,310,300
```

Please note that *my_dict* is an *OrderedDict*.

Get a dictionary of two dimensional array

Suppose you have a multiple sheet book as the following:

Here is the code to obtain those sheets as a single dictionary:

```
>>> book_dict = p.get_book_dict(file_name="book.xls")
```

And check::

```
>>> isinstance(book_dict, OrderedDict)
True
>>> import json
>>> for key, item in book_dict.items():
...     print(json.dumps({key: item}))
{"Sheet 1": [[1, 2, 3], [4, 5, 6], [7, 8, 9]]}
{"Sheet 2": [{"X", "Y", "Z"}, [1, 2, 3], [4, 5, 6]]}
{"Sheet 3": [{"O", "P", "Q"}, [3, 2, 1], [4, 3, 2]]}
```

4.1.2 Data export in one line

Export an array

Suppose you have the following array:

```
>>> data = [[1, 2, 3], [4, 5, 6], [7, 8, 9]]
```

And here is the code to save it as an excel file

```
>>> p.save_as(array=data, dest_file_name="example.xls")
```

Let's verify it:

```
>>> p.get_sheet(file_name="example.xls")
pyexcel_sheet1:
+---+---+---+
| 1 | 2 | 3 |
+---+---+---+
| 4 | 5 | 6 |
+---+---+---+
| 7 | 8 | 9 |
+---+---+---+
```

And here is the code to save it as a csv file

```
>>> p.save_as(array=data,
...           dest_file_name="example.csv",
...           dest_delimiter=',')
```

Let's verify it:

```
>>> with open("example.csv") as f:
...     for line in f.readlines():
...         print(line.rstrip())
...
1:2:3
4:5:6
7:8:9
```

Export a list of dictionaries

```
>>> records = [
...     {"year": 1903, "country": "Germany", "speed": "206.7km/h"},
...     {"year": 1964, "country": "Japan", "speed": "210km/h"},
...     {"year": 2008, "country": "China", "speed": "350km/h"}
... ]
>>> p.save_as(records=records, dest_file_name='high_speed_rail.xls')
```

Export a dictionary of single key value pair

```
>>> henley_on_thames_facts = {
...     "area": "5.58 square meters",
```

(continues on next page)

(continued from previous page)

```
...     "population": "11,619",
...     "civil parish": "Henley-on-Thames",
...     "latitude": "51.536",
...     "longitude": "-0.898"
... }
>>> p.save_as(adict=henley_on_thames_facts, dest_file_name='henley.xlsx')
```

Export a dictionary of single dimensional array

```
>>> ccs_insights = {
...     "year": ["2017", "2018", "2019", "2020", "2021"],
...     "smart phones": [1.53, 1.64, 1.74, 1.82, 1.90],
...     "feature phones": [0.46, 0.38, 0.30, 0.23, 0.17]
... }
>>> p.save_as(adict=ccs_insights, dest_file_name='ccs.csv')
```

Export a dictionary of two dimensional array as a book

Suppose you want to save the below dictionary to an excel file

```
>>> a_dictionary_of_two_dimensional_arrays = {
...     'Sheet 1':
...     [
...         [1.0, 2.0, 3.0],
...         [4.0, 5.0, 6.0],
...         [7.0, 8.0, 9.0]
...     ],
...     'Sheet 2':
...     [
...         ['X', 'Y', 'Z'],
...         [1.0, 2.0, 3.0],
...         [4.0, 5.0, 6.0]
...     ],
...     'Sheet 3':
...     [
...         ['O', 'P', 'Q'],
...         [3.0, 2.0, 1.0],
...         [4.0, 3.0, 2.0]
...     ]
... }
```

Here is the code:

```
>>> p.save_book_as(
...     bookdict=a_dictionary_of_two_dimensional_arrays,
...     dest_file_name="book.xls"
... )
```

If you want to preserve the order of sheets in your dictionary, you have to pass on an ordered dictionary to the function itself. For example:

```
>>> data = OrderedDict()
>>> data.update({"Sheet 2": a_dictionary_of_two_dimensional_arrays['Sheet 2']})
```

(continues on next page)

(continued from previous page)

```
>>> data.update({"Sheet 1": a_dictionary_of_two_dimensional_arrays['Sheet 1']})
>>> data.update({"Sheet 3": a_dictionary_of_two_dimensional_arrays['Sheet 3']})
>>> p.save_book_as(bookdict=data, dest_file_name="book.xls")
```

Let's verify its order:

```
>>> book_dict = p.get_book_dict(file_name="book.xls")
>>> for key, item in book_dict.items():
...     print(json.dumps({key: item}))
{"Sheet 2": [{"X", "Y", "Z"}, [1, 2, 3], [4, 5, 6]]}
{"Sheet 1": [[1, 2, 3], [4, 5, 6], [7, 8, 9]]}
{"Sheet 3": [{"O", "P", "Q"}, [3, 2, 1], [4, 3, 2]]}
```

Please notice that "Sheet 2" is the first item in the *book_dict*, meaning the order of sheets are preserved.

4.1.3 File format transcoding on one line

Note: Please note that the following file transcoding could be with zero line. Please install pyexcel-cli and you will do the transcode in one command. No need to open your editor, save the problem, then python run.

The following code does a simple file format transcoding from xls to csv:

```
>>> p.save_as(file_name="birth.xls", dest_file_name="birth.csv")
```

Again it is really simple. Let's verify what we have gotten:

```
>>> sheet = p.get_sheet(file_name="birth.csv")
>>> sheet
birth.csv:
+-----+-----+-----+
| name | weight | birth |
+-----+-----+-----+
| Adam | 3.4 | 03/02/15 |
+-----+-----+-----+
| Smith | 4.2 | 12/11/14 |
+-----+-----+-----+
```

Note: Please note that csv(comma separate value) file is pure text file. Formula, charts, images and formatting in xls file will disappear no matter which transcoding tool you use. Hence, pyexcel is a quick alternative for this transcoding job.

Let use previous example and save it as xlsx instead

```
>>> p.save_as(file_name="birth.xls",
...           dest_file_name="birth.xlsx") # change the file extension
```

Again let's verify what we have gotten:

```
>>> sheet = p.get_sheet(file_name="birth.xlsx")
>>> sheet
pyexcel_sheet1:
```

(continues on next page)

(continued from previous page)

```

+-----+-----+-----+
| name  | weight | birth  |
+-----+-----+-----+
| Adam  | 3.4    | 03/02/15 |
+-----+-----+-----+
| Smith | 4.2    | 12/11/14 |
+-----+-----+-----+

```

4.1.4 Excel book merge and split operation in one line

Merge all excel files in directory into a book where each file become a sheet

The following code will merge every excel files into one file, say “output.xls”:

```

from pyexcel.cookbook import merge_all_to_a_book
import glob

merge_all_to_a_book(glob.glob("your_csv_directory/*.csv"), "output.xls")

```

You can mix and match with other excel formats: xls, xlsx and ods. For example, if you are sure you have only xls, xlsx, ods and csv files in *your_excel_file_directory*, you can do the following:

```

from pyexcel.cookbook import merge_all_to_a_book
import glob

merge_all_to_a_book(glob.glob("your_excel_file_directory/*.xls"), "output.xls")

```

Split a book into single sheet files

Suppose you have many sheets in a work book and you would like to separate each into a single sheet excel file. You can easily do this:

```

>>> from pyexcel.cookbook import split_a_book
>>> split_a_book("megabook.xls", "output.xls")
>>> import glob
>>> outputfiles = glob.glob("*_output.xls")
>>> for file in sorted(outputfiles):
...     print(file)
...
Sheet 1_output.xls
Sheet 2_output.xls
Sheet 3_output.xls

```

for the output file, you can specify any of the supported formats

Extract just one sheet from a book

Suppose you just want to extract one sheet from many sheets that exists in a work book and you would like to separate it into a single sheet excel file. You can easily do this:

```
>>> from pyexcel.cookbook import extract_a_sheet_from_a_book
>>> extract_a_sheet_from_a_book("megabook.xls", "Sheet 1", "output.xls")
>>> if os.path.exists("Sheet 1_output.xls"):
...     print("Sheet 1_output.xls exists")
...
Sheet 1_output.xls exists
```

for the output file, you can specify any of the supported formats

4.2 Stream APIs for big file : A set of two liners

This section shows you how to get data from your **BIG** excel files and how to export data to excel files in **two lines** at most.

4.2.1 Two liners for get data from big excel files

Get a list of dictionaries

Suppose you want to process the following coffee data:

Let's get a list of dictionary out from the xls file:

```
>>> records = p.get_records(file_name="your_file.xls")
```

And let's check what do we have:

```
>>> for record in records:
...     print("%s of %s has %s mg" % (
...         record['Serving Size'],
...         record['Coffees'],
...         record['Caffeine (mg)']))
venti(20 oz) of Starbucks Coffee Blonde Roast has 475 mg
large(20 oz.) of Dunkin' Donuts Coffee with Turbo Shot has 398 mg
grande(16 oz.) of Starbucks Coffee Pike Place Roast has 310 mg
regular(16 oz.) of Panera Coffee Light Roast has 300 mg
```

Please do not forgot the second line:

```
>>> p.free_resources()
```

Get two dimensional array

Instead, what if you have to use `pyexcel.get_array()` to do the same:

```
>>> for row in p.get_array(file_name="your_file.xls", start_row=1):
...     print("%s of %s has %s mg" % (
...         row[1],
...         row[0],
...         row[2]))
venti(20 oz) of Starbucks Coffee Blonde Roast has 475 mg
large(20 oz.) of Dunkin' Donuts Coffee with Turbo Shot has 398 mg
grande(16 oz.) of Starbucks Coffee Pike Place Roast has 310 mg
regular(16 oz.) of Panera Coffee Light Roast has 300 mg
```

Again, do not forgot the second line:

```
>>> p.free_resources()
```

where *start_row* skips the header row.

4.2.2 Data export in one liners

Export an array

Suppose you have the following array:

```
>>> data = [[1, 2, 3], [4, 5, 6], [7, 8, 9]]
```

And here is the code to save it as an excel file

```
>>> p.isave_as(array=data, dest_file_name="example.xls")
```

But the following line is not required because the data source are not file sources:

```
>>> # p.free_resources()
```

Let's verify it:

```
>>> p.get_sheet(file_name="example.xls")
pyexcel_sheet1:
+---+---+---+
| 1 | 2 | 3 |
+---+---+---+
| 4 | 5 | 6 |
+---+---+---+
| 7 | 8 | 9 |
+---+---+---+
```

And here is the code to save it as a csv file

```
>>> p.isave_as(array=data,
...           dest_file_name="example.csv",
...           dest_delimiter=':')
```

Let's verify it:

```
>>> with open("example.csv") as f:
...     for line in f.readlines():
...         print(line.rstrip())
...
1:2:3
4:5:6
7:8:9
```

Export a list of dictionaries

```
>>> records = [
...     {"year": 1903, "country": "Germany", "speed": "206.7km/h"},
...     {"year": 1964, "country": "Japan", "speed": "210km/h"},
...     {"year": 2008, "country": "China", "speed": "350km/h"}
... ]
>>> p.isave_as(records=records, dest_file_name='high_speed_rail.xls')
```

Export a dictionary of single key value pair

```
>>> henley_on_thames_facts = {
...     "area": "5.58 square meters",
...     "population": "11,619",
...     "civil parish": "Henley-on-Thames",
...     "latitude": "51.536",
...     "longitude": "-0.898"
... }
>>> p.isave_as(adict=henley_on_thames_facts, dest_file_name='henley.xlsx')
```

Export a dictionary of single dimensional array

```
>>> ccs_insights = {
...     "year": ["2017", "2018", "2019", "2020", "2021"],
...     "smart phones": [1.53, 1.64, 1.74, 1.82, 1.90],
...     "feature phones": [0.46, 0.38, 0.30, 0.23, 0.17]
... }
>>> p.isave_as(adict=ccs_insights, dest_file_name='ccs.csv')
>>> p.free_resources()
```

Export a dictionary of two dimensional array as a book

Suppose you want to save the below dictionary to an excel file

```
>>> a_dictionary_of_two_dimensional_arrays = {
...     'Sheet 1':
...     [
...         [1.0, 2.0, 3.0],
...         [4.0, 5.0, 6.0],
...         [7.0, 8.0, 9.0]
...     ],
...     'Sheet 2':
...     [
...         ['X', 'Y', 'Z'],
...         [1.0, 2.0, 3.0],
...         [4.0, 5.0, 6.0]
...     ],
...     'Sheet 3':
...     [
...         ['O', 'P', 'Q'],
...         [3.0, 2.0, 1.0],
...         [4.0, 3.0, 2.0]
...     ]
... }
```

Here is the code:

```
>>> p.isave_book_as(  
...     bookdict=a_dictionary_of_two_dimensional_arrays,  
...     dest_file_name="book.xls"  
... )
```

If you want to preserve the order of sheets in your dictionary, you have to pass on an ordered dictionary to the function itself. For example:

```
>>> from pyexcel._compact import OrderedDict  
>>> data = OrderedDict()  
>>> data.update({"Sheet 2": a_dictionary_of_two_dimensional_arrays['Sheet 2']})  
>>> data.update({"Sheet 1": a_dictionary_of_two_dimensional_arrays['Sheet 1']})  
>>> data.update({"Sheet 3": a_dictionary_of_two_dimensional_arrays['Sheet 3']})  
>>> p.isave_book_as(bookdict=data, dest_file_name="book.xls")  
>>> p.free_resources()
```

Let's verify its order:

```
>>> import json  
>>> book_dict = p.get_book_dict(file_name="book.xls")  
>>> for key, item in book_dict.items():  
...     print(json.dumps({key: item}))  
{"Sheet 2": [{"X", "Y", "Z"}, [1, 2, 3], [4, 5, 6]]}  
{"Sheet 1": [[1, 2, 3], [4, 5, 6], [7, 8, 9]]}  
{"Sheet 3": [{"O", "P", "Q"}, [3, 2, 1], [4, 3, 2]]}
```

Please notice that “Sheet 2” is the first item in the *book_dict*, meaning the order of sheets are preserved.

4.2.3 File format transcoding on one line

Note: Please note that the following file transcoding could be with zero line. Please install pyexcel-cli and you will do the transcode in one command. No need to open your editor, save the problem, then python run.

The following code does a simple file format transcoding from xls to csv:

```
>>> import pyexcel  
>>> p.save_as(file_name="birth.xls", dest_file_name="birth.csv")
```

Again it is really simple. Let's verify what we have gotten:

```
>>> sheet = p.get_sheet(file_name="birth.csv")  
>>> sheet  
birth.csv:  
+-----+-----+-----+  
| name  | weight | birth   |  
+-----+-----+-----+  
| Adam  | 3.4    | 03/02/15 |  
+-----+-----+-----+  
| Smith | 4.2    | 12/11/14 |  
+-----+-----+-----+
```

Note: Please note that csv(comma separate value) file is pure text file. Formula, charts, images and formatting in xls

file will disappear no matter which transcoding tool you use. Hence, pyexcel is a quick alternative for this transcoding job.

Let use previous example and save it as xlsx instead

```
>>> import pyexcel
>>> p.isave_as(file_name="birth.xls",
...           dest_file_name="birth.xlsx") # change the file extension
```

Again let's verify what we have gotten:

```
>>> sheet = p.get_sheet(file_name="birth.xlsx")
>>> sheet
pyexcel_sheet1:
+-----+-----+-----+
| name  | weight | birth  |
+-----+-----+-----+
| Adam  | 3.4    | 03/02/15 |
+-----+-----+-----+
| Smith | 4.2    | 12/11/14 |
+-----+-----+-----+
```

4.3 Pyexcel-io Plugin guide

There has been a lot of plugins for reading and writing a file types. Here is a guide for you to choose them.

Table 1: A list of file formats supported by external plugins

Package name	Supported file formats	Dependencies	Python versions
pyexcel-io	csv, csvz ¹ , tsv, tsvz ²		2.6, 2.7, 3.3, 3.4, 3.5, 3.6 pypy
pyexcel-xls	xls, xlsx(read only), xlsxm(read only)	xlrd, xlwt	same as above
pyexcel-xlsx	xlsx	openpyxl	same as above
pyexcel-ods3	ods	pyexcel-ezodf, lxml	2.6, 2.7, 3.3, 3.4 3.5, 3.6
pyexcel-ods	ods	odfpy	same as above

Table 2: Dedicated file reader and writers

Package name	Supported file formats	Dependencies	Python versions
pyexcel-xlsxw	xlsx(write only)	XlsxWriter	Python 2 and 3
pyexcel-xlsxr	xlsx(read only)	lxml	same as above
pyexcel-ods3r	read only for ods, fods	lxml	same as above
pyexcel-htmlr	html(read only)	lxml,html5lib	same as above

In order to manage the list of plugins installed, you need to use pip to add or remove a plugin. When you use virtualenv, you can have different plugins per virtual environment. In the situation where you have multiple plugins that does the same thing in your environment, you need to tell pyexcel which plugin to use per function call. For example, pyexcel-ods and pyexcel-ods3r, and you want to get_array to use pyexcel-ods3r. You need to append get_array(..., library='pyexcel-ods3r').

¹ zipped csv file

² zipped tsv file

4.3.1 Read and write with performance

Partial reading

`csv`, `tsv` by `pyexcel-io`, `ods` by `pyexcel-odsr`, `html` by `pyexcel-htmlr` are implemented in partial read mode. If you only need first half of the file, the second half of the data will not be read into the memory if and only if you use `igetters(iget_records, iget_array)` and `isaveer(isave_as and isave_book_as)`.

Read on demand

`xls` by `pyexcel-xls` promised to read sheet on demand. It means if you need only one sheet from a multi-sheet book, the rest of the sheets in the book will not be read.

Streaming write

`csv`, `tsv` by `'pyexce-io'` can do streaming write.

Write with constant memory

`xlsx` by `pyexcel-xlsxw` can write big data with constant memory consumption.

4.4 For web developer

The following libraries are written to facilitate the daily import and export of excel data.

framework	plugin/middleware/extension
Flask	Flask-Excel
Django	django-excel
Pyramid	pyramid-excel

And you may make your own by using `pyexcel-webio`

4.4.1 Read any supported excel and respond its content in json

You can find a real world example in `examples/memoryfile/` directory: `pyexcel_server.py`. Here is the example snippet

```
1 def upload():
2     if request.method == 'POST' and 'excel' in request.files:
3         # handle file upload
4         filename = request.files['excel'].filename
5         extension = filename.split(".")[1]
6         # Obtain the file extension and content
7         # pass a tuple instead of a file name
8         content = request.files['excel'].read()
9         if sys.version_info[0] > 2:
10            # in order to support python 3
11            # have to decode bytes to str
12            content = content.decode('utf-8')
13            sheet = pe.get_sheet(file_type=extension, file_content=content)
```

(continues on next page)

(continued from previous page)

```
14     # then use it as usual
15     sheet.name_columns_by_row(0)
16     # respond with a json
17     return jsonify({"result": sheet.dict})
18     return render_template('upload.html')
```

`request.files['excel']` in line 4 holds the file object. line 5 finds out the file extension. line 13 obtains a sheet instance. line 15 uses the first row as data header. line 17 sends the json representation of the excel file back to client browser.

4.4.2 Write to memory and respond to download

```
1 data = [
2     [...],
3     ...
4 ]
5
6 @app.route('/download')
7 def download():
8     sheet = pe.Sheet(data)
9     output = make_response(sheet.csv)
10    output.headers["Content-Disposition"] = "attachment; filename=export.csv"
11    output.headers["Content-type"] = "text/csv"
12    return output
```

`make_response` is a Flask utility to make a memory content as http response.

Note: You can find the corresponding source code at [examples/memoryfile](#)

4.5 Pyexcel data renderers

There exist a few data renderers for pyexcel data. This chapter will walk you through them.

4.5.1 View pyexcel data in ndjson and other formats

With `pyexcel-text`, you can get pyexcel data in newline delimited json, normal json and other formats.

4.5.2 View the pyexcel data in a browser

You can use `pyexcel-handsontable` to render your data.

4.5.3 Include excel data in your python documentation

`sphinxcontrib-excel` help you present your excel data in various formats inside your sphinx documentation.

4.5.4 Draw charts from your excel data

`pyexcel-pygal` helps you with all charting options and give you charts in svg format.

`pyexcel-echarts` draws 2D, 3D, geo charts from pyexcel data and has awesome animations too, but it is under development.

`pyexcel-matplotlib` helps you with scientific charts and is under development.

4.5.5 Gantt chart visualization for your excel data

`'pyexcel-gantt'` is a specialist renderer for gantt chart.

4.6 Sheet

4.6.1 Random access

To randomly access a cell of `Sheet` instance, two syntax are available:

```
sheet[row, column]
```

or:

```
sheet['A1']
```

The former syntax is handy when you know the row and column numbers. The latter syntax is introduced to help you convert the excel column header such as "AX" to integer numbers.

Suppose you have the following data, you can get value 5 by `reader[2, 2]`.

Here is the example code showing how you can randomly access a cell:

```
>>> sheet = pyexcel.get_sheet(file_name="example.xls")
>>> sheet.content
+-----+---+---+---+
| Example | X | Y | Z |
+-----+---+---+---+
| a       | 1 | 2 | 3 |
+-----+---+---+---+
| b       | 4 | 5 | 6 |
+-----+---+---+---+
| c       | 7 | 8 | 9 |
+-----+---+---+---+
>>> print(sheet[2, 2])
5
>>> print(sheet["C3"])
5
>>> sheet[3, 3] = 10
>>> print(sheet[3, 3])
10
```

Note: In order to set a value to a cell, please use `sheet[row_index, column_index] = new_value`

Random access to rows and columns

Continue with previous excel file, you can access row and column separately:

```
>>> sheet.row[1]
['a', 1, 2, 3]
>>> sheet.column[2]
['Y', 2, 5, 8]
```

Use custom names instead of index Alternatively, it is possible to use the first row to refer to each columns:

```
>>> sheet.name_columns_by_row(0)
>>> print(sheet[1, "Y"])
5
>>> sheet[1, "Y"] = 100
>>> print(sheet[1, "Y"])
100
```

You have noticed the row index has been changed. It is because first row is taken as the column names, hence all rows after the first row are shifted. Now accessing the columns are changed too:

```
>>> sheet.column['Y']
[2, 100, 8]
```

Hence access the same cell, this statement also works:

```
>>> sheet.column['Y'][1]
100
```

Further more, it is possible to use first column to refer to each rows:

```
>>> sheet.name_rows_by_column(0)
```

To access the same cell, we can use this line:

```
>>> sheet.row["b"][1]
100
```

For the same reason, the row index has been reduced by 1. Since we have named columns and rows, it is possible to access the same cell like this:

```
>>> print(sheet["b", "Y"])
100
>>> sheet["b", "Y"] = 200
>>> print(sheet["b", "Y"])
200
```

Play with data

Suppose you have the following data in any of the supported excel formats again:

```
>>> sheet = pyexcel.get_sheet(file_name="example_series.xls",
...     name_columns_by_row=0)
```

You can get headers:

```
>>> print(list(sheet.colnames))
['Column 1', 'Column 2', 'Column 3']
```

You can use a utility function to get all in a dictionary:

```
>>> sheet.to_dict()
OrderedDict([('Column 1', [1, 4, 7]), ('Column 2', [2, 5, 8]), ('Column 3', [3, 6, 9])])
```

Maybe you want to get only the data without the column headers. You can call `rows()` instead:

```
>>> list(sheet.rows())
[[1, 2, 3], [4, 5, 6], [7, 8, 9]]
```

You can get data from the bottom to the top one by calling `rrows()`:

```
>>> list(sheet.rrows())
[[7, 8, 9], [4, 5, 6], [1, 2, 3]]
```

You might want the data arranged vertically. You can call `columns()`:

```
>>> list(sheet.columns())
[[1, 4, 7], [2, 5, 8], [3, 6, 9]]
```

You can get columns in reverse sequence as well by calling `rcolumns()`:

```
>>> list(sheet.rcolumns())
[[3, 6, 9], [2, 5, 8], [1, 4, 7]]
```

Do you want to flatten the data? You can get the content in one dimensional array. If you are interested in playing with one dimensional enumeration, you can check out these functions `enumerate()`, `reverse()`, `vertical()`, and `rvertical()`:

```
>>> list(sheet.enumerate())
[1, 2, 3, 4, 5, 6, 7, 8, 9]
>>> list(sheet.reverse())
[9, 8, 7, 6, 5, 4, 3, 2, 1]
>>> list(sheet.vertical())
[1, 4, 7, 2, 5, 8, 3, 6, 9]
>>> list(sheet.rvertical())
[9, 6, 3, 8, 5, 2, 7, 4, 1]
```

attributes

Attributes:

```
>>> import pyexcel
>>> content = "1,2,3\n3,4,5"
>>> sheet = pyexcel.get_sheet(file_type="csv", file_content=content)
>>> sheet.tsv
'1\t2\t3\r\n3\t4\t5\r\n'
>>> print(sheet.simple)
csv:
- - -
1 2 3
3 4 5
- - -
```

What's more, you could as well set value to an attribute, for example::

```
>>> import pyexcel
>>> content = "1,2,3\n3,4,5"
```

(continues on next page)

(continued from previous page)

```
>>> sheet = pyexcel.Sheet()
>>> sheet.csv = content
>>> sheet.array
[[1, 2, 3], [3, 4, 5]]
```

You can get the direct access to underneath stream object. In some situation, it is desired:

```
>>> stream = sheet.stream.tsv
```

The returned stream object has tsv formatted content for reading.

What you could further do is to set a memory stream of any supported file format to a sheet. For example:

```
>>> another_sheet = pyexcel.Sheet()
>>> another_sheet.xls = sheet.xls
>>> another_sheet.content
+---+---+---+
| 1 | 2 | 3 |
+---+---+---+
| 3 | 4 | 5 |
+---+---+---+
```

Yet, it is possible assign a absolute url to an online excel file to an instance of `pyexcel.Sheet`.

custom attributes

You can pass on source specific parameters to getter and setter functions.

```
>>> content = "1-2-3\n3-4-5"
>>> sheet = pyexcel.Sheet()
>>> sheet.set_csv(content, delimiter="-")
>>> sheet.csv
'1,2,3\r\n3,4,5\r\n'
>>> sheet.get_csv(delimiter="|")
'1|2|3\r\n3|4|5\r\n'
```

4.6.2 Data manipulation

The data in a sheet is represented by `Sheet` which maintains the data as a list of lists. You can regard `Sheet` as a two dimensional array with additional iterators. Random access to individual column and row is exposed by `Column` and `Row`

Column manipulation

Suppose have one data file as the following:

```
>>> sheet = pyexcel.get_sheet(file_name="example.xls", name_columns_by_row=0)
>>> sheet
pyexcel sheet:
+-----+-----+-----+
| Column 1 | Column 2 | Column 3 |
+=====+=====+=====+
| 1         | 4         | 7         |
+-----+-----+-----+
```

(continues on next page)

(continued from previous page)

2	5	8	
+-----+	+-----+	+-----+	+-----+
3	6	9	
+-----+	+-----+	+-----+	+-----+

And you want to update Column 2 with these data: [11, 12, 13]

```
>>> sheet.column["Column 2"] = [11, 12, 13]
>>> sheet.column[1]
[11, 12, 13]
>>> sheet
pyexcel sheet:
+-----+-----+-----+
| Column 1 | Column 2 | Column 3 |
+-----+-----+-----+
| 1        | 11       | 7        |
+-----+-----+-----+
| 2        | 12       | 8        |
+-----+-----+-----+
| 3        | 13       | 9        |
+-----+-----+-----+
```

Remove one column of a data file

If you want to remove Column 2, you can just call:

```
>>> del sheet.column["Column 2"]
>>> sheet.column["Column 3"]
[7, 8, 9]
```

The sheet content will become:

```
>>> sheet
pyexcel sheet:
+-----+-----+
| Column 1 | Column 3 |
+-----+-----+
| 1        | 7        |
+-----+-----+
| 2        | 8        |
+-----+-----+
| 3        | 9        |
+-----+-----+
```

Append more columns to a data file

Continue from previous example. Suppose you want add two more columns to the data file

Column 4	Column 5
10	13
11	14
12	15

Here is the example code to append two extra columns:

```
>>> extra_data = [
...     ["Column 4", "Column 5"],
...     [10, 13],
...     [11, 14],
...     [12, 15]
... ]
>>> sheet2 = pyexcel.Sheet(extra_data)
>>> sheet.column += sheet2
>>> sheet.column["Column 4"]
[10, 11, 12]
>>> sheet.column["Column 5"]
[13, 14, 15]
```

Here is what you will get:

```
>>> sheet
pyexcel sheet:
+-----+-----+-----+-----+
| Column 1 | Column 3 | Column 4 | Column 5 |
+-----+-----+-----+-----+
| 1        | 7        | 10       | 13       |
+-----+-----+-----+-----+
| 2        | 8        | 11       | 14       |
+-----+-----+-----+-----+
| 3        | 9        | 12       | 15       |
+-----+-----+-----+-----+
```

Cherry pick some columns to be removed

Suppose you have the following data:

```
>>> data = [
...     ['a', 'b', 'c', 'd', 'e', 'f', 'g', 'h'],
...     [1, 2, 3, 4, 5, 6, 7, 9],
... ]
>>> sheet = pyexcel.Sheet(data, name_columns_by_row=0)
>>> sheet
pyexcel sheet:
+---+---+---+---+---+---+---+---+
| a | b | c | d | e | f | g | h |
+---+---+---+---+---+---+---+---+
| 1 | 2 | 3 | 4 | 5 | 6 | 7 | 9 |
+---+---+---+---+---+---+---+---+
```

And you want to remove columns named as 'a', 'c', 'e', 'h'. This is how you do it:

```
>>> del sheet.column['a', 'c', 'e', 'h']
>>> sheet
pyexcel sheet:
+---+---+---+---+
| b | d | f | g |
+---+---+---+---+
| 2 | 4 | 6 | 7 |
+---+---+---+---+
```

What if the headers are in a different row

Suppose you have the following data:

```
>>> sheet
pyexcel sheet:
+-----+-----+-----+
| 1      | 2      | 3      |
+-----+-----+-----+
| Column 1 | Column 2 | Column 3 |
+-----+-----+-----+
| 4      | 5      | 6      |
+-----+-----+-----+
```

The way to name your columns is to use index 1:

```
>>> sheet.name_columns_by_row(1)
```

Here is what you get:

```
>>> sheet
pyexcel sheet:
+-----+-----+-----+
| Column 1 | Column 2 | Column 3 |
+=====+=====+=====+
| 1      | 2      | 3      |
+-----+-----+-----+
| 4      | 5      | 6      |
+-----+-----+-----+
```

Row manipulation

Suppose you have the following data:

```
>>> sheet
pyexcel sheet:
+---+---+---+---+
| a | b | c | Row 1 |
+---+---+---+---+
| e | f | g | Row 2 |
+---+---+---+---+
| 1 | 2 | 3 | Row 3 |
+---+---+---+---+
```

You can name your rows by column index at 3:

```
>>> sheet.name_rows_by_column(3)
>>> sheet
pyexcel sheet:
+-----+-----+-----+
| Row 1 | a | b | c |
+-----+-----+-----+
| Row 2 | e | f | g |
+-----+-----+-----+
| Row 3 | 1 | 2 | 3 |
+-----+-----+-----+
```

Then you can access rows by its name:

```
>>> sheet.row["Row 1"]
['a', 'b', 'c']
```

4.6.3 Formatting

Previous section has assumed the data is in the format that you want. In reality, you have to manipulate the data types a bit to suit your needs. Hence, formatters comes into the scene. use `format()` to apply formatter immediately.

Note: `int`, `float` and `datetime` values are automatically detected in `csv` files since `pyexcel` version 0.2.2

Convert a column of numbers to strings

Suppose you have the following data:

```
>>> import pyexcel
>>> data = [
...     ["userid", "name"],
...     [10120, "Adam"],
...     [10121, "Bella"],
...     [10122, "Cedar"]
... ]
>>> sheet = pyexcel.Sheet(data)
>>> sheet.name_columns_by_row(0)
>>> sheet.column["userid"]
[10120, 10121, 10122]
```

As you can see, `userid` column is of `int` type. Next, let's convert the column to string format:

```
>>> sheet.column.format("userid", str)
>>> sheet.column["userid"]
['10120', '10121', '10122']
```

Cleanse the cells in a spread sheet

Sometimes, the data in a spreadsheet may have unwanted strings in all or some cells. Let's take an example. Suppose we have a spread sheet that contains all strings but it as random spaces before and after the text values. Some field had weird characters, such as “ ”:

```
>>> data = [
...     ["      Version", "      Comments", "      Author &nbsp;  "],
...     [" v0.0.1      ", " Release versions", "      &nbsp;  Eda"],
...     ["&nbsp;  &nbsp;  v0.0.2  ", "Useful updates &nbsp;   &nbsp;  ", " &nbsp;  Freud"]
... ]
>>> sheet = pyexcel.Sheet(data)
>>> sheet.content
+-----+-----+-----+
|      Version |      Comments      |      Author &nbsp;   |
+-----+-----+-----+
| v0.0.1      | Release versions   |      &nbsp;  Eda |
+-----+-----+-----+
```

(continues on next page)

(continued from previous page)

```
+-----+-----+-----+
| 7      | 8      | 9      |
+-----+-----+-----+
```

Filter out some data

You may want to filter odd rows and print them in an array of dictionaries:

```
>>> sheet.filter(row_indices=[0, 2])
>>> sheet.content
+-----+-----+-----+
| Column 1 | Column 2 | Column 3 |
+-----+-----+-----+
| 4      | 5      | 6      |
+-----+-----+-----+
```

Let's try to further filter out even columns:

```
>>> sheet.filter(column_indices=[1])
>>> sheet.content
+-----+-----+
| Column 1 | Column 3 |
+-----+-----+
| 4      | 6      |
+-----+-----+
```

Save the data

Let's save the previous filtered data:

```
>>> sheet.save_as("example_series_filter.xls")
```

When you open *example_series_filter.xls*, you will find these data

Column 1	Column 3
2	8

How to filter out empty rows in my sheet?

Suppose you have the following data in a sheet and you want to remove those rows with blanks:

```
>>> import pyexcel as pe
>>> sheet = pe.Sheet([[1,2,3],['',''],['',''],[1,2,3]])
```

You can use `pyexcel.filters.RowValueFilter`, which examines each row, return *True* if the row should be filtered out. So, let's define a filter function:

```
>>> def filter_row(row_index, row):
...     result = [element for element in row if element != '']
...     return len(result)==0
```

And then apply the filter on the sheet:

```
>>> del sheet.row[filter_row]
>>> sheet
pyexcel sheet:
+---+---+---+
| 1 | 2 | 3 |
+---+---+---+
| 1 | 2 | 3 |
+---+---+---+
```

4.7 Book

You access each cell via this syntax:

```
book[sheet_index][row, column]
```

or:

```
book["sheet_name"][row, column]
```

Suppose you have the following sheets:

And you can randomly access a cell in a sheet:

```
>>> book = pyexcel.get_book(file_name="example.xls")
>>> print(book["Sheet 1"][0,0])
1
>>> print(book[0][0,0]) # the same cell
1
```

Tip: With pyexcel, you can regard single sheet reader as an two dimensional array and multi-sheet excel book reader as a ordered dictionary of two dimensional arrays.

Write multiple sheet excel file

Suppose you have previous data as a dictionary and you want to save it as multiple sheet excel file:

```
>>> content = {
...     'Sheet 1':
...     [
...         [1.0, 2.0, 3.0],
...         [4.0, 5.0, 6.0],
...         [7.0, 8.0, 9.0]
...     ],
...     'Sheet 2':
...     [
...         ['X', 'Y', 'Z'],
...         [1.0, 2.0, 3.0],
...         [4.0, 5.0, 6.0]
...     ],
...     'Sheet 3':
...     [
...         ['O', 'P', 'Q'],
...         [3.0, 2.0, 1.0],
```

(continues on next page)

(continued from previous page)

```

...         [4.0, 3.0, 2.0]
...     ]
... }
>>> book = pyexcel.get_book(bookdict=content)
>>> book.save_as("output.xls")

```

You shall get a xls file

Read multiple sheet excel file

Let's read the previous file back:

```

>>> book = pyexcel.get_book(file_name="output.xls")
>>> sheets = book.to_dict()
>>> for name in sheets.keys():
...     print(name)
Sheet 1
Sheet 2
Sheet 3

```

4.7.1 Get content

```

>>> book_dict = {
...     'Sheet 2':
...     [
...         ['X', 'Y', 'Z'],
...         [1.0, 2.0, 3.0],
...         [4.0, 5.0, 6.0]
...     ],
...     'Sheet 3':
...     [
...         ['O', 'P', 'Q'],
...         [3.0, 2.0, 1.0],
...         [4.0, 3.0, 2.0]
...     ],
...     'Sheet 1':
...     [
...         [1.0, 2.0, 3.0],
...         [4.0, 5.0, 6.0],
...         [7.0, 8.0, 9.0]
...     ]
... }
>>> book = pyexcel.get_book(bookdict=book_dict)
>>> book
Sheet 1:
+-----+-----+-----+
| 1.0 | 2.0 | 3.0 |
+-----+-----+-----+
| 4.0 | 5.0 | 6.0 |
+-----+-----+-----+
| 7.0 | 8.0 | 9.0 |
+-----+-----+-----+
Sheet 2:
+-----+-----+-----+
| X   | Y   | Z   |

```

(continues on next page)

(continued from previous page)

```

+-----+-----+-----+
| 1.0 | 2.0 | 3.0 |
+-----+-----+-----+
| 4.0 | 5.0 | 6.0 |
+-----+-----+-----+
Sheet 3:
+-----+-----+-----+
| O   | P   | Q   |
+-----+-----+-----+
| 3.0 | 2.0 | 1.0 |
+-----+-----+-----+
| 4.0 | 3.0 | 2.0 |
+-----+-----+-----+
>>> print(book.rst)
Sheet 1:
= = =
1 2 3
4 5 6
7 8 9
= = =
Sheet 2:
=== === ===
X   Y   Z
1.0 2.0 3.0
4.0 5.0 6.0
=== === ===
Sheet 3:
=== === ===
O   P   Q
3.0 2.0 1.0
4.0 3.0 2.0
=== === ===

```

You can get the direct access to underneath stream object. In some situation, it is desired.

```
>>> stream = book.stream.plain
```

The returned stream object has the content formatted in plain format for further reading.

4.7.2 Set content

Surely, you could set content to an instance of `pyexcel.Book`.

```

>>> other_book = pyexcel.Book()
>>> other_book.bookdict = book_dict
>>> print(other_book.plain)
Sheet 1:
1 2 3
4 5 6
7 8 9
Sheet 2:
X   Y   Z
1.0 2.0 3.0
4.0 5.0 6.0
Sheet 3:

```

(continues on next page)

(continued from previous page)

O	P	Q
3.0	2.0	1.0
4.0	3.0	2.0

You can set via 'xls' attribute too.

```
>>> another_book = pyexcel.Book()
>>> another_book.xls = other_book.xls
>>> print(another_book.mediawiki)
Sheet 1:
{| class="wikitable" style="text-align: left;"
|+ <!-- caption -->
|-
| align="right"| 1 || align="right"| 2 || align="right"| 3
|-
| align="right"| 4 || align="right"| 5 || align="right"| 6
|-
| align="right"| 7 || align="right"| 8 || align="right"| 9
|}
Sheet 2:
{| class="wikitable" style="text-align: left;"
|+ <!-- caption -->
|-
| X || Y || Z
|-
| 1 || 2 || 3
|-
| 4 || 5 || 6
|}
Sheet 3:
{| class="wikitable" style="text-align: left;"
|+ <!-- caption -->
|-
| O || P || Q
|-
| 3 || 2 || 1
|-
| 4 || 3 || 2
|}
```

Access to individual sheets

You can access individual sheet of a book via attribute:

```
>>> book = pyexcel.get_book(file_name="book.xls")
>>> book.sheet3
sheet3:
+---+---+---+
| 1 | 2 | 3 |
+---+---+---+
| 4 | 5 | 6 |
+---+---+---+
| 7 | 8 | 9 |
+---+---+---+
```

or via array notations:

```
>>> book["sheet 1"] # there is a space in the sheet name
sheet 1:
+---+---+---+
| 1 | 2 | 3 |
+---+---+---+
| 1 | 2 | 3 |
+---+---+---+
| 4 | 5 | 6 |
+---+---+---+
```

Merge excel books

Suppose you have two excel books and each had three sheets. You can merge them and get a new book:

You also can merge individual sheets:

```
>>> book1 = pyexcel.get_book(file_name="book1.xls")
>>> book2 = pyexcel.get_book(file_name="book2.xlsx")
>>> merged_book = book1 + book2
>>> merged_book = book1["Sheet 1"] + book2["Sheet 2"]
>>> merged_book = book1["Sheet 1"] + book2
>>> merged_book = book1 + book2["Sheet 2"]
```

Manipulate individual sheets

4.7.3 merge sheets into a single sheet

Suppose you want to merge many csv files row by row into a new sheet.

```
>>> import glob
>>> merged = pyexcel.Sheet()
>>> for file in glob.glob("*.csv"):
...     merged.row += pyexcel.get_sheet(file_name=file)
>>> merged.save_as("merged.csv")
```

How do I read a book, process it and save to a new book

Yes, you can do that. The code looks like this:

```
import pyexcel

book = pyexcel.get_book(file_name="yourfile.xls")
for sheet in book:
    # do you processing with sheet
    # do filtering?
    pass
book.save_as("output.xls")
```

What would happen if I save a multi sheet book into "csv" file

Well, you will get one csv file per each sheet. Suppose you have these code:

```

>>> content = {
...     'Sheet 1':
...         [
...             [1.0, 2.0, 3.0],
...             [4.0, 5.0, 6.0],
...             [7.0, 8.0, 9.0]
...         ],
...     'Sheet 2':
...         [
...             ['X', 'Y', 'Z'],
...             [1.0, 2.0, 3.0],
...             [4.0, 5.0, 6.0]
...         ],
...     'Sheet 3':
...         [
...             ['O', 'P', 'Q'],
...             [3.0, 2.0, 1.0],
...             [4.0, 3.0, 2.0]
...         ]
...     }
>>> book = pyexcel.Book(content)
>>> book.save_as("myfile.csv")

```

You will end up with three csv files:

```

>>> import glob
>>> outputfiles = glob.glob("myfile_*.csv")
>>> for file in sorted(outputfiles):
...     print(file)
...
myfile__Sheet 1__0.csv
myfile__Sheet 2__1.csv
myfile__Sheet 3__2.csv

```

and their content is the value of the dictionary at the corresponding key

Alternatively, you could use `save_book_as()` function

```

>>> pyexcel.save_book_as(bookdict=content, dest_file_name="myfile.csv")

```

After I have saved my multiple sheet book in csv format, how do I get them back

First of all, you can read them back individual as csv file using `meth:~pyexcel.get_sheet` method. Secondly, the pyexcel can do the magic to load all of them back into a book. You will just need to provide the common name before the separator “_”:

```

>>> book2 = pyexcel.get_book(file_name="myfile.csv")
>>> book2
Sheet 1:
+-----+-----+-----+
| 1.0 | 2.0 | 3.0 |
+-----+-----+-----+
| 4.0 | 5.0 | 6.0 |
+-----+-----+-----+
| 7.0 | 8.0 | 9.0 |
+-----+-----+-----+

```

(continues on next page)

(continued from previous page)

```

Sheet 2:
+-----+-----+-----+
| X     | Y     | Z     |
+-----+-----+-----+
| 1.0   | 2.0   | 3.0   |
+-----+-----+-----+
| 4.0   | 5.0   | 6.0   |
+-----+-----+-----+
Sheet 3:
+-----+-----+-----+
| O     | P     | Q     |
+-----+-----+-----+
| 3.0   | 2.0   | 1.0   |
+-----+-----+-----+
| 4.0   | 3.0   | 2.0   |
+-----+-----+-----+

```

4.8 Working with databases

4.8.1 How to import an excel sheet to a database using SQLAlchemy

Note: You can find the complete code of this example in examples folder on github

Before going ahead, let's import the needed components and initialize sql engine and table base:

```

>>> import os
>>> import pyexcel as p
>>> from sqlalchemy import create_engine
>>> from sqlalchemy.ext.declarative import declarative_base
>>> from sqlalchemy import Column, Integer, String, Float, Date
>>> from sqlalchemy.orm import sessionmaker
>>> engine = create_engine("sqlite:///birth.db")
>>> Base = declarative_base()
>>> Session = sessionmaker(bind=engine)

```

Let's suppose we have the following database model:

```

>>> class BirthRegister(Base):
...     __tablename__='birth'
...     id=Column(Integer, primary_key=True)
...     name=Column(String)
...     weight=Column(Float)
...     birth=Column(Date)

```

Let's create the table:

```

>>> Base.metadata.create_all(engine)

```

Now here is a sample excel file to be saved to the table:

Here is the code to import it:

```
>>> session = Session() # obtain a sql session
>>> p.save_as(file_name="birth.xls", name_columns_by_row=0, dest_session=session,
↳dest_table=BirthRegister)
```

Done it. It is that simple. Let's verify what has been imported to make sure.

```
>>> sheet = p.get_sheet(session=session, table=BirthRegister)
>>> sheet
birth:
+-----+-----+-----+-----+
| birth      | id | name  | weight |
+-----+-----+-----+-----+
| 2015-02-03 | 1  | Adam  | 3.4    |
+-----+-----+-----+-----+
| 2014-11-12 | 2  | Smith | 4.2    |
+-----+-----+-----+-----+
```


5.1 Recipes

Warning: The pyexcel DOES NOT consider Fonts, Styles and Charts at all. In the resulting excel files, fonts, styles and charts will not be transferred.

These recipes give a one-stop utility functions for known use cases. Similar functionality can be achieved using other application interfaces.

5.1.1 Update one column of a data file

Suppose you have one data file as the following:

example.xls

Column 1	Column 2	Column 3
1	4	7
2	5	8
3	6	9

And you want to update Column 2 with these data: [11, 12, 13]

Here is the code:

```
>>> from pyexcel.cookbook import update_columns
>>> custom_column = {"Column 2": [11, 12, 13]}
>>> update_columns("example.xls", custom_column, "output.xls")
```

Your output.xls will have these data:

Column 1	Column 2	Column 3
1	11	7
2	12	8
3	13	9

5.1.2 Update one row of a data file

Suppose you have the same data file:

example.xls

Row 1	1	2	3
Row 2	4	5	6
Row 3	7	8	9

And you want to update the second row with these data: [7, 4, 1]

Here is the code:

```
>>> from pyexcel.cookbook import update_rows
>>> custom_row = {"Row 1": [11, 12, 13]}
>>> update_rows("example.xls", custom_row, "output.xls")
```

Your output.xls will have these data:

Column 1	Column 2	Column 3
7	4	1
2	5	8
3	6	9

5.1.3 Merge two files into one

Suppose you want to merge the following two data files:

example.csv

Column 1	Column 2	Column 3
1	4	7
2	5	8
3	6	9

example.xls

Column 4	Column 5
10	12
11	13

The following code will merge the tow into one file, say “output.xls”:

```
>>> from pyexcel.cookbook import merge_two_files
>>> merge_two_files("example.csv", "example.xls", "output.xls")
```

The output.xls would have the following data:

Column 1	Column 2	Column 3	Column 4	Column 5
1	4	7	10	12
2	5	8	11	13
3	6	9		

5.1.4 Select candidate columns of two files and form a new one

Suppose you have these two files:

example.ods

Column 1	Column 2	Column 3	Column 4	Column 5
1	4	7	10	13
2	5	8	11	14
3	6	9	12	15

example.xls

Column 6	Column 7	Column 8	Column 9	Column 10
16	17	18	19	20

```
>>> data = [
...     ["Column 1", "Column 2", "Column 3", "Column 4", "Column 5"],
...     [1, 4, 7, 10, 13],
...     [2, 5, 8, 11, 14],
...     [3, 6, 9, 12, 15]
... ]
>>> s = pyexcel.Sheet(data)
>>> s.save_as("example.csv")
>>> data = [
...     ["Column 6", "Column 7", "Column 8", "Column 9", "Column 10"],
...     [16, 17, 18, 19, 20]
... ]
>>> s = pyexcel.Sheet(data)
>>> s.save_as("example.xls")
```

And you want to filter out column 2 and 4 from example.ods, filter out column 6 and 7 and merge them:

Column 1	Column 3	Column 5	Column 8	Column 9	Column 10
1	7	13	18	19	20
2	8	14			
3	9	15			

The following code will do the job:

```
>>> from pyexcel.cookbook import merge_two_readers
>>> sheet1 = pyexcel.get_sheet(file_name="example.csv", name_columns_by_row=0)
>>> sheet2 = pyexcel.get_sheet(file_name="example.xls", name_columns_by_row=0)
>>> del sheet1.column[1, 3, 5]
>>> del sheet2.column[0, 1]
>>> merge_two_readers(sheet1, sheet2, "output.xls")
```

5.1.5 Merge two files into a book where each file become a sheet

Suppose you want to merge the following two data files:

example.csv

Column 1	Column 2	Column 3
1	4	7
2	5	8
3	6	9

example.xls

Column 4	Column 5
10	12
11	13

```
>>> data = [
...     ["Column 1", "Column 2", "Column 3"],
...     [1, 2, 3],
...     [4, 5, 6],
...     [7, 8, 9]
... ]
>>> s = pyexcel.Sheet(data)
>>> s.save_as("example.csv")
>>> data = [
...     ["Column 4", "Column 5"],
...     [10, 12],
...     [11, 13]
... ]
>>> s = pyexcel.Sheet(data)
>>> s.save_as("example.xls")
```

The following code will merge the two into one file, say "output.xls":

```
>>> from pyexcel.cookbook import merge_all_to_a_book
>>> merge_all_to_a_book(["example.csv", "example.xls"], "output.xls")
```

The output.xls would have the following data:

example.csv as sheet name and inside the sheet, you have:

Column 1	Column 2	Column 3
1	4	7
2	5	8
3	6	9

example.xls as sheet name and inside the sheet, you have:

Column 4	Column 5
10	12
11	13

5.2 Loading from other sources

5.2.1 Get back into pyexcel

list

```
>>> import pyexcel as p
>>> two_dimensional_list = [
...     [1, 2, 3, 4],
...     [5, 6, 7, 8],
...     [9, 10, 11, 12],
... ]
>>> sheet = p.get_sheet(array=two_dimensional_list)
>>> sheet
pyexcel_sheet1:
+---+---+---+---+
| 1 | 2 | 3 | 4 |
+---+---+---+---+
| 5 | 6 | 7 | 8 |
+---+---+---+---+
| 9 | 10 | 11 | 12 |
+---+---+---+---+
```

dict

```
>>> a_dictionary_of_key_value_pair = {
...     "IE": 0.2,
...     "Firefox": 0.3
... }
>>> sheet = p.get_sheet(adict=a_dictionary_of_key_value_pair)
>>> sheet
pyexcel_sheet1:
+-----+-----+
| Firefox | IE |
+-----+-----+
| 0.3     | 0.2 |
+-----+-----+
```

```
>>> a_dictionary_of_one_dimensional_arrays = {
...     "Column 1": [1, 2, 3, 4],
...     "Column 2": [5, 6, 7, 8],
...     "Column 3": [9, 10, 11, 12],
... }
>>> sheet = p.get_sheet(adict=a_dictionary_of_one_dimensional_arrays)
>>> sheet
pyexcel_sheet1:
+-----+-----+-----+
| Column 1 | Column 2 | Column 3 |
+-----+-----+-----+
| 1         | 5         | 9         |
+-----+-----+-----+
| 2         | 6         | 10        |
+-----+-----+-----+
| 3         | 7         | 11        |
+-----+-----+-----+
```

(continues on next page)

(continued from previous page)

```
+-----+-----+-----+
| 4      | 8      | 12     |
+-----+-----+-----+
```

records

```
>>> a_list_of_dictionaries = [
...     {
...         "Name": 'Adam',
...         "Age": 28
...     },
...     {
...         "Name": 'Beatrice',
...         "Age": 29
...     },
...     {
...         "Name": 'Ceri',
...         "Age": 30
...     },
...     {
...         "Name": 'Dean',
...         "Age": 26
...     }
... ]
>>> sheet = p.get_sheet(records=a_list_of_dictionaries)
>>> sheet
pyexcel_sheet1:
+-----+-----+
| Age | Name |
+-----+-----+
| 28  | Adam |
+-----+-----+
| 29  | Beatrice |
+-----+-----+
| 30  | Ceri |
+-----+-----+
| 26  | Dean |
+-----+-----+
```

book dict

```
>>> a_dictionary_of_two_dimensional_arrays = {
...     'Sheet 1':
...         [
...             [1.0, 2.0, 3.0],
...             [4.0, 5.0, 6.0],
...             [7.0, 8.0, 9.0]
...         ],
...     'Sheet 2':
...         [
...             ['X', 'Y', 'Z'],
...             [1.0, 2.0, 3.0],
...             [4.0, 5.0, 6.0]
...         ]
... }
```

(continues on next page)

(continued from previous page)

```

...     ],
...     'Sheet 3':
...     [
...         ['O', 'P', 'Q'],
...         [3.0, 2.0, 1.0],
...         [4.0, 3.0, 2.0]
...     ]
... }
>>> book = p.get_book(bookdict=a_dictionary_of_two_dimensional_arrays)
>>> book
Sheet 1:
+-----+-----+-----+
| 1.0 | 2.0 | 3.0 |
+-----+-----+-----+
| 4.0 | 5.0 | 6.0 |
+-----+-----+-----+
| 7.0 | 8.0 | 9.0 |
+-----+-----+-----+
Sheet 2:
+-----+-----+-----+
| X   | Y   | Z   |
+-----+-----+-----+
| 1.0 | 2.0 | 3.0 |
+-----+-----+-----+
| 4.0 | 5.0 | 6.0 |
+-----+-----+-----+
Sheet 3:
+-----+-----+-----+
| O   | P   | Q   |
+-----+-----+-----+
| 3.0 | 2.0 | 1.0 |
+-----+-----+-----+
| 4.0 | 3.0 | 2.0 |
+-----+-----+-----+

```

How to load a sheet from a url

Suppose you have excel file somewhere hosted:

```

>>> sheet = pe.get_sheet(url='http://yourdomain.com/test.csv')
>>> sheet
csv:
+---+---+---+
| 1 | 2 | 3 |
+---+---+---+

```

For sheet

Get content

```

>>> another_sheet = p.Sheet()
>>> another_sheet.url = "https://github.com/pyexcel/pyexcel/raw/master/examples/
↳basics/multiple-sheets-example.xls"

```

(continues on next page)

(continued from previous page)

```
>>> another_sheet.content
+---+---+---+
| 1 | 2 | 3 |
+---+---+---+
| 4 | 5 | 6 |
+---+---+---+
| 7 | 8 | 9 |
+---+---+---+
```

For book

How about setting content via a url?

```
>>> another_book = p.Book()
>>> another_book.url = "https://github.com/pyexcel/pyexcel/raw/master/examples/basics/
↳multiple-sheets-example.xls"
>>> another_book
Sheet 1:
+---+---+---+
| 1 | 2 | 3 |
+---+---+---+
| 4 | 5 | 6 |
+---+---+---+
| 7 | 8 | 9 |
+---+---+---+
Sheet 2:
+---+---+---+
| X | Y | Z |
+---+---+---+
| 1 | 2 | 3 |
+---+---+---+
| 4 | 5 | 6 |
+---+---+---+
Sheet 3:
+---+---+---+
| O | P | Q |
+---+---+---+
| 3 | 2 | 1 |
+---+---+---+
| 4 | 3 | 2 |
+---+---+---+
```

6.1 Questions and Answers

1. Python flask writing to a csv file and reading it
2. PyQt: Import .xls file and populate QTableWidgetItem?
3. How do I write data to csv file in columns and rows from a list in python?
4. How to write dictionary values to a csv file using Python
5. Python convert csv to xlsx
6. How to read data from excel and set data type
7. Remove or keep specific columns in csv file
8. How can I put a CSV file in an array?

6.2 How to inject csv data to database

Here is real case in the stack-overflow. Due to the author's ignorance, the user would like to have the code in matlab than Python. Hence, I am sharing my pyexcel solution here.

6.2.1 Problem definition

Here is my CSV file:

PDB_Id	123442	234335	234336	3549867
a001	6	0	0	8
b001	4	2	0	0
c003	0	0	0	5

I want to put this data in a MYSQL table in the form:

PROTEIN_ID	PROTEIN_KEY	VALUE_OF_KEY
a001	123442	6
a001	234335	0
a001	234336	0
a001	3549867	8
b001	123442	4
b001	234335	2
b001	234336	0
b001	234336	0
c003	123442	0
c003	234335	0
c003	234336	0
c003	3549867	5

I have created table with the following code:

```
sql = """CREATE TABLE ALLPROTEINS (
    Protein_ID CHAR(20),
    PROTEIN_KEY INT ,
    VALUE_OF_KEY INT
) """
```

I need the code for insert.

6.2.2 Pyexcel solution

If you could insert an id field to act as the primary key, it can be mapped using sqlalchemy's ORM:

```
$ sqlite3 /tmp/stack2.db
sqlite> CREATE TABLE ALLPROTEINS (
...>         ID INT,
...>         Protein_ID CHAR(20),
...>         PROTEIN_KEY INT,
...>         VALUE_OF_KEY INT
...>         );
```

Here is the data mapping script vis sqlalchemy:

```
>>> # mapping your database via sqlalchemy
>>> from sqlalchemy import create_engine
>>> from sqlalchemy.ext.declarative import declarative_base
>>> from sqlalchemy import Column, Integer, String
>>> from sqlalchemy.orm import sessionmaker
>>> # checkout http://docs.sqlalchemy.org/en/latest/dialects/index.html
>>> # for a different database server
>>> engine = create_engine("sqlite:///tmp/stack2.db")
>>> Base = declarative_base()
>>> class Proteins(Base):
...     __tablename__ = 'ALLPROTEINS'
...     id = Column(Integer, primary_key=True, autoincrement=True) # <-- appended_
↳field
...     protein_id = Column(String(20))
...     protein_key = Column(Integer)
...     value_of_key = Column(Integer)
>>> Session = sessionmaker(bind=engine)
>>>
```

Here is the short script to get data inserted into the database:

```
>>> import pyexcel as p
>>> from itertools import product
>>> # data insertion code starts here
>>> sheet = p.get_sheet(file_name="csv-to-mysql-in-matlab-code.csv", delimiter='\t')
>>> sheet.name_columns_by_row(0)
>>> sheet.name_rows_by_column(0)
>>> print(sheet)
csv-to-mysql-in-matlab-code.csv:
+-----+-----+-----+-----+-----+
|      | 123442 | 234335 | 234336 | 3549867 |
+=====+=====+=====+=====+=====+
| a001 | 6      | 0      | 0      | 8      |
+-----+-----+-----+-----+
| b001 | 4      | 2      | 0      | 0      |
+-----+-----+-----+-----+
| c003 | 0      | 0      | 0      | 5      |
+-----+-----+-----+-----+
>>> results = []
>>> for protein_id, protein_key in product(sheet.rownames, sheet.colnames):
...     results.append([protein_id, protein_key, sheet[str(protein_id), protein_key]])
>>>
>>> sheet2 = p.get_sheet(array=results)
>>> sheet2.colnames = ['protein_id', 'protein_key', 'value_of_key']
>>> print(sheet2)
pyexcel_sheet1:
+-----+-----+-----+
| protein_id | protein_key | value_of_key |
+=====+=====+=====+
| a001      | 123442      | 6            |
+-----+-----+-----+
| a001      | 234335      | 0            |
+-----+-----+-----+
| a001      | 234336      | 0            |
+-----+-----+-----+
| a001      | 3549867     | 8            |
+-----+-----+-----+
| b001      | 123442      | 4            |
+-----+-----+-----+
| b001      | 234335      | 2            |
+-----+-----+-----+
| b001      | 234336      | 0            |
+-----+-----+-----+
| b001      | 3549867     | 0            |
+-----+-----+-----+
| c003      | 123442      | 0            |
+-----+-----+-----+
| c003      | 234335      | 0            |
+-----+-----+-----+
| c003      | 234336      | 0            |
+-----+-----+-----+
| c003      | 3549867     | 5            |
+-----+-----+-----+
>>> sheet2.save_to_database(session=Session(), table=Proteins)
```

Here is the data inserted:

```
$ sqlite3 /tmp/stack2.db
sqlite> select * from allproteins
...> ;
|a001|123442|6
|a001|234335|0
|a001|234336|0
|a001|3549867|8
|b001|123442|4
|b001|234335|2
|b001|234336|0
|b001|234336|0
|c003|123442|0
|c003|234335|0
|c003|234336|0
|c003|3549867|5
```

7.1 API Reference

This is intended for users of pyexcel.

7.1.1 Signature functions

Obtaining data from excel file

It is believed that once a Python developer could easily operate on list, dictionary and various mixture of both. This library provides four module level functions to help you obtain excel data in those formats. Please refer to “A list of module level functions”, the first three functions operates on any one sheet from an excel book and the fourth one returns all data in all sheets in an excel book.

<code>get_array(**keywords)</code>	Obtain an array from an excel source
<code>get_dict([name_columns_by_row])</code>	Obtain a dictionary from an excel source
<code>get_records([name_columns_by_row])</code>	Obtain a list of records from an excel source
<code>get_book_dict(**keywords)</code>	Obtain a dictionary of two dimensional arrays

pyexcel.get_array

`pyexcel.get_array (**keywords)`

Obtain an array from an excel source

It accepts the same parameters as `get_sheet ()` but return an array instead.

Not all parameters are needed. Here is a table

source	parameters
loading from file	file_name, sheet_name, keywords
loading from string	file_content, file_type, sheet_name, keywords
loading from stream	file_stream, file_type, sheet_name, keywords
loading from sql	session, table
loading from sql in django	model
loading from query sets	any query sets(sqlalchemy or django)
loading from dictionary	adict, with_keys
loading from records	records
loading from array	array
loading from an url	url

Parameters

file_name : a file with supported file extension

file_content : the file content

file_stream : the file stream

file_type : the file type in *file_content* or *file_stream*

session : database session

table : database table

model: a django model

adict: a dictionary of one dimensional arrays

url : a download http url for your excel file

with_keys : load with previous dictionary's keys, default is True

records : a list of dictionaries that have the same keys

array : a two dimensional array, a list of lists

sheet_name : sheet name. if sheet_name is not given, the default sheet at index 0 is loaded

start_row [int] defaults to 0. It allows you to skip rows at the beginning

row_limit: int defaults to -1, meaning till the end of the whole sheet. It allows you to skip the tailing rows.

start_column [int] defaults to 0. It allows you to skip columns on your left hand side

column_limit: int defaults to -1, meaning till the end of the columns. It allows you to skip the tailing columns.

skip_row_func: It allows you to write your own row skipping functions.

The protocol is to return `pyexcel_io.constants.SKIP_DATA` if skipping data, `pyexcel_io.constants.TAKE_DATA` to read data, `pyexcel_io.constants.STOP_ITERATION` to exit the reading procedure

skip_column_func: It allows you to write your own column skipping functions.

The protocol is to return `pyexcel_io.constants.SKIP_DATA` if skipping data, `pyexcel_io.constants.TAKE_DATA` to read data, `pyexcel_io.constants.STOP_ITERATION` to exit the reading procedure

skip_empty_rows: bool Defaults to False. Toggle it to True if the rest of empty rows are useless, but it does affect the number of rows.

row_renderer: You could choose to write a custom row renderer when the data is being read.

auto_detect_float : defaults to True

auto_detect_int : defaults to True

auto_detect_datetime : defaults to True

ignore_infinity : defaults to True

library : choose a specific pyexcel-io plugin for reading

source_library : choose a specific data source plugin for reading

parser_library : choose a pyexcel parser plugin for reading

skip_hidden_sheets: default is True. Please toggle it to read hidden sheets

Parameters related to csv file format

for csv, `fmtparams` are accepted

delimiter : field separator

lineterminator : line terminator

encoding: csv specific. Specify the file encoding the csv file. For example: `encoding='latin1'`. Especially, `encoding='utf-8-sig'` would add utf 8 bom header if used in `renderer`, or would parse a csv with utf bom header used in `parser`.

escapechar : A one-character string used by the writer to escape the delimiter if quoting is set to `QUOTE_NONE` and the `quotechar` if `doublequote` is `False`.

quotechar : A one-character string used to quote fields containing special characters, such as the delimiter or `quotechar`, or which contain new-line characters. It defaults to `'"`

quoting : Controls when quotes should be generated by the writer and recognised by the reader. It can take on any of the `QUOTE_*` constants (see section Module Contents) and defaults to `QUOTE_MINIMAL`.

skipinitialspace : When `True`, whitespace immediately following the delimiter is ignored. The default is `False`.

Parameters related to xls file format: Please note the following parameters apply to `pyexcel-xls`. more details can be found in `xlrd.open_workbook()`

logfile: An open file to which messages and diagnostics are written.

verbosity: Increases the volume of trace material written to the logfile.

use_mmap: Whether to use the `mmap` module is determined heuristically. Use this arg to override the result.

Current heuristic: `mmap` is used if it exists.

encoding_override: Used to overcome missing or bad codepage information in older-version files.

formatting_info: The default is `False`, which saves memory.

When `True`, formatting information will be read from the spreadsheet file. This provides all cells, including empty and blank cells. Formatting information is available for each cell.

ragged_rows: The default of `False` means all rows are padded out with empty cells so that all rows have the same size as found in `ncols`.

`True` means that there are no empty cells at the ends of rows. This can result in substantial memory savings if rows are of widely varying sizes. See also the `row_len()` method.

pyexcel.get_dict

`pyexcel.get_dict` (*name_columns_by_row=0, **keywords*)

Obtain a dictionary from an excel source

It accepts the same parameters as `get_sheet()` but return a dictionary instead.

Specifically: `name_columns_by_row` : specify a row to be a dictionary key. It is default to 0 or first row.

If you would use a column index 0 instead, you should do:

```
get_dict(name_columns_by_row=-1, name_rows_by_column=0)
```

Not all parameters are needed. Here is a table

source	parameters
loading from file	file_name, sheet_name, keywords
loading from string	file_content, file_type, sheet_name, keywords
loading from stream	file_stream, file_type, sheet_name, keywords
loading from sql	session, table
loading from sql in django	model
loading from query sets	any query sets(sqlalchemy or django)
loading from dictionary	adict, with_keys
loading from records	records
loading from array	array
loading from an url	url

Parameters

file_name : a file with supported file extension

file_content : the file content

file_stream : the file stream

file_type : the file type in *file_content* or *file_stream*

session : database session

table : database table

model: a django model

adict: a dictionary of one dimensional arrays

url : a download http url for your excel file

with_keys : load with previous dictionary's keys, default is True

records : a list of dictionaries that have the same keys

array : a two dimensional array, a list of lists

sheet_name : sheet name. if sheet_name is not given, the default sheet at index 0 is loaded

start_row [int] defaults to 0. It allows you to skip rows at the beginning

row_limit: int defaults to -1, meaning till the end of the whole sheet. It allows you to skip the tailing rows.

start_column [int] defaults to 0. It allows you to skip columns on your left hand side

column_limit: int defaults to -1, meaning till the end of the columns. It allows you to skip the tailing columns.

skip_row_func: It allows you to write your own row skipping functions.

The protocol is to return `pyexcel_io.constants.SKIP_DATA` if skipping data, `pyexcel_io.constants.TAKE_DATA` to read data, `pyexcel_io.constants.STOP_ITERATION` to exit the reading procedure

skip_column_func: It allows you to write your own column skipping functions.

The protocol is to return `pyexcel_io.constants.SKIP_DATA` if skipping data, `pyexcel_io.constants.TAKE_DATA` to read data, `pyexcel_io.constants.STOP_ITERATION` to exit the reading procedure

skip_empty_rows: **bool** Defaults to False. Toggle it to True if the rest of empty rows are useless, but it does affect the number of rows.

row_renderer: You could choose to write a custom row renderer when the data is being read.

auto_detect_float : defaults to True

auto_detect_int : defaults to True

auto_detect_datetime : defaults to True

ignore_infinity : defaults to True

library : choose a specific pyexcel-io plugin for reading

source_library : choose a specific data source plugin for reading

parser_library : choose a pyexcel parser plugin for reading

skip_hidden_sheets: default is True. Please toggle it to read hidden sheets

Parameters related to csv file format

for csv, `fmtparams` are accepted

delimiter : field separator

lineterminator : line terminator

encoding: csv specific. Specify the file encoding the csv file. For example: `encoding='latin1'`. Especially, `encoding='utf-8-sig'` would add utf 8 bom header if used in renderer, or would parse a csv with utf bom header used in parser.

escapechar : A one-character string used by the writer to escape the delimiter if quoting is set to `QUOTE_NONE` and the quotechar if `doublequote` is False.

quotechar : A one-character string used to quote fields containing special characters, such as the delimiter or quotechar, or which contain new-line characters. It defaults to `''''`

quoting : Controls when quotes should be generated by the writer and recognised by the reader. It can take on any of the `QUOTE_*` constants (see section Module Contents) and defaults to `QUOTE_MINIMAL`.

skipinitialspace : When True, whitespace immediately following the delimiter is ignored. The default is False.

Parameters related to xls file format: Please note the following parameters apply to pyexcel-xls. more details can be found in `xlrd.open_workbook()`

logfile: An open file to which messages and diagnostics are written.

verbosity: Increases the volume of trace material written to the logfile.

use_mmap: Whether to use the mmap module is determined heuristically. Use this arg to override the result.

Current heuristic: mmap is used if it exists.

encoding_override: Used to overcome missing or bad codepage information in older-version files.

formatting_info: The default is False, which saves memory.

When True, formatting information will be read from the spreadsheet file. This provides all cells, including empty and blank cells. Formatting information is available for each cell.

ragged_rows: The default of False means all rows are padded out with empty cells so that all rows have the same size as found in ncols.

True means that there are no empty cells at the ends of rows. This can result in substantial memory savings if rows are of widely varying sizes. See also the `row_len()` method.

pyexcel.get_records

`pyexcel.get_records(name_columns_by_row=0, **keywords)`

Obtain a list of records from an excel source

It accepts the same parameters as `get_sheet()` but return a list of dictionary(records) instead.

Specifically: `name_columns_by_row` : specify a row to be a dictionary key. It is default to 0 or first row.

If you would use a column index 0 instead, you should do:

```
get_records(name_columns_by_row=-1, name_rows_by_column=0)
```

Not all parameters are needed. Here is a table

source	parameters
loading from file	file_name, sheet_name, keywords
loading from string	file_content, file_type, sheet_name, keywords
loading from stream	file_stream, file_type, sheet_name, keywords
loading from sql	session, table
loading from sql in django	model
loading from query sets	any query sets(sqlalchemy or django)
loading from dictionary	adict, with_keys
loading from records	records
loading from array	array
loading from an url	url

Parameters

file_name : a file with supported file extension

file_content : the file content

file_stream : the file stream

file_type : the file type in `file_content` or `file_stream`

session : database session

table : database table

model: a django model

adict: a dictionary of one dimensional arrays

url : a download http url for your excel file

with_keys : load with previous dictionary's keys, default is True

records : a list of dictionaries that have the same keys

array : a two dimensional array, a list of lists

sheet_name : sheet name. if sheet_name is not given, the default sheet at index 0 is loaded

start_row [int] defaults to 0. It allows you to skip rows at the beginning

row_limit: int defaults to -1, meaning till the end of the whole sheet. It allows you to skip the tailing rows.

start_column [int] defaults to 0. It allows you to skip columns on your left hand side

column_limit: int defaults to -1, meaning till the end of the columns. It allows you to skip the tailing columns.

skip_row_func: It allows you to write your own row skipping functions.

The protocol is to return `pyexcel_io.constants.SKIP_DATA` if skipping data, `pyexcel_io.constants.TAKE_DATA` to read data, `pyexcel_io.constants.STOP_ITERATION` to exit the reading procedure

skip_column_func: It allows you to write your own column skipping functions.

The protocol is to return `pyexcel_io.constants.SKIP_DATA` if skipping data, `pyexcel_io.constants.TAKE_DATA` to read data, `pyexcel_io.constants.STOP_ITERATION` to exit the reading procedure

skip_empty_rows: bool Defaults to False. Toggle it to True if the rest of empty rows are useless, but it does affect the number of rows.

row_renderer: You could choose to write a custom row renderer when the data is being read.

auto_detect_float : defaults to True

auto_detect_int : defaults to True

auto_detect_datetime : defaults to True

ignore_infinity : defaults to True

library : choose a specific pyexcel-io plugin for reading

source_library : choose a specific data source plugin for reading

parser_library : choose a pyexcel parser plugin for reading

skip_hidden_sheets: default is True. Please toggle it to read hidden sheets

Parameters related to csv file format

for csv, `fmtparams` are accepted

delimiter : field separator

lineterminator : line terminator

encoding: csv specific. Specify the file encoding the csv file. For example: `encoding='latin1'`. Especially, `encoding='utf-8-sig'` would add utf 8 bom header if used in renderer, or would parse a csv with utf bom header used in parser.

escapechar : A one-character string used by the writer to escape the delimiter if quoting is set to `QUOTE_NONE` and the quotechar if `doublequote` is False.

quotechar : A one-character string used to quote fields containing special characters, such as the delimiter or quotechar, or which contain new-line characters. It defaults to `''''`

quoting : Controls when quotes should be generated by the writer and recognised by the reader. It can take on any of the `QUOTE_*` constants (see section Module Contents) and defaults to `QUOTE_MINIMAL`.

skipinitialspace : When True, whitespace immediately following the delimiter is ignored. The default is False.

Parameters related to xls file format: Please note the following parameters apply to pyexcel-xls. more details can be found in `xlrd.open_workbook()`

logfile: An open file to which messages and diagnostics are written.

verbosity: Increases the volume of trace material written to the logfile.

use_mmap: Whether to use the mmap module is determined heuristically. Use this arg to override the result.

Current heuristic: mmap is used if it exists.

encoding_override: Used to overcome missing or bad codepage information in older-version files.

formatting_info: The default is False, which saves memory.

When True, formatting information will be read from the spreadsheet file. This provides all cells, including empty and blank cells. Formatting information is available for each cell.

ragged_rows: The default of False means all rows are padded out with empty cells so that all rows have the same size as found in ncols.

True means that there are no empty cells at the ends of rows. This can result in substantial memory savings if rows are of widely varying sizes. See also the `row_len()` method.

pyexcel.get_book_dict

`pyexcel.get_book_dict(**keywords)`

Obtain a dictionary of two dimensional arrays

It accepts the same parameters as `get_book()` but return a dictionary instead.

Here is a table of parameters:

source	parameters
loading from file	file_name, keywords
loading from string	file_content, file_type, keywords
loading from stream	file_stream, file_type, keywords
loading from sql	session, tables
loading from django models	models
loading from dictionary	bookdict
loading from an url	url

Where the dictionary should have text as keys and two dimensional array as values.

Parameters

file_name : a file with supported file extension

file_content : the file content

file_stream : the file stream

file_type : the file type in `file_content` or `file_stream`

session : database session

tables : a list of database table

models : a list of django models

bookdict : a dictionary of two dimensional arrays

url : a download http url for your excel file

sheets: a list of mixed sheet names and sheet indices to be read. This is done to keep Pandas compactibility. With this parameter, more than one sheet can be read and you have the control to read the sheets of your interest instead of all available sheets.

auto_detect_float : defaults to True

auto_detect_int : defaults to True

auto_detect_datetime : defaults to True

ignore_infinity : defaults to True

library : choose a specific pyexcel-io plugin for reading

source_library : choose a specific data source plugin for reading

parser_library : choose a pyexcel parser plugin for reading

skip_hidden_sheets: default is True. Please toggle it to read hidden sheets

Parameters related to csv file format

for csv, `fmtparams` are accepted

delimiter : field separator

lineterminator : line terminator

encoding: csv specific. Specify the file encoding the csv file. For example: `encoding='latin1'`. Especially, `encoding='utf-8-sig'` would add utf 8 bom header if used in renderer, or would parse a csv with utf brom header used in parser.

escapechar : A one-character string used by the writer to escape the delimiter if quoting is set to `QUOTE_NONE` and the quotechar if `doublequote` is `False`.

quotechar : A one-character string used to quote fields containing special characters, such as the delimiter or quotechar, or which contain new-line characters. It defaults to `''''`

quoting : Controls when quotes should be generated by the writer and recognised by the reader. It can take on any of the `QUOTE_*` constants (see section Module Contents) and defaults to `QUOTE_MINIMAL`.

skipinitialspace : When `True`, whitespace immediately following the delimiter is ignored. The default is `False`.

In cases where the excel data needs custom manipulations, a pyexcel user got a few choices: one is to use *Sheet* and *Book*, the other is to look for more sophisticated ones:

- Pandas, for numerical analysis
- Do-it-yourself

<code>get_book(**keywords)</code>	Get an instance of <i>Book</i> from an excel source
<code>get_sheet(**keywords)</code>	Get an instance of <i>Sheet</i> from an excel source

pyexcel.get_book

`pyexcel.get_book(**keywords)`

Get an instance of *Book* from an excel source

Here is a table of parameters:

source	parameters
loading from file	file_name, keywords
loading from string	file_content, file_type, keywords
loading from stream	file_stream, file_type, keywords
loading from sql	session, tables
loading from django models	models
loading from dictionary	bookdict
loading from an url	url

Where the dictionary should have text as keys and two dimensional array as values.

Parameters

file_name : a file with supported file extension

file_content : the file content

file_stream : the file stream

file_type : the file type in *file_content* or *file_stream*

session : database session

tables : a list of database table

models : a list of django models

bookdict : a dictionary of two dimensional arrays

url : a download http url for your excel file

sheets: a list of mixed sheet names and sheet indices to be read. This is done to keep Pandas compactibility.

With this parameter, more than one sheet can be read and you have the control to read the sheets of your interest instead of all available sheets.

auto_detect_float : defaults to True

auto_detect_int : defaults to True

auto_detect_datetime : defaults to True

ignore_infinity : defaults to True

library : choose a specific pyexcel-io plugin for reading

source_library : choose a specific data source plugin for reading

parser_library : choose a pyexcel parser plugin for reading

skip_hidden_sheets: default is True. Please toggle it to read hidden sheets

Parameters related to csv file format

for csv, `fmtparams` are accepted

delimiter : field separator

lineterminator : line terminator

encoding: csv specific. Specify the file encoding the csv file. For example: `encoding='latin1'`. Especially, `encoding='utf-8-sig'` would add utf 8 bom header if used in renderer, or would parse a csv with utf brom header used in parser.

escapechar : A one-character string used by the writer to escape the delimiter if quoting is set to `QUOTE_NONE` and the `quotechar` if `doublequote` is `False`.

quotechar : A one-character string used to quote fields containing special characters, such as the delimiter or quotechar, or which contain new-line characters. It defaults to ‘”’

quoting : Controls when quotes should be generated by the writer and recognised by the reader. It can take on any of the QUOTE_* constants (see section Module Contents) and defaults to QUOTE_MINIMAL.

skipinitialspace : When True, whitespace immediately following the delimiter is ignored. The default is False.

pyexcel.get_sheet

pyexcel.get_sheet (**keywords)

Get an instance of *Sheet* from an excel source

Not all parameters are needed. Here is a table

source	parameters
loading from file	file_name, sheet_name, keywords
loading from string	file_content, file_type, sheet_name, keywords
loading from stream	file_stream, file_type, sheet_name, keywords
loading from sql	session, table
loading from sql in django	model
loading from query sets	any query sets(sqlalchemy or django)
loading from dictionary	adict, with_keys
loading from records	records
loading from array	array
loading from an url	url

Parameters

file_name : a file with supported file extension

file_content : the file content

file_stream : the file stream

file_type : the file type in *file_content* or *file_stream*

session : database session

table : database table

model: a django model

adict: a dictionary of one dimensional arrays

url : a download http url for your excel file

with_keys : load with previous dictionary’s keys, default is True

records : a list of dictionaries that have the same keys

array : a two dimensional array, a list of lists

sheet_name : sheet name. if sheet_name is not given, the default sheet at index 0 is loaded

start_row [int] defaults to 0. It allows you to skip rows at the beginning

row_limit: int defaults to -1, meaning till the end of the whole sheet. It allows you to skip the tailing rows.

start_column [int] defaults to 0. It allows you to skip columns on your left hand side

column_limit: int defaults to -1, meaning till the end of the columns. It allows you to skip the tailing columns.

skip_row_func: It allows you to write your own row skipping functions.

The protocol is to return `pyexcel_io.constants.SKIP_DATA` if skipping data, `pyexcel_io.constants.TAKE_DATA` to read data, `pyexcel_io.constants.STOP_ITERATION` to exit the reading procedure

skip_column_func: It allows you to write your own column skipping functions.

The protocol is to return `pyexcel_io.constants.SKIP_DATA` if skipping data, `pyexcel_io.constants.TAKE_DATA` to read data, `pyexcel_io.constants.STOP_ITERATION` to exit the reading procedure

skip_empty_rows: **bool** Defaults to False. Toggle it to True if the rest of empty rows are useless, but it does affect the number of rows.

row_renderer: You could choose to write a custom row renderer when the data is being read.

auto_detect_float : defaults to True

auto_detect_int : defaults to True

auto_detect_datetime : defaults to True

ignore_infinity : defaults to True

library : choose a specific pyexcel-io plugin for reading

source_library : choose a specific data source plugin for reading

parser_library : choose a pyexcel parser plugin for reading

skip_hidden_sheets: default is True. Please toggle it to read hidden sheets

Parameters related to csv file format

for csv, `fmtparams` are accepted

delimiter : field separator

lineterminator : line terminator

encoding: csv specific. Specify the file encoding the csv file. For example: `encoding='latin1'`. Especially, `encoding='utf-8-sig'` would add utf 8 bom header if used in renderer, or would parse a csv with utf bom header used in parser.

escapechar : A one-character string used by the writer to escape the delimiter if quoting is set to `QUOTE_NONE` and the quotechar if `doublequote` is False.

quotechar : A one-character string used to quote fields containing special characters, such as the delimiter or quotechar, or which contain new-line characters. It defaults to `''''`

quoting : Controls when quotes should be generated by the writer and recognised by the reader. It can take on any of the `QUOTE_*` constants (see section Module Contents) and defaults to `QUOTE_MINIMAL`.

skipinitialspace : When True, whitespace immediately following the delimiter is ignored. The default is False.

Parameters related to xls file format: Please note the following parameters apply to pyexcel-xls. more details can be found in `xlrd.open_workbook()`

logfile: An open file to which messages and diagnostics are written.

verbosity: Increases the volume of trace material written to the logfile.

use_mmap: Whether to use the mmap module is determined heuristically. Use this arg to override the result.
Current heuristic: mmap is used if it exists.

encoding_override: Used to overcome missing or bad codepage information in older-version files.

formatting_info: The default is False, which saves memory.

When True, formatting information will be read from the spreadsheet file. This provides all cells, including empty and blank cells. Formatting information is available for each cell.

ragged_rows: The default of False means all rows are padded out with empty cells so that all rows have the same size as found in ncols.

True means that there are no empty cells at the ends of rows. This can result in substantial memory savings if rows are of widely varying sizes. See also the `row_len()` method.

The following two variants of the data access function use generator and should work well with big data files. However, you will need to call `free_resources()` to make sure file handles are closed.

<code>iget_array(**keywords)</code>	Obtain a generator of an two dimensional array from an excel source
<code>iget_records([custom_headers])</code>	Obtain a generator of a list of records from an excel source
<code>free_resources()</code>	Close file handles opened by signature functions that starts with 'i'

pyexcel.iget_array

`pyexcel.iget_array(**keywords)`

Obtain a generator of an two dimensional array from an excel source

It is similiar to `pyexcel.get_array()` but it has less memory footprint.

Not all parameters are needed. Here is a table

source	parameters
loading from file	file_name, sheet_name, keywords
loading from string	file_content, file_type, sheet_name, keywords
loading from stream	file_stream, file_type, sheet_name, keywords
loading from sql	session, table
loading from sql in django	model
loading from query sets	any query sets(sqlalchemy or django)
loading from dictionary	adict, with_keys
loading from records	records
loading from array	array
loading from an url	url

Parameters

file_name : a file with supported file extension

file_content : the file content

file_stream : the file stream

file_type : the file type in `file_content` or `file_stream`

session : database session

table : database table

model: a django model

adict: a dictionary of one dimensional arrays

url : a download http url for your excel file

with_keys : load with previous dictionary's keys, default is True

records : a list of dictionaries that have the same keys

array : a two dimensional array, a list of lists

sheet_name : sheet name. if sheet_name is not given, the default sheet at index 0 is loaded

start_row [int] defaults to 0. It allows you to skip rows at the beginning

row_limit: int defaults to -1, meaning till the end of the whole sheet. It allows you to skip the tailing rows.

start_column [int] defaults to 0. It allows you to skip columns on your left hand side

column_limit: int defaults to -1, meaning till the end of the columns. It allows you to skip the tailing columns.

skip_row_func: It allows you to write your own row skipping functions.

The protocol is to return `pyexcel_io.constants.SKIP_DATA` if skipping data, `pyexcel_io.constants.TAKE_DATA` to read data, `pyexcel_io.constants.STOP_ITERATION` to exit the reading procedure

skip_column_func: It allows you to write your own column skipping functions.

The protocol is to return `pyexcel_io.constants.SKIP_DATA` if skipping data, `pyexcel_io.constants.TAKE_DATA` to read data, `pyexcel_io.constants.STOP_ITERATION` to exit the reading procedure

skip_empty_rows: bool Defaults to False. Toggle it to True if the rest of empty rows are useless, but it does affect the number of rows.

row_renderer: You could choose to write a custom row renderer when the data is being read.

auto_detect_float : defaults to True

auto_detect_int : defaults to True

auto_detect_datetime : defaults to True

ignore_infinity : defaults to True

library : choose a specific pyexcel-io plugin for reading

source_library : choose a specific data source plugin for reading

parser_library : choose a pyexcel parser plugin for reading

skip_hidden_sheets: default is True. Please toggle it to read hidden sheets

Parameters related to csv file format

for csv, `fmtparams` are accepted

delimiter : field separator

lineterminator : line terminator

encoding: csv specific. Specify the file encoding the csv file. For example: `encoding='latin1'`. Especially, `encoding='utf-8-sig'` would add utf 8 bom header if used in renderer, or would parse a csv with utf brom header used in parser.

escapechar : A one-character string used by the writer to escape the delimiter if quoting is set to `QUOTE_NONE` and the quotechar if doublequote is False.

quotechar : A one-character string used to quote fields containing special characters, such as the delimiter or quotechar, or which contain new-line characters. It defaults to ‘”’

quoting : Controls when quotes should be generated by the writer and recognised by the reader. It can take on any of the QUOTE_* constants (see section Module Contents) and defaults to QUOTE_MINIMAL.

skipinitialspace : When True, whitespace immediately following the delimiter is ignored. The default is False.

Parameters related to xls file format: Please note the following parameters apply to pyexcel-xls. more details can be found in `xlrd.open_workbook()`

logfile: An open file to which messages and diagnostics are written.

verbosity: Increases the volume of trace material written to the logfile.

use_mmap: Whether to use the mmap module is determined heuristically. Use this arg to override the result.

Current heuristic: mmap is used if it exists.

encoding_override: Used to overcome missing or bad codepage information in older-version files.

formatting_info: The default is False, which saves memory.

When True, formatting information will be read from the spreadsheet file. This provides all cells, including empty and blank cells. Formatting information is available for each cell.

ragged_rows: The default of False means all rows are padded out with empty cells so that all rows have the same size as found in ncols.

True means that there are no empty cells at the ends of rows. This can result in substantial memory savings if rows are of widely varying sizes. See also the `row_len()` method.

When you use this function to work on physical files, this function will leave its file handle open. When you finish the operation on its data, you need to call `pyexcel.free_resources()` to close file handle(s).

for csv, csvz file formats, file handles will be left open. for xls, ods file formats, the file is read all into memory and is close afterwards. for xlsx, file handles will be left open in python 2.7 - 3.5 by pyexcel-xlsx(openpyxl). In other words, pyexcel-xls, pyexcel-ods, pyexcel-ods3 won't leak file handles.

pyexcel.iget_records

`pyexcel.iget_records` (*custom_headers=None, **keywords*)

Obtain a generator of a list of records from an excel source

It is similiar to `pyexcel.get_records()` but it has less memory footprint but requires the headers to be in the first row. And the data matrix should be of equal length. It should consume less memory and should work well with large files.

Not all parameters are needed. Here is a table

source	parameters
loading from file	file_name, sheet_name, keywords
loading from string	file_content, file_type, sheet_name, keywords
loading from stream	file_stream, file_type, sheet_name, keywords
loading from sql	session, table
loading from sql in django	model
loading from query sets	any query sets(sqlalchemy or django)
loading from dictionary	adict, with_keys
loading from records	records
loading from array	array
loading from an url	url

Parameters

file_name : a file with supported file extension

file_content : the file content

file_stream : the file stream

file_type : the file type in *file_content* or *file_stream*

session : database session

table : database table

model: a django model

adict: a dictionary of one dimensional arrays

url : a download http url for your excel file

with_keys : load with previous dictionary's keys, default is True

records : a list of dictionaries that have the same keys

array : a two dimensional array, a list of lists

sheet_name : sheet name. if sheet_name is not given, the default sheet at index 0 is loaded

start_row [int] defaults to 0. It allows you to skip rows at the beginning

row_limit: int defaults to -1, meaning till the end of the whole sheet. It allows you to skip the tailing rows.

start_column [int] defaults to 0. It allows you to skip columns on your left hand side

column_limit: int defaults to -1, meaning till the end of the columns. It allows you to skip the tailing columns.

skip_row_func: It allows you to write your own row skipping functions.

The protocol is to return `pyexcel_io.constants.SKIP_DATA` if skipping data, `pyexcel_io.constants.TAKE_DATA` to read data, `pyexcel_io.constants.STOP_ITERATION` to exit the reading procedure

skip_column_func: It allows you to write your own column skipping functions.

The protocol is to return `pyexcel_io.constants.SKIP_DATA` if skipping data, `pyexcel_io.constants.TAKE_DATA` to read data, `pyexcel_io.constants.STOP_ITERATION` to exit the reading procedure

skip_empty_rows: bool Defaults to False. Toggle it to True if the rest of empty rows are useless, but it does affect the number of rows.

row_renderer: You could choose to write a custom row renderer when the data is being read.

auto_detect_float : defaults to True

auto_detect_int : defaults to True

auto_detect_datetime : defaults to True

ignore_infinity : defaults to True

library : choose a specific pyexcel-io plugin for reading

source_library : choose a specific data source plugin for reading

parser_library : choose a pyexcel parser plugin for reading

skip_hidden_sheets: default is True. Please toggle it to read hidden sheets

Parameters related to csv file format

for csv, `fmtparams` are accepted

delimiter : field separator

lineterminator : line terminator

encoding: csv specific. Specify the file encoding the csv file. For example: `encoding='latin1'`. Especially, `encoding='utf-8-sig'` would add utf 8 bom header if used in `renderer`, or would parse a csv with utf bom header used in `parser`.

escapechar : A one-character string used by the writer to escape the delimiter if quoting is set to `QUOTE_NONE` and the `quotechar` if `doublequote` is `False`.

quotechar : A one-character string used to quote fields containing special characters, such as the delimiter or `quotechar`, or which contain new-line characters. It defaults to `"'"`

quoting : Controls when quotes should be generated by the writer and recognised by the reader. It can take on any of the `QUOTE_*` constants (see section Module Contents) and defaults to `QUOTE_MINIMAL`.

skipinitialspace : When `True`, whitespace immediately following the delimiter is ignored. The default is `False`.

Parameters related to xls file format: Please note the following parameters apply to `pyexcel-xls`. more details can be found in `xlrd.open_workbook()`

logfile: An open file to which messages and diagnostics are written.

verbosity: Increases the volume of trace material written to the logfile.

use_mmap: Whether to use the `mmap` module is determined heuristically. Use this arg to override the result.

Current heuristic: `mmap` is used if it exists.

encoding_override: Used to overcome missing or bad codepage information in older-version files.

formatting_info: The default is `False`, which saves memory.

When `True`, formatting information will be read from the spreadsheet file. This provides all cells, including empty and blank cells. Formatting information is available for each cell.

ragged_rows: The default of `False` means all rows are padded out with empty cells so that all rows have the same size as found in `ncols`.

`True` means that there are no empty cells at the ends of rows. This can result in substantial memory savings if rows are of widely varying sizes. See also the `row_len()` method.

When you use this function to work on physical files, this function will leave its file handle open. When you finish the operation on its data, you need to call `pyexcel.free_resources()` to close file handle(s).

for csv, csvz file formats, file handles will be left open. for xls, ods file formats, the file is read all into memory and is close afterwards. for xlsx, file handles will be left open in python 2.7 - 3.5 by pyexcel-xlsx(openpyxl). In other words, pyexcel-xls, pyexcel-ods, pyexcel-ods3 won't leak file handles.

pyexcel.free_resources

`pyexcel.free_resources()`

Close file handles opened by signature functions that starts with 'i'

for csv, csvz file formats, file handles will be left open. for xls, ods file formats, the file is read all into memory and is close afterwards. for xlsx, file handles will be left open in python 2.7 - 3.5 by pyexcel-xlsx(openpyxl). In other words, pyexcel-xls, pyexcel-ods, pyexcel-ods3 won't leak file handles.

Saving data to excel file

<code>save_as(**keywords)</code>	Save a sheet from a data source to another one
<code>save_book_as(**keywords)</code>	Save a book from a data source to another one

pyexcel.save_as

`pyexcel.save_as(**keywords)`

Save a sheet from a data source to another one

It accepts two sets of keywords. Why two sets? one set is source, the other set is destination. In order to distinguish the two sets, source set will be exactly the same as the ones for `pyexcel.get_sheet()`; destination set are exactly the same as the ones for `pyexcel.Sheet.save_as` but require a 'dest' prefix.

Saving to source	parameters
file	dest_file_name, dest_sheet_name, keywords with prefix 'dest'
memory	dest_file_type, dest_content, dest_sheet_name, keywords with prefix 'dest'
sql	dest_session, dest_table, dest_initializer, dest_mapdict
django model	dest_model, dest_initializer, dest_mapdict, dest_batch_size

Not all parameters are needed. Here is a table

source	parameters
loading from file	file_name, sheet_name, keywords
loading from string	file_content, file_type, sheet_name, keywords
loading from stream	file_stream, file_type, sheet_name, keywords
loading from sql	session, table
loading from sql in django	model
loading from query sets	any query sets(sqlalchemy or django)
loading from dictionary	adict, with_keys
loading from records	records
loading from array	array
loading from an url	url

Parameters

file_name : a file with supported file extension

file_content : the file content

file_stream : the file stream

file_type : the file type in *file_content* or *file_stream*

session : database session

table : database table

model: a django model

adict: a dictionary of one dimensional arrays

url : a download http url for your excel file

with_keys : load with previous dictionary's keys, default is True

records : a list of dictionaries that have the same keys

array : a two dimensional array, a list of lists

sheet_name : sheet name. if sheet_name is not given, the default sheet at index 0 is loaded

start_row [int] defaults to 0. It allows you to skip rows at the beginning

row_limit: int defaults to -1, meaning till the end of the whole sheet. It allows you to skip the tailing rows.

start_column [int] defaults to 0. It allows you to skip columns on your left hand side

column_limit: int defaults to -1, meaning till the end of the columns. It allows you to skip the tailing columns.

skip_row_func: It allows you to write your own row skipping functions.

The protocol is to return `pyexcel_io.constants.SKIP_DATA` if skipping data, `pyexcel_io.constants.TAKE_DATA` to read data, `pyexcel_io.constants.STOP_ITERATION` to exit the reading procedure

skip_column_func: It allows you to write your own column skipping functions.

The protocol is to return `pyexcel_io.constants.SKIP_DATA` if skipping data, `pyexcel_io.constants.TAKE_DATA` to read data, `pyexcel_io.constants.STOP_ITERATION` to exit the reading procedure

skip_empty_rows: bool Defaults to False. Toggle it to True if the rest of empty rows are useless, but it does affect the number of rows.

row_renderer: You could choose to write a custom row renderer when the data is being read.

auto_detect_float : defaults to True

auto_detect_int : defaults to True

auto_detect_datetime : defaults to True

ignore_infinity : defaults to True

library : choose a specific pyexcel-io plugin for reading

source_library : choose a specific data source plugin for reading

parser_library : choose a pyexcel parser plugin for reading

skip_hidden_sheets: default is True. Please toggle it to read hidden sheets

Parameters related to csv file format

for csv, `fmtparams` are accepted

delimiter : field separator

lineterminator : line terminator

encoding: csv specific. Specify the file encoding the csv file. For example: `encoding='latin1'`. Especially, `encoding='utf-8-sig'` would add utf 8 bom header if used in `renderer`, or would parse a csv with utf bom header used in `parser`.

escapechar : A one-character string used by the writer to escape the delimiter if quoting is set to `QUOTE_NONE` and the `quotechar` if `doublequote` is `False`.

quotechar : A one-character string used to quote fields containing special characters, such as the delimiter or `quotechar`, or which contain new-line characters. It defaults to `'"`

quoting : Controls when quotes should be generated by the writer and recognised by the reader. It can take on any of the `QUOTE_*` constants (see section Module Contents) and defaults to `QUOTE_MINIMAL`.

skipinitialspace : When `True`, whitespace immediately following the delimiter is ignored. The default is `False`.

Parameters related to xls file format: Please note the following parameters apply to `pyexcel-xls`. more details can be found in `xlrd.open_workbook()`

logfile: An open file to which messages and diagnostics are written.

verbosity: Increases the volume of trace material written to the logfile.

use_mmap: Whether to use the `mmap` module is determined heuristically. Use this arg to override the result.

Current heuristic: `mmap` is used if it exists.

encoding_override: Used to overcome missing or bad codepage information in older-version files.

formatting_info: The default is `False`, which saves memory.

When `True`, formatting information will be read from the spreadsheet file. This provides all cells, including empty and blank cells. Formatting information is available for each cell.

ragged_rows: The default of `False` means all rows are padded out with empty cells so that all rows have the same size as found in `ncols`.

`True` means that there are no empty cells at the ends of rows. This can result in substantial memory savings if rows are of widely varying sizes. See also the `row_len()` method.

dest_file_name: another file name.

dest_file_type: this is needed if you want to save to memory

dest_session: the target database session

dest_table: the target destination table

dest_model: the target django model

dest_mapdict: a mapping dictionary see `pyexcel.Sheet.save_to_memory()`

dest_initializer: a custom initializer function for table or model

dest_mapdict: nominate headers

dest_batch_size: object creation batch size. it is Django specific

dest_library: choose a specific `pyexcel-io` plugin for writing

dest_source_library: choose a specific data source plugin for writing

dest_renderer_library: choose a `pyexcel` parser plugin for writing

if csv file is destination format, python csv `fmtparams` are accepted

for example: `dest_lineterminator` will replace default `'` to the one you specified

In addition, this function use `pyexcel.Sheet` to render the data which could have performance penalty. In exchange, parameters for `pyexcel.Sheet` can be passed on, e.g. `name_columns_by_row`.

pyexcel.save_book_as

`pyexcel.save_book_as` (**keywords)

Save a book from a data source to another one

Here is a table of parameters:

source	parameters
loading from file	file_name, keywords
loading from string	file_content, file_type, keywords
loading from stream	file_stream, file_type, keywords
loading from sql	session, tables
loading from django models	models
loading from dictionary	bookdict
loading from an url	url

Where the dictionary should have text as keys and two dimensional array as values.

Parameters

file_name : a file with supported file extension

file_content : the file content

file_stream : the file stream

file_type : the file type in `file_content` or `file_stream`

session : database session

tables : a list of database table

models : a list of django models

bookdict : a dictionary of two dimensional arrays

url : a download http url for your excel file

sheets: a list of mixed sheet names and sheet indices to be read. This is done to keep Pandas compactibility.

With this parameter, more than one sheet can be read and you have the control to read the sheets of your interest instead of all available sheets.

auto_detect_float : defaults to True

auto_detect_int : defaults to True

auto_detect_datetime : defaults to True

ignore_infinity : defaults to True

library : choose a specific pyexcel-io plugin for reading

source_library : choose a specific data source plugin for reading

parser_library : choose a pyexcel parser plugin for reading

skip_hidden_sheets: default is True. Please toggle it to read hidden sheets

Parameters related to csv file format

for csv, `fmtparams` are accepted

delimiter : field separator

lineterminator : line terminator

encoding: csv specific. Specify the file encoding the csv file. For example: `encoding='latin1'`. Especially, `encoding='utf-8-sig'` would add utf 8 bom header if used in `renderer`, or would parse a csv with utf bom header used in `parser`.

escapechar : A one-character string used by the writer to escape the delimiter if quoting is set to `QUOTE_NONE` and the `quotechar` if `doublequote` is `False`.

quotechar : A one-character string used to quote fields containing special characters, such as the delimiter or `quotechar`, or which contain new-line characters. It defaults to `'"`

quoting : Controls when quotes should be generated by the writer and recognised by the reader. It can take on any of the `QUOTE_*` constants (see section Module Contents) and defaults to `QUOTE_MINIMAL`.

skipinitialspace : When `True`, whitespace immediately following the delimiter is ignored. The default is `False`.

dest_file_name: another file name.

dest_file_type: this is needed if you want to save to memory

dest_session : the target database session

dest_tables : the list of target destination tables

dest_models : the list of target destination django models

dest_mapdicts : a list of mapping dictionaries

dest_initializers : table initialization functions

dest_mapdicts : to nominate a model or table fields. Optional

dest_batch_size : batch creation size. Optional

Where the dictionary should have text as keys and two dimensional array as values.

Saving to source	parameters
file	<code>dest_file_name</code> , <code>dest_sheet_name</code> , keywords with prefix <code>'dest'</code>
memory	<code>dest_file_type</code> , <code>dest_content</code> , <code>dest_sheet_name</code> , keywords with prefix <code>'dest'</code>
sql	<code>dest_session</code> , <code>dest_tables</code> , <code>dest_table_init_func</code> , <code>dest_mapdict</code>
django model	<code>dest_models</code> , <code>dest_initializers</code> , <code>dest_mapdict</code> , <code>dest_batch_size</code>

The following functions would work with big data and will work every well with `iget_array()` and `iget_records()`.

<code>isave_as(**keywords)</code>	Save a sheet from a data source to another one with less memory
<code>isave_book_as(**keywords)</code>	Save a book from a data source to another one

pyexcel.isave_as

`pyexcel.isave_as(**keywords)`
 Save a sheet from a data source to another one with less memory

It is similar to `pyexcel.save_as()` except that it does not accept parameters for `pyexcel.Sheet`. And it reads when it writes.

It accepts two sets of keywords. Why two sets? one set is source, the other set is destination. In order to distinguish the two sets, source set will be exactly the same as the ones for `pyexcel.get_sheet()`; destination set are exactly the same as the ones for `pyexcel.Sheet.save_as` but require a 'dest' prefix.

Saving to source	parameters
file	dest_file_name, dest_sheet_name, keywords with prefix 'dest'
memory	dest_file_type, dest_content, dest_sheet_name, keywords with prefix 'dest'
sql	dest_session, dest_table, dest_initializer, dest_mapdict
django model	dest_model, dest_initializer, dest_mapdict, dest_batch_size

Not all parameters are needed. Here is a table

source	parameters
loading from file	file_name, sheet_name, keywords
loading from string	file_content, file_type, sheet_name, keywords
loading from stream	file_stream, file_type, sheet_name, keywords
loading from sql	session, table
loading from sql in django	model
loading from query sets	any query sets(sqlalchemy or django)
loading from dictionary	adict, with_keys
loading from records	records
loading from array	array
loading from an url	url

Parameters

file_name : a file with supported file extension

file_content : the file content

file_stream : the file stream

file_type : the file type in *file_content* or *file_stream*

session : database session

table : database table

model: a django model

adict: a dictionary of one dimensional arrays

url : a download http url for your excel file

with_keys : load with previous dictionary's keys, default is True

records : a list of dictionaries that have the same keys

array : a two dimensional array, a list of lists

sheet_name : sheet name. if sheet_name is not given, the default sheet at index 0 is loaded

start_row [int] defaults to 0. It allows you to skip rows at the beginning

row_limit: int defaults to -1, meaning till the end of the whole sheet. It allows you to skip the tailing rows.

start_column [int] defaults to 0. It allows you to skip columns on your left hand side

column_limit: int defaults to -1, meaning till the end of the columns. It allows you to skip the tailing columns.

skip_row_func: It allows you to write your own row skipping functions.

The protocol is to return `pyexcel_io.constants.SKIP_DATA` if skipping data, `pyexcel_io.constants.TAKE_DATA` to read data, `pyexcel_io.constants.STOP_ITERATION` to exit the reading procedure

skip_column_func: It allows you to write your own column skipping functions.

The protocol is to return `pyexcel_io.constants.SKIP_DATA` if skipping data, `pyexcel_io.constants.TAKE_DATA` to read data, `pyexcel_io.constants.STOP_ITERATION` to exit the reading procedure

skip_empty_rows: bool Defaults to False. Toggle it to True if the rest of empty rows are useless, but it does affect the number of rows.

row_renderer: You could choose to write a custom row renderer when the data is being read.

auto_detect_float : defaults to True

auto_detect_int : defaults to True

auto_detect_datetime : defaults to True

ignore_infinity : defaults to True

library : choose a specific pyexcel-io plugin for reading

source_library : choose a specific data source plugin for reading

parser_library : choose a pyexcel parser plugin for reading

skip_hidden_sheets: default is True. Please toggle it to read hidden sheets

Parameters related to csv file format

for csv, `fmtparams` are accepted

delimiter : field separator

lineterminator : line terminator

encoding: csv specific. Specify the file encoding the csv file. For example: `encoding='latin1'`. Especially, `encoding='utf-8-sig'` would add utf 8 bom header if used in renderer, or would parse a csv with utf brom header used in parser.

escapechar : A one-character string used by the writer to escape the delimiter if quoting is set to `QUOTE_NONE` and the `quotechar` if `doublequote` is False.

quotechar : A one-character string used to quote fields containing special characters, such as the delimiter or `quotechar`, or which contain new-line characters. It defaults to `'"`

quoting : Controls when quotes should be generated by the writer and recognised by the reader. It can take on any of the `QUOTE_*` constants (see section Module Contents) and defaults to `QUOTE_MINIMAL`.

skipinitialspace : When True, whitespace immediately following the delimiter is ignored. The default is False.

Parameters related to xls file format: Please note the following parameters apply to pyexcel-xls. more details can be found in `xlrd.open_workbook()`

logfile: An open file to which messages and diagnostics are written.

verbosity: Increases the volume of trace material written to the logfile.

use_mmap: Whether to use the mmap module is determined heuristically. Use this arg to override the result.

Current heuristic: mmap is used if it exists.

encoding_override: Used to overcome missing or bad codepage information in older-version files.

formatting_info: The default is False, which saves memory.

When True, formatting information will be read from the spreadsheet file. This provides all cells, including empty and blank cells. Formatting information is available for each cell.

ragged_rows: The default of False means all rows are padded out with empty cells so that all rows have the same size as found in ncols.

True means that there are no empty cells at the ends of rows. This can result in substantial memory savings if rows are of widely varying sizes. See also the `row_len()` method.

dest_file_name: another file name.

dest_file_type: this is needed if you want to save to memory

dest_session: the target database session

dest_table: the target destination table

dest_model: the target django model

dest_mapdict: a mapping dictionary see `pyexcel.Sheet.save_to_memory()`

dest_initializer: a custom initializer function for table or model

dest_mapdict: nominate headers

dest_batch_size: object creation batch size. it is Django specific

dest_library: choose a specific pyexcel-io plugin for writing

dest_source_library: choose a specific data source plugin for writing

dest_renderer_library: choose a pyexcel parser plugin for writing

if csv file is destination format, python csv `fmtparams` are accepted

for example: `dest_lineterminator` will replace default ‘ ‘ to the one you specified

In addition, this function use `pyexcel.Sheet` to render the data which could have performance penalty. In exchange, parameters for `pyexcel.Sheet` can be passed on, e.g. `name_columns_by_row`.

When you use this function to work on physical files, this function will leave its file handle open. When you finish the operation on its data, you need to call `pyexcel.free_resources()` to close file handle(s).

for csv, csvz file formats, file handles will be left open. for xls, ods file formats, the file is read all into memory and is close afterwards. for xlsx, file handles will be left open in python 2.7 - 3.5 by `pyexcel-xlsx(openpyxl)`. In other words, `pyexcel-xls`, `pyexcel-ods`, `pyexcel-ods3` won't leak file handles.

pyexcel.isave_book_as

`pyexcel.isave_book_as(**keywords)`

Save a book from a data source to another one

It is simliar to `pyexcel.save_book_as()` but it read when it writes. This function provide some speedup but the output data is not made uniform.

Here is a table of parameters:

source	parameters
loading from file	file_name, keywords
loading from string	file_content, file_type, keywords
loading from stream	file_stream, file_type, keywords
loading from sql	session, tables
loading from django models	models
loading from dictionary	bookdict
loading from an url	url

Where the dictionary should have text as keys and two dimensional array as values.

Parameters

file_name : a file with supported file extension

file_content : the file content

file_stream : the file stream

file_type : the file type in *file_content* or *file_stream*

session : database session

tables : a list of database table

models : a list of django models

bookdict : a dictionary of two dimensional arrays

url : a download http url for your excel file

sheets: a list of mixed sheet names and sheet indices to be read. This is done to keep Pandas compactibility.

With this parameter, more than one sheet can be read and you have the control to read the sheets of your interest instead of all available sheets.

auto_detect_float : defaults to True

auto_detect_int : defaults to True

auto_detect_datetime : defaults to True

ignore_infinity : defaults to True

library : choose a specific pyexcel-io plugin for reading

source_library : choose a specific data source plugin for reading

parser_library : choose a pyexcel parser plugin for reading

skip_hidden_sheets: default is True. Please toggle it to read hidden sheets

Parameters related to csv file format

for csv, `fmtparams` are accepted

delimiter : field separator

lineterminator : line terminator

encoding: csv specific. Specify the file encoding the csv file. For example: `encoding='latin1'`. Especially, `encoding='utf-8-sig'` would add utf 8 bom header if used in renderer, or would parse a csv with utf brom header used in parser.

escapechar : A one-character string used by the writer to escape the delimiter if quoting is set to `QUOTE_NONE` and the `quotechar` if `doublequote` is False.

quotechar : A one-character string used to quote fields containing special characters, such as the delimiter or quotechar, or which contain new-line characters. It defaults to ‘”’

quoting : Controls when quotes should be generated by the writer and recognised by the reader. It can take on any of the QUOTE_* constants (see section Module Contents) and defaults to QUOTE_MINIMAL.

skipinitialspace : When True, whitespace immediately following the delimiter is ignored. The default is False.

dest_file_name: another file name.

dest_file_type: this is needed if you want to save to memory

dest_session : the target database session

dest_tables : the list of target destination tables

dest_models : the list of target destination django models

dest_mapdicts : a list of mapping dictionaries

dest_initializers : table initialization functions

dest_mapdicts : to nominate a model or table fields. Optional

dest_batch_size : batch creation size. Optional

Where the dictionary should have text as keys and two dimensional array as values.

Saving to source	parameters
file	dest_file_name, dest_sheet_name, keywords with prefix ‘dest’
memory	dest_file_type, dest_content, dest_sheet_name, keywords with prefix ‘dest’
sql	dest_session, dest_tables, dest_table_init_func, dest_mapdict
django model	dest_models, dest_initializers, dest_mapdict, dest_batch_size

When you use this function to work on physical files, this function will leave its file handle open. When you finish the operation on its data, you need to call `pyexcel.free_resources()` to close file handle(s).

for csv, csvz file formats, file handles will be left open. for xls, ods file formats, the file is read all into memory and is close afterwards. for xlsx, file handles will be left open in python 2.7 - 3.5 by pyexcel-xlsx(openpyxl). In other words, pyexcel-xls, pyexcel-ods, pyexcel-ods3 won’t leak file handles.

If you would only use these two functions to do format transcoding, you may enjoy a speed boost using `isave_as()` and `isave_book_as()`, because they use `yield` keyword and minimize memory footprint. However, you will need to call `free_resources()` to make sure file handles are closed. And `save_as()` and `save_book_as()` reads all data into memory and **will make all rows the same width**.

7.1.2 Cookbook

<code>merge_csv_to_a_book(filelist[, outfile_name])</code>	merge a list of csv files into a excel book
<code>merge_all_to_a_book(filelist[, outfile_name])</code>	merge a list of excel files into a excel book
<code>split_a_book(file_name[, outfile_name])</code>	Split a file into separate sheets
<code>extract_a_sheet_from_a_book(file_name, sheetname)</code>	Extract a sheet from a excel book

pyexcel.merge_csv_to_a_book

`pyexcel.merge_csv_to_a_book(filelist, outfile_name='merged.xls')`
merge a list of csv files into a excel book

Parameters

- **filelist** (*list*) – a list of accessible file path
- **outfilename** (*str*) – save the sheet as

pyexcel.merge_all_to_a_book

`pyexcel.merge_all_to_a_book` (*filelist*, *outfilename='merged.xls'*)
merge a list of excel files into a excel book

Parameters

- **filelist** (*list*) – a list of accessible file path
- **outfilename** (*str*) – save the sheet as

pyexcel.split_a_book

`pyexcel.split_a_book` (*file_name*, *outfilename=None*)
Split a file into separate sheets

Parameters

- **file_name** (*str*) – an accessible file name
- **outfilename** (*str*) – save the sheets with file suffix

pyexcel.extract_a_sheet_from_a_book


`pyexcel.extract_a_sheet_from_a_book` (*file_name*, *sheetname*, *outfilename=None*)
Extract a sheet from a excel book

Parameters

- **file_name** (*str*) – an accessible file name
- **sheetname** (*str*) – a valid sheet name
- **outfilename** (*str*) – save the sheet as

7.1.3 Book

Here's the entity relationship between Book, Sheet, Row and Column



Constructor

`Book([sheets, filename, path])`

Read an excel book that has one or more sheets

pyexcel.Book

class `pyexcel.Book` (*sheets=None, filename='memory', path=None*)

Read an excel book that has one or more sheets

For csv file, there will be just one sheet

`__init__` (*sheets=None, filename='memory', path=None*)

Book constructor

Selecting a specific book according to filename extension

Parameters

- **sheets** – a dictionary of data
- **filename** – the physical file
- **path** – the relative path or absolute path
- **keywords** – additional parameters to be passed on

Methods

<code>__init__([sheets, filename, path])</code>	Book constructor
<code>get_array(**keywords)</code>	Get data in array format
<code>get_bookdict(**keywords)</code>	Get data in bookdict format
<code>get_csv(**keywords)</code>	Get data in csv format
<code>get_csvz(**keywords)</code>	Get data in csvz format
<code>get_dict(**keywords)</code>	Get data in dict format
<code>Book.get_echarts_html</code>	
<code>get_fods(**_)</code>	fods getter is not defined.
<code>Book.get_gantt_html</code>	
<code>Book.get_grid</code>	
<code>get_handsonable_html(**keywords)</code>	Get data in handsonable.html format
<code>Book.get_html</code>	
<code>Book.get_json</code>	
<code>Book.get_latex</code>	
<code>Book.get_latex_booktabs</code>	
<code>Book.get_mediawiki</code>	
<code>Book.get_ndjson</code>	
<code>get_ods(**keywords)</code>	Get data in ods format
<code>Book.get_orgtbl</code>	
<code>Book.get_pdf</code>	
<code>Book.get_pipe</code>	
<code>Book.get_plain</code>	
<code>get_records(**keywords)</code>	Get data in records format
<code>Book.get_rst</code>	
<code>Book.get_simple</code>	
<code>Book.get_sortable_html</code>	
<code>get_svg(**keywords)</code>	Get data in svg format
<code>get_texttable(**keywords)</code>	Get data in texttable format
<code>get_tsv(**keywords)</code>	Get data in tsv format
<code>get_tsvz(**keywords)</code>	Get data in tsvz format
<code>get_url(**_)</code>	url getter is not defined.
<code>get_xls(**keywords)</code>	Get data in xls format
<code>get_xlsm(**keywords)</code>	Get data in xlsm format
<code>get_xlsx(**keywords)</code>	Get data in xlsx format
<code>init([sheets, filename, path])</code>	independent function so that it could be called multiple times
<code>load_from_sheets(sheets)</code>	Load content from existing sheets
<code>number_of_sheets()</code>	Return the number of sheets
<code>register_input(file_type)</code>	partial(func, *args, **keywords) - new function with partial application of the given arguments and keywords.
<code>register_io(file_type)</code>	partial(func, *args, **keywords) - new function with partial application of the given arguments and keywords.
<code>register_presentation(file_type[, ...])</code>	partial(func, *args, **keywords) - new function with partial application of the given arguments and keywords.
<code>remove_sheet(sheet)</code>	Remove a sheet

Continued on next page

Table 8 – continued from previous page

<code>save_as(filename, **keywords)</code>	Save the content to a new file
<code>save_to_database(session, tables[, ...])</code>	Save data in sheets to database tables
<code>save_to_django_models(models[, ...])</code>	Save to database table through django model
<code>save_to_memory(file_type[, stream])</code>	Save the content to a memory stream
<code>set_array(content, **keywords)</code>	Set data in array format
<code>set_bookdict(content, **keywords)</code>	Set data in bookdict format
<code>set_csv(content, **keywords)</code>	Set data in csv format
<code>set_csvz(content, **keywords)</code>	Set data in csvz format
<code>set_dict(content, **keywords)</code>	Set data in dict format
<code>Book.set_echarts_html</code>	
<code>set_fods(content, **keywords)</code>	Set data in fods format
<code>Book.set_gantt_html</code>	
<code>Book.set_grid</code>	
<code>set_handsontable_html(_y, **_z)</code>	handsontable.html setter is not defined.
<code>Book.set_html</code>	
<code>Book.set_json</code>	
<code>Book.set_latex</code>	
<code>Book.set_latex_booktabs</code>	
<code>Book.set_mediawiki</code>	
<code>Book.set_ndjson</code>	
<code>set_ods(content, **keywords)</code>	Set data in ods format
<code>Book.set Orgtbl</code>	
<code>Book.set_pdf</code>	
<code>Book.set_pipe</code>	
<code>Book.set_plain</code>	
<code>set_records(content, **keywords)</code>	Set data in records format
<code>Book.set_rst</code>	
<code>Book.set_simple</code>	
<code>Book.set_sortable_html</code>	
<code>set_svg(_y, **_z)</code>	svg setter is not defined.
<code>set_texttable(_y, **_z)</code>	texttable setter is not defined.
<code>set_tsv(content, **keywords)</code>	Set data in tsv format
<code>set_tsvz(content, **keywords)</code>	Set data in tsvz format
<code>set_url(content, **keywords)</code>	Set data in url format
<code>set_xls(content, **keywords)</code>	Set data in xls format
<code>set_xlsm(content, **keywords)</code>	Set data in xlsm format
<code>set_xlsx(content, **keywords)</code>	Set data in xlsx format
<code>sheet_by_index(index)</code>	Get the sheet with the specified index
<code>sheet_by_name(name)</code>	Get the sheet with the specified name
<code>sheet_names()</code>	Return all sheet names
<code>to_dict()</code>	Convert the book to a dictionary

Attributes

<code>array</code>	Get/Set data in/from array format
<code>bookdict</code>	Get/Set data in/from bookdict format
<code>csv</code>	Get/Set data in/from csv format
<code>csvz</code>	Get/Set data in/from csvz format
<code>dict</code>	Get/Set data in/from dict format

Continued on next page

Table 9 – continued from previous page

<code>Book.echarts_html</code>	
<code>fods</code>	Set data in fods format
<code>Book.gantt_html</code>	
<code>Book.grid</code>	
<code>handsontable_html</code>	Get data in handsontable.html format
<code>Book.html</code>	
<code>Book.json</code>	
<code>Book.latex</code>	
<code>Book.latex_booktabs</code>	
<code>Book.mediawiki</code>	
<code>Book.ndjson</code>	
<code>ods</code>	Get/Set data in/from ods format
<code>Book.orgtbl</code>	
<code>Book.pdf</code>	
<code>Book.pipe</code>	
<code>Book.plain</code>	
<code>plot([file_type])</code>	Visualize the data
<code>records</code>	Get/Set data in/from records format
<code>Book.rst</code>	
<code>Book.simple</code>	
<code>Book.sortable_html</code>	
<code>stream</code>	Return a stream in which the content is properly encoded
<code>svg</code>	Get data in svg format
<code>texttable</code>	Get data in texttable format
<code>tsv</code>	Get/Set data in/from tsv format
<code>tsvz</code>	Get/Set data in/from tsvz format
<code>url</code>	Set data in url format
<code>xls</code>	Get/Set data in/from xls format
<code>xlsm</code>	Get/Set data in/from xlsm format
<code>xlsx</code>	Get/Set data in/from xlsx format

Attribute

<code>Book.number_of_sheets()</code>	Return the number of sheets
<code>Book.sheet_names()</code>	Return all sheet names

pyexcel.Book.number_of_sheets

`Book.number_of_sheets()`
Return the number of sheets

pyexcel.Book.sheet_names

`Book.sheet_names()`
Return all sheet names

Conversions

<code>Book.bookdict</code>	Get/Set data in/from bookdict format
<code>Book.url</code>	Set data in url format
<code>Book.csv</code>	Get/Set data in/from csv format
<code>Book.tsv</code>	Get/Set data in/from tsv format
<code>Book.csvz</code>	Get/Set data in/from csvz format
<code>Book.tsvz</code>	Get/Set data in/from tszv format
<code>Book.xls</code>	Get/Set data in/from xls format
<code>Book.xlsm</code>	Get/Set data in/from xlsm format
<code>Book.xlsx</code>	Get/Set data in/from xlsx format
<code>Book.ods</code>	Get/Set data in/from ods format
<code>Book.stream</code>	Return a stream in which the content is properly encoded

pyexcel.Book.bookdict

Book.bookdict

Get/Set data in/from bookdict format

You could obtain content in bookdict format by dot notation:

```
Book.bookdict
```

And you could as well set content by dot notation:

```
Book.bookdict = the_io_stream_in_bookdict_format
```

if you need to pass on more parameters, you could use:

```
Book.get_bookdict(**keywords)
Book.set_bookdict(the_io_stream_in_bookdict_format, **keywords)
```

pyexcel.Book.url

Book.url

Set data in url format

You could set content in url format by dot notation:

```
Book.url
```

if you need to pass on more parameters, you could use:

```
Book.set_url(the_io_stream_in_url_format, **keywords)
```

pyexcel.Book.csv

Book.csv

Get/Set data in/from csv format

You could obtain content in csv format by dot notation:

```
Book.csv
```

And you could as well set content by dot notation:

```
Book.csv = the_io_stream_in_csv_format
```

if you need to pass on more parameters, you could use:

```
Book.get_csv(**keywords)
Book.set_csv(the_io_stream_in_csv_format, **keywords)
```

pyexcel.Book.tsv

Book.**tsv**

Get/Set data in/from tsv format

You could obtain content in tsv format by dot notation:

```
Book.tsv
```

And you could as well set content by dot notation:

```
Book.tsv = the_io_stream_in_tsv_format
```

if you need to pass on more parameters, you could use:

```
Book.get_tsv(**keywords)
Book.set_tsv(the_io_stream_in_tsv_format, **keywords)
```

pyexcel.Book.csvz

Book.**csvz**

Get/Set data in/from csvz format

You could obtain content in csvz format by dot notation:

```
Book.csvz
```

And you could as well set content by dot notation:

```
Book.csvz = the_io_stream_in_csvz_format
```

if you need to pass on more parameters, you could use:

```
Book.get_csvz(**keywords)
Book.set_csvz(the_io_stream_in_csvz_format, **keywords)
```

pyexcel.Book.tsvz

Book.**tsvz**

Get/Set data in/from tsvz format

You could obtain content in tsvz format by dot notation:

```
Book.tsvz
```

And you could as well set content by dot notation:

```
Book.tsvz = the_io_stream_in_tsvz_format
```

if you need to pass on more parameters, you could use:

```
Book.get_tsvz(**keywords)
Book.set_tsvz(the_io_stream_in_tsvz_format, **keywords)
```

pyexcel.Book.xls

Book.**.xls**

Get/Set data in/from xls format

You could obtain content in xls format by dot notation:

```
Book.xls
```

And you could as well set content by dot notation:

```
Book.xls = the_io_stream_in_xls_format
```

if you need to pass on more parameters, you could use:

```
Book.get_xls(**keywords)
Book.set_xls(the_io_stream_in_xls_format, **keywords)
```

pyexcel.Book.xlsxm

Book.**.xlsxm**

Get/Set data in/from xlsxm format

You could obtain content in xlsxm format by dot notation:

```
Book.xlsxm
```

And you could as well set content by dot notation:

```
Book.xlsxm = the_io_stream_in_xlsxm_format
```

if you need to pass on more parameters, you could use:

```
Book.get_xlsxm(**keywords)
Book.set_xlsxm(the_io_stream_in_xlsxm_format, **keywords)
```

pyexcel.Book.xlsx

Book.**.xlsx**

Get/Set data in/from xlsx format

You could obtain content in xlsx format by dot notation:

```
Book.xlsx
```

And you could as well set content by dot notation:

```
Book.xlsx = the_io_stream_in_xlsx_format
```

if you need to pass on more parameters, you could use:

```
Book.get_xlsx(**keywords)
Book.set_xlsx(the_io_stream_in_xlsx_format, **keywords)
```

pyexcel.Book.ods

Book.ods

Get/Set data in/from ods format

You could obtain content in ods format by dot notation:

```
Book.ods
```

And you could as well set content by dot notation:

```
Book.ods = the_io_stream_in_ods_format
```

if you need to pass on more parameters, you could use:

```
Book.get_ods(**keywords)
Book.set_ods(the_io_stream_in_ods_format, **keywords)
```

pyexcel.Book.stream

Book.stream

Return a stream in which the content is properly encoded

Example:

```
>>> import pyexcel as p
>>> b = p.get_book(bookdict={"A": [[1]]})
>>> csv_stream = b.stream.texttable
>>> print(csv_stream.getvalue())
A:
+----+
| 1 |
+----+
```

Where `b.stream.xls.getvalue()` is equivalent to `b.xls`. In some situation `b.stream.xls` is preferred than `b.xls`.

Sheet examples:

```
>>> import pyexcel as p
>>> s = p.Sheet([[1]], 'A')
>>> csv_stream = s.stream.texttable
>>> print(csv_stream.getvalue())
A:
```

(continues on next page)

(continued from previous page)

```
+----+
|  1  |
+----+
```

Where `s.stream.xls.getvalue()` is equivalent to `s.xls`. In some situation `s.stream.xls` is preferred than `s.xls`.

It is similar to `save_to_memory()`.

Save changes

<code>Book.save_as(filename, **keywords)</code>	Save the content to a new file
<code>Book.save_to_memory(file_type[, stream])</code>	Save the content to a memory stream
<code>Book.save_to_database(session, tables[, ...])</code>	Save data in sheets to database tables
<code>Book.save_to_django_models(models[, ...])</code>	Save to database table through django model

pyexcel.Book.save_as

`Book.save_as(filename, **keywords)`

Save the content to a new file

Keywords may vary depending on your file type, because the associated file type employs different library.

PARAMETERS

filename: a file path

library: choose a specific pyexcel-io plugin for writing

renderer_library: choose a pyexcel parser plugin for writing

Parameters related to csv file format

for csv, `fmtparams` are accepted

delimiter : field separator

lineterminator : line terminator

encoding: csv specific. Specify the file encoding the csv file. For example: `encoding='latin1'`. Especially, `encoding='utf-8-sig'` would add utf 8 bom header if used in renderer, or would parse a csv with utf brom header used in parser.

escapechar : A one-character string used by the writer to escape the delimiter if quoting is set to `QUOTE_NONE` and the `quotechar` if `doublequote` is `False`.

quotechar : A one-character string used to quote fields containing special characters, such as the delimiter or `quotechar`, or which contain new-line characters. It defaults to `''''`

quoting : Controls when quotes should be generated by the writer and recognised by the reader. It can take on any of the `QUOTE_*` constants (see section Module Contents) and defaults to `QUOTE_MINIMAL`.

skipinitialspace : When `True`, whitespace immediately following the delimiter is ignored. The default is `False`.

pyexcel.Book.save_to_memory

`Book.save_to_memory(file_type, stream=None, **keywords)`

Save the content to a memory stream

Parameters

- **file_type** – what format the stream is in
- **stream** – a memory stream. Note in Python 3, for csv and tsv format, please pass an instance of StringIO. For xls, xlsx, and ods, an instance of BytesIO.

pyexcel.Book.save_to_database

Book.**save_to_database** (*session, tables, initializers=None, mapdicts=None, auto_commit=True*)

Save data in sheets to database tables

Parameters

- **session** – database session
- **tables** – a list of database tables, that is accepted by `Sheet.save_to_database()`. The sequence of tables matters when there is dependencies in between the tables. For example, **Car** is made by **Car Maker**. **Car Maker** table should be specified before **Car** table.
- **initializers** – a list of initialization functions for your tables and the sequence should match tables,
- **mapdicts** – custom map dictionary for your data columns and the sequence should match tables
- **auto_commit** – by default, data is committed.

pyexcel.Book.save_to_django_models

Book.**save_to_django_models** (*models, initializers=None, mapdicts=None, **keywords*)

Save to database table through django model

Parameters

- **models** – a list of database models, that is accepted by `Sheet.save_to_django_model()`. The sequence of tables matters when there is dependencies in between the tables. For example, **Car** is made by **Car Maker**. **Car Maker** table should be specified before **Car** table.
- **initializers** – a list of initialization functions for your tables and the sequence should match tables,
- **mapdicts** – custom map dictionary for your data columns and the sequence should match tables

optional parameters: :param batch_size: django bulk_create batch size :param bulk_save: whether to use bulk_create or to use single save

per record

7.1.4 Sheet

Constructor

<code>Sheet(sheet, name, name_columns_by_row, ...)</code>	Two dimensional data container for filtering, formatting and iteration
---	--

pyexcel.Sheet

```
class pyexcel.Sheet (sheet=None, name='pyexcel sheet', name_columns_by_row=-1,
                    name_rows_by_column=-1, colnames=None, rownames=None, trans-
                    pose_before=False, transpose_after=False)
```

Two dimensional data container for filtering, formatting and iteration

`Sheet` is a container for a two dimensional array, where individual cell can be any Python types. Other than numbers, value of these types: string, date, time and boolean can be mixed in the array. This differs from Numpy's matrix where each cell are of the same number type.

In order to prepare two dimensional data for your computation, formatting functions help convert array cells to required types. Formatting can be applied not only to the whole sheet but also to selected rows or columns. Custom conversion function can be passed to these formatting functions. For example, to remove extra spaces surrounding the content of a cell, a custom function is required.

Filtering functions are used to reduce the information contained in the array.

Variables

- **name** – sheet name. use to change sheet name
- **row** – access data row by row
- **column** – access data column by column

Example:

```
>>> import pyexcel as p
>>> content = {'A': [[1]]}
>>> b = p.get_book(bookdict=content)
>>> b
A:
+----+
| 1 |
+----+
>>> b[0].name
'A'
>>> b[0].name = 'B'
>>> b
B:
+----+
| 1 |
+----+
```

```
__init__(sheet=None, name='pyexcel sheet', name_columns_by_row=-1, name_rows_by_column=-1,
        colnames=None, rownames=None, transpose_before=False, transpose_after=False)
Constructor
```

Parameters

- **sheet** – two dimensional array
- **name** – this becomes the sheet name.
- **name_columns_by_row** – use a row to name all columns
- **name_rows_by_column** – use a column to name all rows

- **colnames** – use an external list of strings to name the columns
- **rownames** – use an external list of strings to name the rows

Methods

<code>__init__</code> ([sheet, name, name_columns_by_row, ...])	Constructor
<code>cell_value</code> (row, column[, new_value])	Random access to table cells
<code>column_at</code> (index)	Gets the data at the specified column
<code>column_range</code> ()	Utility function to get column range
<code>columns</code> ()	Returns a left to right column iterator
<code>contains</code> (predicate)	Has something in the table
<code>cut</code> (topleft_corner, bottomright_corner)	Get a rectangle shaped data out and clear them in position
<code>delete_columns</code> (column_indices)	Delete one or more columns
<code>delete_named_column_at</code> (name)	Works only after you named columns by a row
<code>delete_named_row_at</code> (name)	Take the first column as row names
<code>delete_rows</code> (row_indices)	Delete one or more rows
<code>enumerate</code> ()	Iterate cell by cell from top to bottom and from left to right
<code>extend_columns</code> (columns)	Take ordereddict to extend named columns
<code>extend_columns_with_rows</code> (rows)	Put rows on the right most side of the data
<code>extend_rows</code> (rows)	Take ordereddict to extend named rows
<code>filter</code> ([column_indices, row_indices])	Apply the filter with immediate effect
<code>format</code> (formatter)	Apply a formatting action for the whole sheet
<code>get_array</code> (**keywords)	Get data in array format
<code>get_bookdict</code> (**keywords)	Get data in bookdict format
<code>get_csv</code> (**keywords)	Get data in csv format
<code>get_csvz</code> (**keywords)	Get data in csvz format
<code>get_dict</code> (**keywords)	Get data in dict format
<code>Sheet.get_echarts_html</code>	
<code>get_fods</code> (**_)	fods getter is not defined.
<code>Sheet.get_gantt_html</code>	
<code>Sheet.get_grid</code>	
<code>get_handsontable_html</code> (**keywords)	Get data in handsontable.html format
<code>Sheet.get_html</code>	
<code>get_internal_array</code> ()	present internal array
<code>Sheet.get_json</code>	
<code>Sheet.get_latex</code>	
<code>Sheet.get_latex_booktabs</code>	
<code>Sheet.get_mediawiki</code>	
<code>Sheet.get_ndjson</code>	
<code>get_ods</code> (**keywords)	Get data in ods format
<code>Sheet.get Orgtbl</code>	
<code>Sheet.get_pdf</code>	
<code>Sheet.get_pipe</code>	
<code>Sheet.get_plain</code>	
<code>get_records</code> (**keywords)	Get data in records format
<code>Sheet.get_rst</code>	

Continued on next page

Table 14 – continued from previous page

<code>Sheet.get_simple</code>	
<code>Sheet.get_sortable_html</code>	
<code>get_svg(**keywords)</code>	Get data in svg format
<code>get_texttable(**keywords)</code>	Get data in texttable format
<code>get_tsv(**keywords)</code>	Get data in tsv format
<code>get_tsvz(**keywords)</code>	Get data in tsvz format
<code>get_url(**_)</code>	url getter is not defined.
<code>get_xls(**keywords)</code>	Get data in xls format
<code>get_xlsm(**keywords)</code>	Get data in xlsm format
<code>get_xlsx(**keywords)</code>	Get data in xlsx format
<code>Sheet.group_rows_by_column</code>	
<code>init([sheet, name, name_columns_by_row, ...])</code>	custom initialization functions
<code>map(custom_function)</code>	Execute a function across all cells of the sheet
<code>name_columns_by_row(row_index)</code>	Use the elements of a specified row to represent individual columns
<code>name_rows_by_column(column_index)</code>	Use the elements of a specified column to represent individual rows
<code>named_column_at(name)</code>	Get a column by its name
<code>named_columns()</code>	iterate rows using column names
<code>named_row_at(name)</code>	Get a row by its name
<code>named_rows()</code>	iterate rows using row names
<code>number_of_columns()</code>	The number of columns
<code>number_of_rows()</code>	The number of rows
<code>paste(topleft_corner[, rows, columns])</code>	Paste a rectangle shaped data after a position
<code>rcolumns()</code>	Returns a right to left column iterator
<code>region(topleft_corner, bottomright_corner)</code>	Get a rectangle shaped data out
<code>register_input(file_type[, instance_name])</code>	<code>partial(func, *args, **keywords)</code> - new function with partial application of the given arguments and keywords.
<code>register_io(file_type[, presenter_func, ...])</code>	<code>partial(func, *args, **keywords)</code> - new function with partial application of the given arguments and keywords.
<code>register_presentation(file_type[, ...])</code>	
<code>reverse()</code>	Opposite to enumerate
<code>row_at(index)</code>	Gets the data at the specified row
<code>row_range()</code>	Utility function to get row range
<code>rows()</code>	Returns a top to bottom row iterator
<code>rrows()</code>	Returns a bottom to top row iterator
<code>rvertical()</code>	Default iterator to go through each cell one by one from rightmost column to leftmost row and from bottom to top example.
<code>save_as(filename, **keywords)</code>	Save the content to a named file
<code>save_to_database(session, table[, ...])</code>	Save data in sheet to database table
<code>save_to_django_model(model[, initializer, ...])</code>	Save to database table through django model
<code>save_to_memory(file_type[, stream])</code>	Save the content to memory
<code>set_array(content, **keywords)</code>	Set data in array format
<code>set_bookdict(content, **keywords)</code>	Set data in bookdict format
<code>set_column_at(column_index, data_array[, ...])</code>	Updates a column data range
<code>set_csv(content, **keywords)</code>	Set data in csv format

Continued on next page

Table 14 – continued from previous page

<code>set_csvz(content, **keywords)</code>	Set data in csvz format
<code>set_dict(content, **keywords)</code>	Set data in dict format
<code>Sheet.set_echarts_html</code>	
<code>set_fods(content, **keywords)</code>	Set data in fods format
<code>Sheet.set_gantt_html</code>	
<code>Sheet.set_grid</code>	
<code>set_handsontable_html(_y, *_z)</code>	handsontable.html setter is not defined.
<code>Sheet.set_html</code>	
<code>Sheet.set_json</code>	
<code>Sheet.set_latex</code>	
<code>Sheet.set_latex_booktabs</code>	
<code>Sheet.set_mediawiki</code>	
<code>set_named_column_at(name, column_array)</code>	Take the first row as column names
<code>set_named_row_at(name, row_array)</code>	Take the first column as row names
<code>Sheet.set_ndjson</code>	
<code>set_ods(content, **keywords)</code>	Set data in ods format
<code>Sheet.set_orgtbl</code>	
<code>Sheet.set_pdf</code>	
<code>Sheet.set_pipe</code>	
<code>Sheet.set_plain</code>	
<code>set_records(content, **keywords)</code>	Set data in records format
<code>set_row_at(row_index, data_array)</code>	Update a row data range
<code>Sheet.set_rst</code>	
<code>Sheet.set_simple</code>	
<code>Sheet.set_sortable_html</code>	
<code>set_svg(_y, *_z)</code>	svg setter is not defined.
<code>set_texttable(_y, *_z)</code>	texttable setter is not defined.
<code>set_tsv(content, **keywords)</code>	Set data in tsv format
<code>set_tsvz(content, **keywords)</code>	Set data in tsvz format
<code>set_url(content, **keywords)</code>	Set data in url format
<code>set_xls(content, **keywords)</code>	Set data in xls format
<code>set_xlsm(content, **keywords)</code>	Set data in xlsm format
<code>set_xlsx(content, **keywords)</code>	Set data in xlsx format
<code>to_array()</code>	Returns an array after filtering
<code>to_dict([row])</code>	Returns a dictionary
<code>to_records([custom_headers])</code>	Make an array of dictionaries
<code>top([lines])</code>	Preview top most 5 rows
<code>top_left([rows, columns])</code>	Preview top corner: 5x5
<code>transpose()</code>	Rotate the data table by 90 degrees
<code>vertical()</code>	Default iterator to go through each cell one by one from leftmost column to rightmost row and from top to bottom example.

Attributes

<code>array</code>	Get/Set data in/from array format
<code>bookdict</code>	Get/Set data in/from bookdict format
<code>colnames</code>	Return column names if any
<code>content</code>	Plain representation without headers

Continued on next page

Table 15 – continued from previous page

<i>csv</i>	Get/Set data in/from csv format
<i>csvz</i>	Get/Set data in/from csvz format
<i>dict</i>	Get/Set data in/from dict format
Sheet.echarts_html	
fods	Set data in fods format
Sheet.gantt_html	
Sheet.grid	
handsontable_html	Get data in handsontable.html format
Sheet.html	
Sheet.json	
Sheet.latex	
Sheet.latex_booktabs	
Sheet.mediawiki	
Sheet.ndjson	
<i>ods</i>	Get/Set data in/from ods format
Sheet.orgtbl	
Sheet.pdf	
Sheet.pipe	
Sheet.plain	
plot([file_type])	Visualize the data
<i>records</i>	Get/Set data in/from records format
<i>rownames</i>	Return row names if any
Sheet.rst	
Sheet.simple	
Sheet.sortable_html	
<i>stream</i>	Return a stream in which the content is properly encoded
svg	Get data in svg format
texttable	Get data in texttable format
<i>tsv</i>	Get/Set data in/from tsv format
<i>tsvz</i>	Get/Set data in/from tsvz format
<i>url</i>	Set data in url format
<i>xls</i>	Get/Set data in/from xls format
<i>xlsm</i>	Get/Set data in/from xlsm format
<i>xlsx</i>	Get/Set data in/from xlsx format

Attributes

<i>Sheet.content</i>	Plain representation without headers
<i>Sheet.number_of_rows()</i>	The number of rows
<i>Sheet.number_of_columns()</i>	The number of columns
<i>Sheet.row_range()</i>	Utility function to get row range
<i>Sheet.column_range()</i>	Utility function to get column range

pyexcel.Sheet.content

Sheet.content

Plain representation without headers

pyexcel.Sheet.number_of_rows

Sheet.**number_of_rows** ()
The number of rows

pyexcel.Sheet.number_of_columns

Sheet.**number_of_columns** ()
The number of columns

pyexcel.Sheet.row_range

Sheet.**row_range** ()
Utility function to get row range

pyexcel.Sheet.column_range

Sheet.**column_range** ()
Utility function to get column range

Iteration

<i>Sheet.rows()</i>	Returns a top to bottom row iterator
<i>Sheet.rrows()</i>	Returns a bottom to top row iterator
<i>Sheet.columns()</i>	Returns a left to right column iterator
<i>Sheet.rcolumns()</i>	Returns a right to left column iterator
<i>Sheet.enumerate()</i>	Iterate cell by cell from top to bottom and from left to right
<i>Sheet.reverse()</i>	Opposite to enumerate
<i>Sheet.vertical()</i>	Default iterator to go through each cell one by one from leftmost column to rightmost row and from top to bottom example.
<i>Sheet.rvertical()</i>	Default iterator to go through each cell one by one from rightmost column to leftmost row and from bottom to top example.

pyexcel.Sheet.rows

Sheet.**rows** ()
Returns a top to bottom row iterator

example:

```
import pyexcel as pe
data = [
    [1, 2, 3, 4],
    [5, 6, 7, 8],
    [9, 10, 11, 12]
]
```

(continues on next page)

(continued from previous page)

```
m = pe.internal.sheets.Matrix(data)
print(pe.utils.to_array(m.rows()))
```

output:

```
[[1, 2, 3, 4], [5, 6, 7, 8], [9, 10, 11, 12]]
```

More details see RowIterator

pyexcel.Sheet.rows

Sheet.**rows**()

Returns a bottom to top row iterator

```
import pyexcel as pe
data = [
    [1, 2, 3, 4],
    [5, 6, 7, 8],
    [9, 10, 11, 12]
]
m = pe.internal.sheets.Matrix(data)
print(pe.utils.to_array(m.rows()))
```

```
[[9, 10, 11, 12], [5, 6, 7, 8], [1, 2, 3, 4]]
```

More details see RowReverseIterator

pyexcel.Sheet.columns

Sheet.**columns**()

Returns a left to right column iterator

```
import pyexcel as pe
data = [
    [1, 2, 3, 4],
    [5, 6, 7, 8],
    [9, 10, 11, 12]
]
m = pe.internal.sheets.Matrix(data)
print(list(m.columns()))
```

```
[[1, 5, 9], [2, 6, 10], [3, 7, 11], [4, 8, 12]]
```

More details see ColumnIterator

pyexcel.Sheet.rcolumns

Sheet.**rcolumns**()

Returns a right to left column iterator

example:

```
import pyexcel as pe
data = [
    [1, 2, 3, 4],
    [5, 6, 7, 8],
    [9, 10, 11, 12]
]
m = pe.internal.sheets.Matrix(data)
print(pe.utils.to_array(m.rcolumns()))
```

output:

```
[[4, 8, 12], [3, 7, 11], [2, 6, 10], [1, 5, 9]]
```

More details see `ColumnReverseIterator`

pyexcel.Sheet.enumerate

Sheet.**enumerate**()

Iterate cell by cell from top to bottom and from left to right

```
>>> import pyexcel as pe
>>> data = [
...     [1, 2, 3, 4],
...     [5, 6, 7, 8],
...     [9, 10, 11, 12]
... ]
>>> m = pe.internal.sheets.Matrix(data)
>>> print(list(m.enumerate()))
[1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12]
```

More details see `HTLBRIterator`

pyexcel.Sheet.reverse

Sheet.**reverse**()

Opposite to `enumerate`

each cell one by one from bottom row to top row and from right to left example:

```
>>> import pyexcel as pe
>>> data = [
...     [1, 2, 3, 4],
...     [5, 6, 7, 8],
...     [9, 10, 11, 12]
... ]
>>> m = pe.internal.sheets.Matrix(data)
>>> print(list(m.reverse()))
[12, 11, 10, 9, 8, 7, 6, 5, 4, 3, 2, 1]
```

More details see `HBRTLIterator`

pyexcel.Sheet.vertical

Sheet.**vertical**()

Default iterator to go through each cell one by one from leftmost column to rightmost row and from top to bottom example:

```
import pyexcel as pe
data = [
    [1, 2, 3, 4],
    [5, 6, 7, 8],
    [9, 10, 11, 12]
]
m = pe.internal.sheets.Matrix(data)
print(list(m.vertical()))
```

output:

```
[1, 5, 9, 2, 6, 10, 3, 7, 11, 4, 8, 12]
```

More details see VTLBRIterator

pyexcel.Sheet.rvertical

Sheet.**rvertical**()

Default iterator to go through each cell one by one from rightmost column to leftmost row and from bottom to top example:

```
import pyexcel as pe
data = [
    [1, 2, 3, 4],
    [5, 6, 7, 8],
    [9, 10, 11, 12]
]
m = pe.internal.sheets.Matrix(data)
print(pe.utils.to_array(m.rvertical()))
```

output:

```
[12, 8, 4, 11, 7, 3, 10, 6, 2, 9, 5, 1]
```

More details see VBRTLIterator

Cell access

<code>Sheet.cell_value(row, column[, new_value])</code>	Random access to table cells
<code>Sheet.__getitem__(aset)</code>	By default, this class recognize from top to bottom from left to right

pyexcel.Sheet.cell_value

Sheet.**cell_value**(row, column, new_value=None)

Random access to table cells

Parameters

- **row** (*int*) – row index which starts from 0
- **column** (*int*) – column index which starts from 0
- **new_value** (*any*) – new value if this is to set the value

pyexcel.Sheet.__getitem__

Sheet.**__getitem__** (*aset*)

By default, this class recognize from top to bottom from left to right

Row access

<i>Sheet.row_at</i> (index)	Gets the data at the specified row
<i>Sheet.set_row_at</i> (row_index, data_array)	Update a row data range
<i>Sheet.delete_rows</i> (row_indices)	Delete one or more rows
<i>Sheet.extend_rows</i> (rows)	Take ordereddict to extend named rows

pyexcel.Sheet.row_at

Sheet.**row_at** (*index*)

Gets the data at the specified row

pyexcel.Sheet.set_row_at

Sheet.**set_row_at** (*row_index, data_array*)

Update a row data range

pyexcel.Sheet.delete_rows

Sheet.**delete_rows** (*row_indices*)

Delete one or more rows

Parameters **row_indices** (*list*) – a list of row indices

pyexcel.Sheet.extend_rows

Sheet.**extend_rows** (*rows*)

Take ordereddict to extend named rows

Parameters **rows** (*ordereddict/list*) – a list of rows.

Column access

<i>Sheet.column_at</i> (index)	Gets the data at the specified column
--------------------------------	---------------------------------------

Continued on next page

Table 20 – continued from previous page

<code>Sheet.set_column_at(column_index, data_array)</code>	Updates a column data range
<code>Sheet.delete_columns(column_indices)</code>	Delete one or more columns
<code>Sheet.extend_columns(columns)</code>	Take ordereddict to extend named columns

pyexcel.Sheet.column_at

`Sheet.column_at(index)`

Gets the data at the specified column

pyexcel.Sheet.set_column_at

`Sheet.set_column_at(column_index, data_array, starting=0)`

Updates a column data range

It works like this if the call is: `set_column_at(2, ['N','N', 'N'], 1)`:

```

++-> column_index = 2
    |
A B C
1 3 N <- starting = 1
2 4 N

```

This function will not set element outside the current table range

Parameters

- **column_index** (*int*) – which column to be modified
- **data_array** (*list*) – one dimensional array
- **starting** (*int*) – from which index, the update happens

Raises `IndexError` – if `column_index` exceeds column range or `starting` exceeds row range

pyexcel.Sheet.delete_columns

`Sheet.delete_columns(column_indices)`

Delete one or more columns

Parameters **column_indices** (*list*) – a list of column indices

pyexcel.Sheet.extend_columns

`Sheet.extend_columns(columns)`

Take ordereddict to extend named columns

Parameters **columns** (*ordereddict/list*) – a list of columns

Data series

Any column as row name

<code>Sheet.name_columns_by_row(row_index)</code>	Use the elements of a specified row to represent individual columns
<code>Sheet.rownames</code>	Return row names if any
<code>Sheet.named_column_at(name)</code>	Get a column by its name
<code>Sheet.set_named_column_at(name, column_array)</code>	Take the first row as column names
<code>Sheet.delete_named_column_at(name)</code>	Works only after you named columns by a row

pyexcel.Sheet.name_columns_by_row

`Sheet.name_columns_by_row(row_index)`

Use the elements of a specified row to represent individual columns

The specified row will be deleted from the data :param row_index: the index of the row that has the column names

pyexcel.Sheet.rownames

`Sheet.rownames`

Return row names if any

pyexcel.Sheet.named_column_at

`Sheet.named_column_at(name)`

Get a column by its name

pyexcel.Sheet.set_named_column_at

`Sheet.set_named_column_at(name, column_array)`

Take the first row as column names

Given name to identify the column index, set the column to the given array except the column name.

pyexcel.Sheet.delete_named_column_at

`Sheet.delete_named_column_at(name)`

Works only after you named columns by a row

Given name to identify the column index, set the column to the given array except the column name. :param str name: a column name

Any row as column name

<code>Sheet.name_rows_by_column(column_index)</code>	Use the elements of a specified column to represent individual rows
<code>Sheet.colnames</code>	Return column names if any
<code>Sheet.named_row_at(name)</code>	Get a row by its name
<code>Sheet.set_named_row_at(name, row_array)</code>	Take the first column as row names
<code>Sheet.delete_named_row_at(name)</code>	Take the first column as row names

pyexcel.Sheet.name_rows_by_column

`Sheet.name_rows_by_column` (*column_index*)

Use the elements of a specified column to represent individual rows

The specified column will be deleted from the data :param column_index: the index of the column that has the row names

pyexcel.Sheet.colnames

`Sheet.colnames`

Return column names if any

pyexcel.Sheet.named_row_at

`Sheet.named_row_at` (*name*)

Get a row by its name

pyexcel.Sheet.set_named_row_at

`Sheet.set_named_row_at` (*name, row_array*)

Take the first column as row names

Given name to identify the row index, set the row to the given array except the row name.

pyexcel.Sheet.delete_named_row_at

`Sheet.delete_named_row_at` (*name*)

Take the first column as row names

Given name to identify the row index, set the row to the given array except the row name.

Conversion

<code>Sheet.array</code>	Get/Set data in/from array format
<code>Sheet.records</code>	Get/Set data in/from records format
<code>Sheet.dict</code>	Get/Set data in/from dict format
<code>Sheet.url</code>	Set data in url format
<code>Sheet.csv</code>	Get/Set data in/from csv format
<code>Sheet.tsv</code>	Get/Set data in/from tsv format

Continued on next page

Table 23 – continued from previous page

<code>Sheet.csvz</code>	Get/Set data in/from csvz format
<code>Sheet.tsvz</code>	Get/Set data in/from tsvz format
<code>Sheet.xls</code>	Get/Set data in/from xls format
<code>Sheet.xlsm</code>	Get/Set data in/from xlsm format
<code>Sheet.xlsx</code>	Get/Set data in/from xlsx format
<code>Sheet.ods</code>	Get/Set data in/from ods format
<code>Sheet.stream</code>	Return a stream in which the content is properly encoded

pyexcel.Sheet.array

Sheet.array

Get/Set data in/from array format

You could obtain content in array format by dot notation:

```
Sheet.array
```

And you could as well set content by dot notation:

```
Sheet.array = the_io_stream_in_array_format
```

if you need to pass on more parameters, you could use:

```
Sheet.get_array(**keywords)
Sheet.set_array(the_io_stream_in_array_format, **keywords)
```

pyexcel.Sheet.records

Sheet.records

Get/Set data in/from records format

You could obtain content in records format by dot notation:

```
Sheet.records
```

And you could as well set content by dot notation:

```
Sheet.records = the_io_stream_in_records_format
```

if you need to pass on more parameters, you could use:

```
Sheet.get_records(**keywords)
Sheet.set_records(the_io_stream_in_records_format, **keywords)
```

pyexcel.Sheet.dict

Sheet.dict

Get/Set data in/from dict format

You could obtain content in dict format by dot notation:

```
Sheet.dict
```

And you could as well set content by dot notation:

```
Sheet.dict = the_io_stream_in_dict_format
```

if you need to pass on more parameters, you could use:

```
Sheet.get_dict(**keywords)  
Sheet.set_dict(the_io_stream_in_dict_format, **keywords)
```

pyexcel.Sheet.url

Sheet.**url**

Set data in url format

You could set content in url format by dot notation:

```
Sheet.url
```

if you need to pass on more parameters, you could use:

```
Sheet.set_url(the_io_stream_in_url_format, **keywords)
```

pyexcel.Sheet.csv

Sheet.**csv**

Get/Set data in/from csv format

You could obtain content in csv format by dot notation:

```
Sheet.csv
```

And you could as well set content by dot notation:

```
Sheet.csv = the_io_stream_in_csv_format
```

if you need to pass on more parameters, you could use:

```
Sheet.get_csv(**keywords)  
Sheet.set_csv(the_io_stream_in_csv_format, **keywords)
```

pyexcel.Sheet.tsv

Sheet.**tsv**

Get/Set data in/from tsv format

You could obtain content in tsv format by dot notation:

```
Sheet.tsv
```

And you could as well set content by dot notation:

```
Sheet.tsv = the_io_stream_in_tsv_format
```

if you need to pass on more parameters, you could use:

```
Sheet.get_tsv(**keywords)
Sheet.set_tsv(the_io_stream_in_tsv_format, **keywords)
```

pyexcel.Sheet.csvz

Sheet.**.csvz**

Get/Set data in/from csvz format

You could obtain content in csvz format by dot notation:

```
Sheet.csvz
```

And you could as well set content by dot notation:

```
Sheet.csvz = the_io_stream_in_csvz_format
```

if you need to pass on more parameters, you could use:

```
Sheet.get_csvz(**keywords)
Sheet.set_csvz(the_io_stream_in_csvz_format, **keywords)
```

pyexcel.Sheet.tsvz

Sheet.**.tsvz**

Get/Set data in/from tsvz format

You could obtain content in tsvz format by dot notation:

```
Sheet.tsvz
```

And you could as well set content by dot notation:

```
Sheet.tsvz = the_io_stream_in_tsvz_format
```

if you need to pass on more parameters, you could use:

```
Sheet.get_tsvz(**keywords)
Sheet.set_tsvz(the_io_stream_in_tsvz_format, **keywords)
```

pyexcel.Sheet.xls

Sheet.**.xls**

Get/Set data in/from xls format

You could obtain content in xls format by dot notation:

```
Sheet.xls
```

And you could as well set content by dot notation:

```
Sheet.xls = the_io_stream_in_xls_format
```

if you need to pass on more parameters, you could use:

```
Sheet.get_xls(**keywords)
Sheet.set_xls(the_io_stream_in_xls_format, **keywords)
```

pyexcel.Sheet.xlsm

Sheet.xlsm

Get/Set data in/from xlsm format

You could obtain content in xlsm format by dot notation:

```
Sheet.xlsm
```

And you could as well set content by dot notation:

```
Sheet.xlsm = the_io_stream_in_xlsm_format
```

if you need to pass on more parameters, you could use:

```
Sheet.get_xlsm(**keywords)
Sheet.set_xlsm(the_io_stream_in_xlsm_format, **keywords)
```

pyexcel.Sheet.xlsx

Sheet.xlsx

Get/Set data in/from xlsx format

You could obtain content in xlsx format by dot notation:

```
Sheet.xlsx
```

And you could as well set content by dot notation:

```
Sheet.xlsx = the_io_stream_in_xlsx_format
```

if you need to pass on more parameters, you could use:

```
Sheet.get_xlsx(**keywords)
Sheet.set_xlsx(the_io_stream_in_xlsx_format, **keywords)
```

pyexcel.Sheet.ods

Sheet.ods

Get/Set data in/from ods format

You could obtain content in ods format by dot notation:

```
Sheet.ods
```

And you could as well set content by dot notation:

```
Sheet.ods = the_io_stream_in_ods_format
```

if you need to pass on more parameters, you could use:

```
Sheet.get_ods(**keywords)
Sheet.set_ods(the_io_stream_in_ods_format, **keywords)
```

pyexcel.Sheet.stream

Sheet.**stream**

Return a stream in which the content is properly encoded

Example:

```
>>> import pyexcel as p
>>> b = p.get_book(bookdict={"A": [[1]]})
>>> csv_stream = b.stream.texttable
>>> print(csv_stream.getvalue())
A:
+----+
| 1 |
+----+
```

Where `b.stream.xls.getvalue()` is equivalent to `b.xls`. In some situation `b.stream.xls` is preferred than `b.xls`.

Sheet examples:

```
>>> import pyexcel as p
>>> s = p.Sheet([[1]], 'A')
>>> csv_stream = s.stream.texttable
>>> print(csv_stream.getvalue())
A:
+----+
| 1 |
+----+
```

Where `s.stream.xls.getvalue()` is equivalent to `s.xls`. In some situation `s.stream.xls` is preferred than `s.xls`.

It is similar to `save_to_memory()`.

Formatting

`Sheet.format(formatter)`

Apply a formatting action for the whole sheet

pyexcel.Sheet.format

Sheet.**format** (*formatter*)

Apply a formatting action for the whole sheet

Example:

```
>>> import pyexcel as pe
>>> # Given a dictionary as the following
>>> data = {
```

(continues on next page)

(continued from previous page)

```

...     "1": [1, 2, 3, 4, 5, 6, 7, 8],
...     "3": [1.25, 2.2, 3.3, 4.4, 5.5, 6.6, 7.7, 8.8],
...     "5": [2, 3, 4, 5, 6, 7, 8, 9],
...     "7": [1, '', ]
...     }
>>> sheet = pe.get_sheet(adict=data)
>>> sheet.row[1]
[1, 1.25, 2, 1]
>>> sheet.format(str)
>>> sheet.row[1]
['1', '1.25', '2', '1']
>>> sheet.format(int)
>>> sheet.row[1]
[1, 1, 2, 1]

```

Filtering

<code>Sheet.filter([column_indices, row_indices])</code>	Apply the filter with immediate effect
--	--

pyexcel.Sheet.filter

`Sheet.filter` (*column_indices=None, row_indices=None*)
Apply the filter with immediate effect

Transformation

<code>Sheet.transpose()</code>	Rotate the data table by 90 degrees
<code>Sheet.map(custom_function)</code>	Execute a function across all cells of the sheet
<code>Sheet.region(topleft_corner, bottomright_corner)</code>	Get a rectangle shaped data out
<code>Sheet.cut(topleft_corner, bottomright_corner)</code>	Get a rectangle shaped data out and clear them in position
<code>Sheet.paste(topleft_corner[, rows, columns])</code>	Paste a rectangle shaped data after a position

pyexcel.Sheet.transpose

`Sheet.transpose()`
Rotate the data table by 90 degrees
Reference `transpose()`

pyexcel.Sheet.map

`Sheet.map` (*custom_function*)
Execute a function across all cells of the sheet

Example:

```

>>> import pyexcel as pe
>>> # Given a dictionary as the following

```

(continues on next page)

(continued from previous page)

```

>>> data = {
...     "1": [1, 2, 3, 4, 5, 6, 7, 8],
...     "3": [1.25, 2.2, 3.3, 4.4, 5.5, 6.6, 7.7, 8.8],
...     "5": [2, 3, 4, 5, 6, 7, 8, 9],
...     "7": [1, '',]
...     }
>>> sheet = pe.get_sheet(adict=data)
>>> sheet.row[1]
[1, 1.25, 2, 1]
>>> inc = lambda value: (float(value) if value != '' else 0)+1
>>> sheet.map(inc)
>>> sheet.row[1]
[2.0, 2.25, 3.0, 2.0]

```

pyexcel.Sheet.region

Sheet.**region** (*topleft_corner*, *bottomright_corner*)

Get a rectangle shaped data out

Parameters

- **topleft_corner** (*slice*) – the top left corner of the rectangle
- **bottomright_corner** (*slice*) – the bottom right corner of the rectangle

pyexcel.Sheet.cut

Sheet.**cut** (*topleft_corner*, *bottomright_corner*)

Get a rectangle shaped data out and clear them in position

Parameters

- **topleft_corner** (*slice*) – the top left corner of the rectangle
- **bottomright_corner** (*slice*) – the bottom right corner of the rectangle

pyexcel.Sheet.paste

Sheet.**paste** (*topleft_corner*, *rows=None*, *columns=None*)

Paste a rectangle shaped data after a position

Parameters **topleft_corner** (*slice*) – the top left corner of the rectangle

example:

```

>>> import pyexcel as pe
>>> data = [
...     # 0 1 2 3 4 5 6
...     [1, 2, 3, 4, 5, 6, 7], # 0
...     [21, 22, 23, 24, 25, 26, 27],
...     [31, 32, 33, 34, 35, 36, 37],
...     [41, 42, 43, 44, 45, 46, 47],
...     [51, 52, 53, 54, 55, 56, 57] # 4
... ]

```

(continues on next page)

(continued from previous page)

```

>>> s = pe.Sheet(data)
>>> # cut 1<= row < 4, 1<= column < 5
>>> data = s.cut([1, 1], [4, 5])
>>> s.paste([4,6], rows=data)
>>> s
pyexcel sheet:
+---+---+---+---+---+---+---+---+---+---+
| 1 | 2 | 3 | 4 | 5 | 6 | 7 |   |   |   |   |
+---+---+---+---+---+---+---+---+---+---+
| 21 |   |   |   |   | 26 | 27 |   |   |   |   |
+---+---+---+---+---+---+---+---+---+---+
| 31 |   |   |   |   | 36 | 37 |   |   |   |   |
+---+---+---+---+---+---+---+---+---+---+
| 41 |   |   |   |   | 46 | 47 |   |   |   |   |
+---+---+---+---+---+---+---+---+---+---+
| 51 | 52 | 53 | 54 | 55 | 56 | 22 | 23 | 24 | 25 |
+---+---+---+---+---+---+---+---+---+---+
|   |   |   |   |   |   | 32 | 33 | 34 | 35 |
+---+---+---+---+---+---+---+---+---+---+
|   |   |   |   |   |   | 42 | 43 | 44 | 45 |
+---+---+---+---+---+---+---+---+---+---+
>>> s.paste([6,9], columns=data)
>>> s
pyexcel sheet:
+---+---+---+---+---+---+---+---+---+---+---+---+
| 1 | 2 | 3 | 4 | 5 | 6 | 7 |   |   |   |   |   |   |
+---+---+---+---+---+---+---+---+---+---+---+---+
| 21 |   |   |   |   | 26 | 27 |   |   |   |   |   |   |
+---+---+---+---+---+---+---+---+---+---+---+---+
| 31 |   |   |   |   | 36 | 37 |   |   |   |   |   |   |
+---+---+---+---+---+---+---+---+---+---+---+---+
| 41 |   |   |   |   | 46 | 47 |   |   |   |   |   |   |
+---+---+---+---+---+---+---+---+---+---+---+---+
| 51 | 52 | 53 | 54 | 55 | 56 | 22 | 23 | 24 | 25 |   |   |
+---+---+---+---+---+---+---+---+---+---+---+---+
|   |   |   |   |   |   | 32 | 33 | 34 | 35 |   |   |
+---+---+---+---+---+---+---+---+---+---+---+---+
|   |   |   |   |   |   | 42 | 43 | 44 | 22 | 32 | 42 |
+---+---+---+---+---+---+---+---+---+---+---+---+
|   |   |   |   |   |   |   |   |   | 23 | 33 | 43 |
+---+---+---+---+---+---+---+---+---+---+---+---+
|   |   |   |   |   |   |   |   |   | 24 | 34 | 44 |
+---+---+---+---+---+---+---+---+---+---+---+---+
|   |   |   |   |   |   |   |   |   | 25 | 35 | 45 |
+---+---+---+---+---+---+---+---+---+---+---+---+

```

Save changes

<code>Sheet.save_as(filename, **keywords)</code>	Save the content to a named file
<code>Sheet.save_to_memory(file_type[, stream])</code>	Save the content to memory
<code>Sheet.save_to_database(session, table[, ...])</code>	Save data in sheet to database table
<code>Sheet.save_to_django_model(model[, ...])</code>	Save to database table through django model

pyexcel.Sheet.save_as

Sheet . **save_as** (*filename*, ****keywords**)

Save the content to a named file

Keywords may vary depending on your file type, because the associated file type employs different library.

PARAMETERS

filename: a file path

library: choose a specific pyexcel-io plugin for writing

renderer_library: choose a pyexcel parser plugin for writing

Parameters related to csv file format

for csv, **fmtparams** are accepted

delimiter : field separator

lineterminator : line terminator

encoding: csv specific. Specify the file encoding the csv file. For example: `encoding='latin1'`. Especially, `encoding='utf-8-sig'` would add utf 8 bom header if used in renderer, or would parse a csv with utf bom header used in parser.

escapechar : A one-character string used by the writer to escape the delimiter if quoting is set to QUOTE_NONE and the quotechar if doublequote is False.

quotechar : A one-character string used to quote fields containing special characters, such as the delimiter or quotechar, or which contain new-line characters. It defaults to `"`

quoting : Controls when quotes should be generated by the writer and recognised by the reader. It can take on any of the QUOTE_* constants (see section Module Contents) and defaults to QUOTE_MINIMAL.

skipinitialspace : When True, whitespace immediately following the delimiter is ignored. The default is False.

pyexcel.Sheet.save_to_memory

Sheet . **save_to_memory** (*file_type*, *stream=None*, ****keywords**)

Save the content to memory

Parameters

- **file_type** – any value of 'csv', 'tsv', 'csvz', 'tsvz', 'xls', 'xlsm', 'xlsx', 'ods'
- **stream** – the memory stream to be written to. Note in Python 3, for csv and tsv format, please pass an instance of StringIO. For xls, xlsx, and ods, an instance of BytesIO.

pyexcel.Sheet.save_to_database

Sheet . **save_to_database** (*session*, *table*, *initializer=None*, *mapdict=None*, *auto_commit=True*)

Save data in sheet to database table

Parameters

- **session** – database session
- **table** – a database table
- **initializer** – a initialization functions for your table

- **mapdict** – custom map dictionary for your data columns
- **auto_commit** – by default, data is auto committed.

pyexcel.Sheet.save_to_django_model

Sheet.**save_to_django_model** (*model, initializer=None, mapdict=None, batch_size=None*)
 Save to database table through django model

Parameters

- **model** – a database model
- **initializer** – a initialization functions for your model
- **mapdict** – custom map dictionary for your data columns
- **batch_size** – a parameter to Django concerning the size for bulk insertion

7.2 Internal API reference

This is intended for developers and hackers of pyexcel.

7.2.1 Data sheet representation

In inheritance order from parent to child

<i>Matrix</i> (array)	The internal representation of a sheet data.
-----------------------	--

pyexcel.internal.sheets.Matrix

class pyexcel.internal.sheets.**Matrix** (*array*)

The internal representation of a sheet data. Each element can be of any python types

__init__ (*array*)
 Constructor

The reason a deep copy was not made here is because the data sheet could be huge. It could be costly to copy every cell to a new memory area :param list array: a list of arrays

Methods

__init__ (array)	Constructor
cell_value(row, column[, new_value])	Random access to table cells
column_at(index)	Gets the data at the specified column
column_range()	Utility function to get column range
columns()	Returns a left to right column iterator
contains(predicate)	Has something in the table
cut(topleft_corner, bottomright_corner)	Get a rectangle shaped data out and clear them in position

Continued on next page

Table 29 – continued from previous page

<code>delete_columns(column_indices)</code>	Delete columns by specified list of indices
<code>delete_rows(row_indices)</code>	Deletes specified row indices
<code>enumerate()</code>	Iterate cell by cell from top to bottom and from left to right
<code>extend_columns(columns)</code>	Inserts two dimensional data after the rightmost column
<code>extend_columns_with_rows(rows)</code>	Rows were appended to the rightmost side
<code>extend_rows(rows)</code>	Inserts two dimensional data after the bottom row
<code>filter([column_indices, row_indices])</code>	Apply the filter with immediate effect
<code>format(formatter)</code>	Apply a formatting action for the whole sheet
<code>get_array(**keywords)</code>	Get data in array format
<code>get_bookdict(**keywords)</code>	Get data in bookdict format
<code>get_csv(**keywords)</code>	Get data in csv format
<code>get_csvz(**keywords)</code>	Get data in csvz format
<code>get_dict(**keywords)</code>	Get data in dict format
<code>Matrix.get_echarts_html</code>	
<code>get_fods(**_)</code>	fods getter is not defined.
<code>Matrix.get_gantt_html</code>	
<code>Matrix.get_grid</code>	
<code>get_handsonable_html(**keywords)</code>	Get data in handsonable.html format
<code>Matrix.get_html</code>	
<code>get_internal_array()</code>	present internal array
<code>Matrix.get_json</code>	
<code>Matrix.get_latex</code>	
<code>Matrix.get_latex_booktabs</code>	
<code>Matrix.get_mediawiki</code>	
<code>Matrix.get_ndjson</code>	
<code>get_ods(**keywords)</code>	Get data in ods format
<code>Matrix.get Orgtbl</code>	
<code>Matrix.get_pdf</code>	
<code>Matrix.get_pipe</code>	
<code>Matrix.get_plain</code>	
<code>get_records(**keywords)</code>	Get data in records format
<code>Matrix.get_rst</code>	
<code>Matrix.get_simple</code>	
<code>Matrix.get_sortable_html</code>	
<code>get_svg(**keywords)</code>	Get data in svg format
<code>get_texttable(**keywords)</code>	Get data in texttable format
<code>get_tsv(**keywords)</code>	Get data in tsv format
<code>get_tsvz(**keywords)</code>	Get data in tsvz format
<code>get_url(**_)</code>	url getter is not defined.
<code>get_xls(**keywords)</code>	Get data in xls format
<code>get_xlsm(**keywords)</code>	Get data in xlsm format
<code>get_xlsx(**keywords)</code>	Get data in xlsx format
<code>map(custom_function)</code>	Execute a function across all cells of the sheet
<code>number_of_columns()</code>	The number of columns
<code>number_of_rows()</code>	The number of rows
<code>paste(topleft_corner[, rows, columns])</code>	Paste a rectangle shaped data after a position
<code>rcolumns()</code>	Returns a right to left column iterator
<code>region(topleft_corner, bottomright_corner)</code>	Get a rectangle shaped data out

Continued on next page

Table 29 – continued from previous page

<code>register_input(file_type[, instance_name])</code>	<code>partial(func, *args, **keywords)</code> - new function with partial application of the given arguments and keywords.
<code>register_io(file_type[, presenter_func, ...])</code>	<code>partial(func, *args, **keywords)</code> - new function with partial application of the given arguments and keywords.
<code>register_presentation(file_type[, ...])</code>	
<code>reverse()</code>	Opposite to <code>enumerate</code>
<code>row_at(index)</code>	Gets the data at the specified row
<code>row_range()</code>	Utility function to get row range
<code>rows()</code>	Returns a top to bottom row iterator
<code>rrows()</code>	Returns a bottom to top row iterator
<code>rvertical()</code>	Default iterator to go through each cell one by one from rightmost column to leftmost row and from bottom to top example.
<code>save_as(filename, **keywords)</code>	Save the content to a named file
<code>save_to_database(session, table[, ...])</code>	Save data in sheet to database table
<code>save_to_django_model(model[, initializer, ...])</code>	Save to database table through django model
<code>save_to_memory(file_type[, stream])</code>	Save the content to memory
<code>set_array(content, **keywords)</code>	Set data in array format
<code>set_bookdict(content, **keywords)</code>	Set data in bookdict format
<code>set_column_at(column_index, data_array[, ...])</code>	Updates a column data range
<code>set_csv(content, **keywords)</code>	Set data in csv format
<code>set_csvz(content, **keywords)</code>	Set data in csvz format
<code>set_dict(content, **keywords)</code>	Set data in dict format
<code>Matrix.set_echarts_html</code>	
<code>set_fods(content, **keywords)</code>	Set data in fods format
<code>Matrix.set_gantt_html</code>	
<code>Matrix.set_grid</code>	
<code>set_handsonatable_html(_y, **_z)</code>	<code>handsonatable.html</code> setter is not defined.
<code>Matrix.set_html</code>	
<code>Matrix.set_json</code>	
<code>Matrix.set_latex</code>	
<code>Matrix.set_latex_booktabs</code>	
<code>Matrix.set_mediawiki</code>	
<code>Matrix.set_ndjson</code>	
<code>set_ods(content, **keywords)</code>	Set data in ods format
<code>Matrix.set Orgtbl</code>	
<code>Matrix.set_pdf</code>	
<code>Matrix.set_pipe</code>	
<code>Matrix.set_plain</code>	
<code>set_records(content, **keywords)</code>	Set data in records format
<code>set_row_at(row_index, data_array)</code>	Update a row data range
<code>Matrix.set_rst</code>	
<code>Matrix.set_simple</code>	
<code>Matrix.set_sortable_html</code>	
<code>set_svg(_y, **_z)</code>	<code>svg</code> setter is not defined.
<code>set_texttable(_y, **_z)</code>	<code>texttable</code> setter is not defined.
<code>set_tsv(content, **keywords)</code>	Set data in tsv format

Continued on next page

Table 29 – continued from previous page

<code>set_tsvz(content, **keywords)</code>	Set data in tsvz format
<code>set_url(content, **keywords)</code>	Set data in url format
<code>set_xls(content, **keywords)</code>	Set data in xls format
<code>set_xlsm(content, **keywords)</code>	Set data in xlsm format
<code>set_xlsx(content, **keywords)</code>	Set data in xlsx format
<code>to_array()</code>	Get an array out
<code>transpose()</code>	Rotate the data table by 90 degrees
<code>vertical()</code>	Default iterator to go through each cell one by one from leftmost column to rightmost row and from top to bottom example.

Attributes

<code>array</code>	Get/Set data in/from array format
<code>bookdict</code>	Get/Set data in/from bookdict format
<code>csv</code>	Get/Set data in/from csv format
<code>csvz</code>	Get/Set data in/from csvz format
<code>dict</code>	Get/Set data in/from dict format
<code>Matrix.echarts_html</code>	
<code>fods</code>	Set data in fods format
<code>Matrix.gantt_html</code>	
<code>Matrix.grid</code>	
<code>handsontable_html</code>	Get data in handsontable.html format
<code>Matrix.html</code>	
<code>Matrix.json</code>	
<code>Matrix.latex</code>	
<code>Matrix.latex_booktabs</code>	
<code>Matrix.mediawiki</code>	
<code>Matrix.ndjson</code>	
<code>ods</code>	Get/Set data in/from ods format
<code>Matrix.orgtbl</code>	
<code>Matrix.pdf</code>	
<code>Matrix.pipe</code>	
<code>Matrix.plain</code>	
<code>plot([file_type])</code>	Visualize the data
<code>records</code>	Get/Set data in/from records format
<code>Matrix.rst</code>	
<code>Matrix.simple</code>	
<code>Matrix.sortable_html</code>	
<code>stream</code>	Return a stream in which the content is properly encoded
<code>svg</code>	Get data in svg format
<code>texttable</code>	Get data in texttable format
<code>tsv</code>	Get/Set data in/from tsv format
<code>tsvz</code>	Get/Set data in/from tsvz format
<code>url</code>	Set data in url format
<code>xls</code>	Get/Set data in/from xls format
<code>xlsm</code>	Get/Set data in/from xlsm format
<code>xlsx</code>	Get/Set data in/from xlsx format

<code>SheetStream(name, payload)</code>	Memory efficient sheet representation
<code>BookStream(sheets, filename, path)</code>	Memory efficient book representation

pyexcel.internal.generators.SheetStream

class `pyexcel.internal.generators.SheetStream` (*name, payload*)
 Memory efficient sheet representation

This class wraps around the data read from pyexcel-io. Comparing with `pyexcel.Sheet`, the instance of this class does not load all data into memory. Hence it performs better when dealing with big data.

If you would like to do custom rendering for each row of the two dimensional data, you would need to pass a row formatting/rendering function to the parameter “renderer” of pyexcel’s signature functions.

`__init__` (*name, payload*)
`x.__init__(...)` initializes x; see `help(type(x))` for signature

Methods

<code>__init__(name, payload)</code>	<code>x.__init__(...)</code> initializes x; see <code>help(type(x))</code> for signature
<code>get_internal_array()</code>	
<code>to_array()</code>	Simply return the generator

Attributes

<code>array</code>	array attribute
--------------------	-----------------

pyexcel.internal.generators.BookStream

class `pyexcel.internal.generators.BookStream` (*sheets=None, filename='memory', path=None*)

Memory efficient book representation

Comparing with `pyexcel.Book`, the instance of this class uses `pyexcel.generators.SheetStream` as its internal representation of sheet objects. Because `SheetStream` does not read data into memory, it is memory efficient.

`__init__` (*sheets=None, filename='memory', path=None*)
 Book constructor

Selecting a specific book according to filename extension :param `OrderedDict/dict` sheets: a dictionary of data :param `str` filename: the physical file :param `str` path: the relative path or absolute path :param set keywords: additional parameters to be passed on

Methods

<code>__init__([sheets, filename, path])</code>	Book constructor
<code>load_from_sheets(sheets)</code>	Load content from existing sheets
<code>number_of_sheets()</code>	Return the number of sheets

Continued on next page

Table 34 – continued from previous page

<code>to_dict()</code>	Get book data structure as a dictionary
------------------------	---

7.2.2 Row representation

<code>Row(matrix)</code>	Represent row of a matrix
--------------------------	---------------------------

pyexcel.internal.sheets.Row

class `pyexcel.internal.sheets.Row` (*matrix*)
 Represent row of a matrix

Table 36: “example.csv”

1	2	3
4	5	6
7	8	9

Above column manipulation can be performed on rows similarly. This section will not repeat the same example but show some advance usages.

```
>>> import pyexcel as pe
>>> data = [[1,2,3], [4,5,6], [7,8,9]]
>>> m = pe.internal.sheets.Matrix(data)
>>> m.row[0:2]
[[1, 2, 3], [4, 5, 6]]
>>> m.row[0:3] = [0, 0, 0]
>>> m.row[2]
[0, 0, 0]
>>> del m.row[0:2]
>>> m.row[0]
[0, 0, 0]
```

`__init__` (*matrix*)
 x.`__init__`(...) initializes x; see `help(type(x))` for signature

Methods

<code>__init__(matrix)</code>	x. <code>__init__</code> (...) initializes x; see <code>help(type(x))</code> for signature
<code>format([row_index, formatter, format_specs])</code>	Format a row
<code>get_converter(theformatter)</code>	return the actual converter or a built-in converter
<code>select(indices)</code>	Delete row indices other than specified

7.2.3 Column representation

<code>Column(matrix)</code>	Represent columns of a matrix
-----------------------------	-------------------------------

pyexcel.internal.sheets.Column

class pyexcel.internal.sheets.**Column** (*matrix*)
 Represent columns of a matrix

Table 39: “example.csv”

1	2	3
4	5	6
7	8	9

Let us manipulate the data columns on the above data matrix:

```
>>> import pyexcel as pe
>>> data = [[1,2,3], [4,5,6], [7,8,9]]
>>> m = pe.internal.sheets.Matrix(data)
>>> m.column[0]
[1, 4, 7]
>>> m.column[2] = [0, 0, 0]
>>> m.column[2]
[0, 0, 0]
>>> del m.column[1]
>>> m.column[1]
[0, 0, 0]
>>> m.column[2]
Traceback (most recent call last):
...
IndexError
```

__init__ (*matrix*)
 x.__init__(...) initializes x; see help(type(x)) for signature

Methods

__init__ (<i>matrix</i>)	x.__init__(...) initializes x; see help(type(x)) for signature
format ([<i>column_index</i> , <i>formatter</i> , <i>format_specs</i>])	Format a column
get_converter (<i>theformatter</i>)	return the actual converter or a built-in converter
select (<i>indices</i>)	

Examples

8.1 Developer's guide

8.1.1 Architecture

pyexcel uses loosely couple plugins to fullfil the promise to access various file formats. **lml** is the plugin management library that provide the specialized support for the loose coupling.

The components of **pyexcel** is designed as building blocks. For your project, you can cherry-pick the file format support without affecting the core functionality of pyexcel. Each plugin will bring in additional dependences. For example, if you choose pyexcel-xls, xlrd and xlwt will be brought in as 2nd level depondencies.

Looking at the following architectural diagram, pyexcel hosts plugin interfaces for data source, data renderer and data parser. pyexel-pygal, pyexcel-matplotlib, and pyexce-handsontable extend pyexcel using data renderer interface. pyexcel-io package takes away the responsibilities to interface with excel libraries, for example: xlrd, openpyxl, ezodf.

As in *A list of file formats supported by external plugins*, there are overlapping capabilities in reading and writing xlsx, ods files. Because each third parties express different personalities although they may read and write data in the same file format, you as the pyexcel is left to pick which suit your task best.

Dotted arrow means the package or module is loaded later.

Development steps for code changes

1. git clone <https://github.com/pyexcel/pyexcel.git>
2. cd pyexcel

Upgrade your setup tools and pip. They are needed for development and testing only:

1. pip install --upgrade setuptools pip

Then install relevant development requirements:

1. pip install -r rnd_requirements.txt # if such a file exists

2. `pip install -r requirements.txt`
3. `pip install -r tests/requirements.txt`

Once you have finished your changes, please provide test case(s), relevant documentation and update `CHANGELOG.rst`.

Note: As to `rnd_requirements.txt`, usually, it is created when a dependent library is not released. Once the dependency is installed (will be released), the future version of the dependency in the `requirements.txt` will be valid.

8.1.2 How to test your contribution

Although *nose* and *doctest* are both used in code testing, it is advisable that unit tests are put in tests. *doctest* is incorporated only to make sure the code examples in documentation remain valid across different development releases.

On Linux/Unix systems, please launch your tests like this:

```
$ make
```

On Windows systems, please issue this command:

```
> test.bat
```

8.1.3 How to update test environment and update documentation

Additional steps are required:

1. `pip install moban`
2. `git clone https://github.com/moremoban/setupmobans.git # generic setup`
3. `git clone https://github.com/pyexcel/pyexcel-commons.git commons`
4. make your changes in `.moban.d` directory, then issue command `moban`

8.1.4 What is pyexcel-commons

Many information that are shared across pyexcel projects, such as: this developer guide, license info, etc. are stored in *pyexcel-commons* project.

8.1.5 What is .moban.d

`.moban.d` stores the specific meta data for the library.

8.1.6 Acceptance criteria

1. Has Test cases written
2. Has all code lines tested
3. Passes all Travis CI builds
4. Has fair amount of documentation if your change is complex

5. Please update CHANGELOG.rst
6. Please add yourself to CONTRIBUTORS.rst
7. Agree on NEW BSD License for your contribution

8.2 How to log pyexcel

When developing source plugins, it becomes necessary to have log trace available. It helps find out what goes wrong quickly.

The basic step would be to set up logging before pyexcel import statement.

```
import logging
import logging.config
logging.basicConfig(format='%(asctime)s - %(name)s - %(levelname)s - %(message)s',
                    level=logging.DEBUG)

import pyexcel
```

And if you would use a complex configuration, you can use the following code.

```
import logging
import logging.config
logging.config.fileConfig('log.conf')

import pyexcel
```

And then save the following content as log.conf in your directory:

```
[loggers]
keys=root, sources, renderers

[handlers]
keys=consoleHandler

[formatters]
keys=custom

[logger_root]
level=INFO
handlers=consoleHandler

[logger_sources]
level=DEBUG
handlers=consoleHandler
qualname=pyexcel.sources.factory
propagate=0

[logger_renderers]
level=DEBUG
handlers=consoleHandler
qualname=pyexcel.renderers.factory
propagate=0

[handler_consoleHandler]
class=StreamHandler
```

(continues on next page)

(continued from previous page)

```
level=DEBUG
formatter=custom
args=(sys.stdout,)

[formatter_custom]
format=%(asctime)s - %(name)s - %(levelname)s - %(message)s
datefmt=
```

8.3 Packaging with PyInstaller

With pyexcel v0.5.0, the way to package it has been changed because it uses lml for all plugins.

And you need to do the same for pyexcel-io plugins too.

8.3.1 Built-in plugins of pyexcel

In order to package every built-in plugins of pyexcel-io, you need to specify:

```
--hidden-import pyexcel.plugins.renderers.sqlalchemy
--hidden-import pyexcel.plugins.renderers.django
--hidden-import pyexcel.plugins.renderers.excel
--hidden-import pyexcel.plugins.renderers._texttable
--hidden-import pyexcel.plugins.parsers.excel
--hidden-import pyexcel.plugins.parsers.sqlalchemy
--hidden-import pyexcel.plugins.sources.http
--hidden-import pyexcel.plugins.sources.file_input
--hidden-import pyexcel.plugins.sources.memory_input
--hidden-import pyexcel.plugins.sources.file_output
--hidden-import pyexcel.plugins.sources.output_to_memory
--hidden-import pyexcel.plugins.sources.pydata.bookdict
--hidden-import pyexcel.plugins.sources.pydata.dictsource
--hidden-import pyexcel.plugins.sources.pydata.arraysource
--hidden-import pyexcel.plugins.sources.pydata.records
--hidden-import pyexcel.plugins.sources.django
--hidden-import pyexcel.plugins.sources.sqlalchemy
--hidden-import pyexcel.plugins.sources.querysets
```

8.4 How to write a plugin for pyexcel

Note: Under writing. Stay tuned.

There are three types of plugins for pyexcel: data parser, data renderer and data source.

8.4.1 Tutorial

Let me walk you through the process of creating pyexcel-pdf package.

Prerequisites:

1. pip install moban yehua
2. git clone <https://github.com/moremoban/setupmobans.git> # generic setup
3. git clone <https://github.com/pyexcel/pyexcel-commons.git>

Let me assume that you have the work directory as:

```
setupmobans pyexcel-commons
```

and *YOUR_WORK_DIRECTORY* points to the base directory for both.

And then please export an environment variable:

```
export YEHUA_FILE=$YOUR_WORK_DIRECTORY/pyexcel-commons/yehua/yehua.yml
```

Now let's get started.

Step 1

Call *yehua* to get the basic scaffolding:

```
$ yehua
Yehua will walk you through creating a pyexcel package.
Press ^C to quit at any time.

What is your project name? pyexcel-pdf
What is the description? parses tables in pdf file as tabular data
What is project type?
1. pyexcel plugins
2. command line interface
3. python's C extensnion
(1,2,3): 1
What is the nick name? pdf
$
```

Step 2

Call *moban* to inflate all project files:

```
$ cd pyexcel-pdf/
$ ln -s ../pyexcel-commons/ commons
$ ln -s ../setupmobans/ setupmobans
$ moban
Templating README.rst to README.rst
Templating setup.py to setup.py
Templating requirements.txt to requirements.txt
Templating NEW_BSD_LICENSE.jj2 to LICENSE
Templating MANIFEST.in.jj2 to MANIFEST.in
Templating tests/requirements.txt to tests/requirements.txt
Templating test.script.jj2 to test.sh
Templating test.script.jj2 to test.bat
Templating travis.yml.jj2 to .travis.yml
Templating gitignore.jj2 to .gitignore
Templating docs/source/conf.py.jj2 to docs/source/conf.py
```

Step 3 - Coding

Please put your code in `pyxcel_pdr`

9.1 Migrate away from 0.4.3

`get_{{file_type}}_stream` functions from `pyexcel.Sheet` and `pyexcel.Book` were introduced since 0.4.3 but were removed since 0.4.4. Please be advised to use `save_to_memory` functions, `Sheet.io.{{file_type}}` or `Book.io.{{file_type}}`.

9.2 Migrate from 0.2.x to 0.3.0+

Filtering and formatting behavior of `pyexcel.Sheet` are simplified. Soft filter and soft formatter are removed. Extra classes such as `iterator`, `formatter`, `filter` are removed.

Most of formatting tasks could be achieved using `format()` and `map()`. and Filtering with `filter()`. Formatting and filtering on row and/or column can be found with `row()` and `column()`

9.2.1 1. Updated filter function

There is no alternative to replace the following code:

```
sheet.filter(pe.OddRowFilter())
```

You will need to remove odd rows by yourself:

```
>>> import pyexcel as pe
>>> data = [
...     ['1'],
...     ['2'],
...     ['3'],
... ]
>>> sheet = pe.Sheet(data)
>>> to_remove = []
```

(continues on next page)

(continued from previous page)

```

>>> for index in sheet.row_range():
...     if index % 2 == 0:
...         to_remove.append(index)
>>> sheet.filter(row_indices=to_remove)
>>> sheet
pyexcel sheet:
+----+
| 2 |
+----+

```

Or, you could do this:

```

>>> data = [
...     ['1'],
...     ['2'],
...     ['3'],
... ]
>>> sheet = pe.Sheet(data)
>>> def odd_filter(row_index, _):
...     return row_index % 2 == 0
>>> del sheet.row[odd_filter]
>>> sheet
pyexcel sheet:
+----+
| 2 |
+----+

```

And the same applies to EvenRowFilter, OddColumnFilter, EvenColumnFilter.

9.2.2 2. Updated format function

2.1 Replacement of sheetformatter

The following formatting code:

```
sheet.apply_formatter(pe.sheets.formatters.SheetFormatter(int))
```

can be replaced by:

```
sheet.format(int)
```

2.2 Replacement of row formatters

The following code:

```
row_formatter = pe.sheets.formatters.RowFormatter([1, 2], str)
sheet.add_formatter(row_formatter)
```

can be replaced by:

```
sheet.row.format([1, 2], str)
```

2.3 Replacement of column formatters

The following code:

```
f = NamedColumnFormatter(["Column 1", "Column 3"], str)
sheet.apply_formatter(f)
```

can be replaced by:

```
sheet.column.format(["Column 1", "Column 3"], str)
```

9.3 Migrate from 0.2.1 to 0.2.2+

9.3.1 1. Explicit imports, no longer needed

Please forget about these statements:

```
import pyexcel.ext.xls
import pyexcel.ext.ods
import pyexcel.ext.xlsx
```

They are no longer needed. As long as you have pip-installed them, they will be auto-loaded. However, if you do not want some of the plugins, please use *pip* to uninstall them.

What if you have your code as it is? No harm but a few warnings shown:

```
Deprecated usage since v0.2.2! Explicit import is no longer required. pyexcel.ext.ods_
↳ is auto imported.
```

9.3.2 2. Invalid environment marker: platform_python_implementation=="PyPy"

Yes, it is a surprise. Please upgrade setuptools in your environment:

```
pip install --upgrade setuptools
```

At the time of writing, setuptools (18.0.1) or setuptools-21.0.0-py2.py3-none-any.whl is installed on author's computer and worked.

9.3.3 3. How to keep both pyexcel-xls and pyexcel-xlsx

As in [Issue 20](#), pyexcel-xls was used for xls and pyexcel-xlsx had to be used for xlsx. Both must co-exist due to requirements. The workaround would failed when auto-import are enabled in v0.2.2. Hence, user of pyexcel in this situation shall use 'library' parameter to all signature functions, to instruct pyexcel to use a named library for each function call.

9.3.4 4. pyexcel.get_io is no longer exposed

pyexcel.get_io was passed on from pyexcel-io. However, it is no longer exposed. Please use pyexcel_io.manager.RWManager.get_io if you have to.

You are likely to use `pyexcel.get_io` when you do `pyexcel.Sheet.save_to_memory()` or `pyexcel.Book.save_to_memory()` where you need to put in a io stream. But actually, with latest code, you could put in a `None`.

9.4 Migrate from 0.1.x to 0.2.x

9.4.1 1. “Writer” is gone, Please use `save_as`.

Here is a piece of legacy code:

```
w = pyexcel.Writer("afile.csv")
data=[['a', 'b', 'c', 'd', 'e', 'f', 'g', 'h', 'i', 'j', 1.1, 1]]
w.write_array(table)
w.close()
```

The new code is:

```
>>> data=[['a', 'b', 'c', 'd', 'e', 'f', 'g', 'h', 'i', 'j', 1.1, 1]]
>>> pyexcel.save_as(array=data, dest_file_name="afile.csv")
```

Here is another piece of legacy code:

```
content = {
    "X": [1,2,3,4,5],
    "Y": [6,7,8,9,10],
    "Z": [11,12,13,14,15],
}
w = pyexcel.Writer("afile.csv")
w.write_dict(self.content)
w.close()
```

The new code is:

```
>>> content = {
...     "X": [1,2,3,4,5],
...     "Y": [6,7,8,9,10],
...     "Z": [11,12,13,14,15],
... }
>>> pyexcel.save_as(adict=content, dest_file_name="afile.csv")
```

Here is yet another piece of legacy code:

```
data = [
    [1, 2, 3],
    [4, 5, 6]
]
io = StringIO()
w = pyexcel.Writer(("csv",io))
w.write_rows(data)
w.close()
```

The new code is:

```
>>> data = [
...     [1, 2, 3],
```

(continues on next page)

(continued from previous page)

```

...     [4, 5, 6]
... ]
>>> io = pyexcel.save_as(dest_file_type='csv', array=data)
>>> for line in io.readlines():
...     print(line.rstrip())
1,2,3
4,5,6

```

9.4.2 2. “BookWriter” is gone. Please use save_book_as.

Here is a piece of legacy code:

```

import pyexcel
content = {
    "Sheet1": [[1, 1, 1, 1], [2, 2, 2, 2], [3, 3, 3, 3]],
    "Sheet2": [[4, 4, 4, 4], [5, 5, 5, 5], [6, 6, 6, 6]],
    "Sheet3": [[u'X', u'Y', u'Z'], [1, 4, 7], [2, 5, 8], [3, 6, 9]]
}
w = pyexcel.BookWriter("afile.csv")
w.write_book_from_dict(content)
w.close()

```

The replacement code is:

```

>>> import pyexcel
>>> content = {
...     "Sheet1": [[1, 1, 1, 1], [2, 2, 2, 2], [3, 3, 3, 3]],
...     "Sheet2": [[4, 4, 4, 4], [5, 5, 5, 5], [6, 6, 6, 6]],
...     "Sheet3": [[u'X', u'Y', u'Z'], [1, 4, 7], [2, 5, 8], [3, 6, 9]]
... }
>>> pyexcel.save_book_as(bookdict=content, dest_file_name="afile.csv")

```

9.5 Change log

9.5.1 0.6.0 - unreleased

Planned

1. investigate if hidden columns could be supported
2. update cookbook.py using 0.5.0 api
3. refactor test code
4. support missing pandas io features: use custom boolean values, write stylish spreadsheets.

Added

1. implemented `__len__` for `pyexcel.Book` and `pyexcel.Sheet`. Suddenly, `Sheet` could be a argument of `Sheet`. So `Sheet(Sheet([[1, 2]]))` works.
2. `pyexcel.Sheet.group_rows_by_column()`, helps categorize similiar fields into a book.

3. `__version__` at module level is finally available
4. Presentation won't break if there is an object (list, dict). Un-recognized type will be json dumped.
5. `Sheet.column.column_name`, `Sheet.row.row_name` is added to provide a short cut for `Sheet.column['column name']`, `Sheet.row['row name']`. In total, 4 characters less in typing.
6. plotting functions using echarts are integrated.

Updated

1. `custom_headers` for `iget_records` could have extra headers that does not exist in the current excel sheet. It helps header normalization across multiple excel sheets that has various headers. In this situation, what you may have done is to get a union of all headers in all excel sheets, then try get records from each sheet and merge all.
2. `pyexcel.Sheet.to_records()`, `pyexcel.get_records`, `pyexcel.Sheet.records` returns a generator instead of a static array of dictionary.

9.5.2 0.5.6 - 23.10.2017

Removed

1. #105, remove gease from `setup_requires`, introduced by 0.5.5.
2. removed testing against python 2.6

9.5.3 0.5.5 - 20.10.2017

Added

1. #103, include LICENSE file in MANIFEST.in, meaning LICENSE file will appear in the released tar ball.

9.5.4 0.5.4 - 27.09.2017

Updated

1. #100, `Sheet.to_dict()` gets out of range error because there is only one row.
2. Updated the baseline of `pyexcel-io` to 0.5.1.

9.5.5 0.5.3 - 01-08-2017

Updated

1. #95, respect the order of records in `iget_records`, `isave_as` and `save_as`.
2. #97, new feature to allow intuitive initialization of `pyexcel.Book`.

9.5.6 0.5.2 - 26-07-2017

Updated

1. embeded the enabler for pyexcel-htmlr. http source does not support text/html as mime type.

9.5.7 0.5.1 - 12.06.2017

Updated

1. support saving SheetStream and BookStream to database targets. This is needed for pyexcel-webio and its downstream projects.

9.5.8 0.5.0 - 19.06.2017

Added

1. Sheet.top() and Sheet.top_left() for data browsing
2. add html as default rich display in Jupyter notebook when pyexcel-text and pyexcel-chart is installed
3. add svg as default rich display in Jupyter notebook when pyexcel-chart and one of its implementation plugin(pyexcel-pygal, etc.) are is installed
4. new dictionary source supported: a dictionary of key value pair could be read into a sheet.
5. added dynamic external plugin loading. meaning if a pyexcel plugin is installed, it will be loaded implicitly. And this change would remove unnecessary info log for those who do not use pyexcel-text and pyexcel-gal
6. save_book_as before 0.5.0 becomes isave_book_as and save_book_as in 0.5.0 convert BookStream to Book before saving.
7. #83, file closing mechanism is enforced. free_resource is added and it should be called when iget_array, iget_records, isave_as and/or isave_book_as are used.

Updated

1. array is passed to pyexcel.Sheet as reference. it means your array data will be modified.

Removed

1. pyexcel.Writer and pyexcel.BookWriter were removed
2. pyexcel.load_book_from_sql and pyexcel.load_from_sql were removed
3. pyexcel.deprecated.load_from_query_sets, pyexcel.deprecated.load_book_from_django_models and pyexcel.deprecated.load_from_django_model were removed
4. Removed plugin loading code and lml is used instead

9.5.9 0.4.5 - 17.03.2017

Updated

1. #80: remove pyexcel-chart import from v0.4.x

9.5.10 0.4.4 - 06.02.2017

Updated

1. #68: regression save_to_memory() should have returned a stream instance which has been reset to zero if possible. The exception is sys.stdout, which cannot be reset.
2. #74: Not able to handle decimal.Decimal

Removed

1. remove get_{{file_type}}_stream functions from pyexcel.Sheet and pyexcel.Book introduced since 0.4.3.

9.5.11 0.4.3 - 26.01.2017

Added

1. '.stream' attribute are attached to *~pyexcel.Sheet* and *~pyexcel.Book* to get direct access the underneath stream in responding to file type attributes, such as sheet.xls. it helps provide a custom stream to external world, for example, Sheet.stream.csv gives a text stream that contains csv formatted data. Book.stream.xls returns a xls format data in a byte stream.

Updated

1. Better error reporting when an unknown parameters or unsupported file types were given to the signature functions.

9.5.12 0.4.2 - 17.01.2017

Updated

1. Raise exception if the incoming sheet does not have column names. In other words, only sheet with column names could be saved to database. sheet with row names cannot be saved. The alternative is to transpose the sheet, then name_columns_by_row and then save.
2. fix iget_records where a non-uniform content should be given, e.g. [{"x", "y"}, [1, 2], [3]], some record would become non-uniform, e.g. key 'y' would be missing from the second record.
3. *skip_empty_rows* is applicable when saving a python data structure to another data source. For example, if your array contains a row which is consisted of empty string, such as [“, ‘, “ ... ‘], please specify *skip_empty_rows=False* in order to preserve it. This becomes subtle when you try save a python dictionary where empty rows is not easy to be spotted.
4. #69: better documentation for save_book_as.

9.5.13 0.4.1 - 23.12.2016

Updated

1. #68: regression `save_to_memory()` should have returned a stream instance.

9.5.14 0.4.0 - 22.12.2016

Added

1. Flask-Excel#19 allow `sheet_name` parameter
2. pyexcel-xls#11 case-insensitive for `file_type`. `xls` and `XLS` are treated in the same way

Updated

1. #66: `export_columns` is ignored
2. Update dependency on pyexcel-io v0.3.0

9.5.15 0.3.3 - 07.11.2016

Updated

1. #63: cannot display empty sheet(hence book with empty sheet) as `texttable`

9.5.16 0.3.2 - 02.11.2016

Updated

1. #62: optional module import error become visible.

9.5.17 0.3.0 - 28.10.2016

Added:

1. file type setters for Sheet and Book, and its documentation
2. `iget_records` returns a generator for a list of records and should have better memory performance, especially dealing with large csv files.
3. `iget_array` returns a generator for a list of two dimensional array and should have better memory performance, especially dealing with large csv files.
4. Enable pagination support, and custom row renderer via pyexcel-io v0.2.3

Updated

1. Take *isave_as* out from *save_as*. Hence two functions are there for save a sheet as
2. #60: encode 'utf-8' if the console is of ascii encoding.
3. #59: custom row renderer
4. #56: set cell value does not work
5. `pyexcel.transpose` becomes `pyexcel.sheets.transpose`
6. iterator functions of `pyexcel.Sheet` were converted to generator functions
 - `pyexcel.Sheet.enumerate()`
 - `pyexcel.Sheet.reverse()`
 - `pyexcel.Sheet.vertical()`
 - `pyexcel.Sheet.rvertical()`
 - `pyexcel.Sheet.rows()`
 - `pyexcel.Sheet.rrows()`
 - `pyexcel.Sheet.columns()`
 - `pyexcel.Sheet.rcolumns()`
 - `pyexcel.Sheet.named_rows()`
 - `pyexcel.Sheet.named_columns()`
7. `~pyexcel.Sheet.save_to_memory` and `~pyexcel.Book.save_to_memory` return the actual content. No longer they will return a io object hence you cannot call `getvalue()` on them.

Removed:

1. `content` and `out_file` as function parameters to the signature functions are no longer supported.
2. `SourceFactory` and `RendererFactory` are removed
3. The following methods are removed
 - `pyexcel.to_array`
 - `pyexcel.to_dict`
 - `pyexcel.utils.to_one_dimensional_array`
 - `pyexcel.dict_to_array`
 - `pyexcel.from_records`
 - `pyexcel.to_records`
4. `pyexcel.Sheet.filter` has been re-implemented and all filters were removed:
 - `pyexcel.filters.ColumnIndexFilter`
 - `pyexcel.filters.ColumnFilter`
 - `pyexcel.filters.RowFilter`
 - `pyexcel.filters.EvenColumnFilter`
 - `pyexcel.filters.OddColumnFilter`

- *pyexcel.filters.EvenRowFilter*
- *pyexcel.filters.OddRowFilter*
- *pyexcel.filters.RowIndexFilter*
- *pyexcel.filters.SingleColumnFilter*
- *pyexcel.filters.RowValueFilter*
- *pyexcel.filters.NamedRowValueFilter*
- *pyexcel.filters.ColumnValueFilter*
- *pyexcel.filters.NamedColumnValueFilter*
- *pyexcel.filters.SingleRowFilter*

5. the following functions have been removed

- *add_formatter*
- *remove_formatter*
- *clear_formatters*
- *freeze_formatters*
- *add_filter*
- *remove_filter*
- *clear_filters*
- *freeze_formatters*

6. *pyexcel.Sheet.filter* has been re-implemented and all filters were removed:

- *pyexcel.formatters.SheetFormatter*

9.5.18 0.2.5 - 31.08.2016

Updated:

1. #58: *texttable* should have been made as compulsory requirement

9.5.19 0.2.4 - 14.07.2016

Updated:

1. For python 2, writing to *sys.stdout* by *pyexcel-cli* raise *IOError*.

9.5.20 0.2.3 - 11.07.2016

Updated:

1. For python 3, do not seek 0 when saving to memory if *sys.stdout* is passed on. Hence, adding support for *sys.stdin* and *sys.stdout*.

9.5.21 0.2.2 - 01.06.2016

Updated:

1. Explicit imports, no longer needed
2. Depends on latest setuptools 18.0.1
3. NotImplementedError will be raised if parameters to core functions are not supported, e.g. `get_sheet(cannot_find_me_option=)` will be thrown out as `NotImplementedError`)

9.5.22 0.2.1 - 23.04.2016

Added:

1. add pyexcel-text file types as attributes of `pyexcel.Sheet` and `pyexcel.Book`, related to #31
2. auto import pyexcel-text if it is pip installed

Updated:

1. code refactoring done for easy addition of sources.
2. bug fix #29, Even if the format is a string it is displayed as a float
3. pyexcel-text is no longer a plugin to pyexcel-io but to `pyexcel.sources`, see [pyexcel-text#22](#)

Removed:

1. `pyexcel.presentation` is removed. No longer the internal decorate `@outsource` is used. related to #31

9.5.23 0.2.0 - 17.01.2016

Updated

1. adopt pyexcel-io yield key word to return generator as content
2. `pyexcel.save_as` and `pyexcel.save_book_as` get performance improvements

9.5.24 0.1.7 - 03.07.2015

Added

1. Support pyramid-excel which does the database commit on its own.

9.5.25 0.1.6 - 13.06.2015

Added

1. get excel data from a http url

9.5.26 0.0.13 - 07.02.2015

Added

1. Support django
2. texttable as default renderer

9.5.27 0.0.12 - 25.01.2015

Added

1. Added sqlalchemy support

9.5.28 0.0.10 - 15.12.2015

Added

1. added csvz and tsvz format

9.5.29 0.0.4 - 12.10.2014

Updated

1. Support python 3

9.5.30 0.0.1 - 14.09.2014

Added

1. read and write csv, ods, xls, xlsx and xlsm files(which are referred later as excel files)
2. various iterators for the reader
3. row and column filters for the reader
4. utilities to get array and dictionary out from excel files.
5. cookbok recipes for some common and simple usage of this library.

CHAPTER 10

Indices and tables

- `genindex`
- `modindex`
- `search`

Bibliography

[f1] quoted from whatis.com. Technical details can be found at [MSDN XLS](#)

[f2] `xlsx` is used by MS-Excel 2007, more information can be found at [MSDN XLSX](#)

Symbols

[__getitem__\(\)](#) (pyexcel.Sheet method), 100
[__init__\(\)](#) (pyexcel.Book method), 81
[__init__\(\)](#) (pyexcel.Sheet method), 91
[__init__\(\)](#) (pyexcel.internal.generators.BookStream method), 117
[__init__\(\)](#) (pyexcel.internal.generators.SheetStream method), 117
[__init__\(\)](#) (pyexcel.internal.sheets.Column method), 119
[__init__\(\)](#) (pyexcel.internal.sheets.Matrix method), 113
[__init__\(\)](#) (pyexcel.internal.sheets.Row method), 118

A

[array](#) (pyexcel.Sheet attribute), 104

B

[Book](#) (class in pyexcel), 81
[bookdict](#) (pyexcel.Book attribute), 85
[BookStream](#) (class in pyexcel.internal.generators), 117

C

[cell_value\(\)](#) (pyexcel.Sheet method), 99
[colnames](#) (pyexcel.Sheet attribute), 103
[Column](#) (class in pyexcel.internal.sheets), 119
[column_at\(\)](#) (pyexcel.Sheet method), 101
[column_range\(\)](#) (pyexcel.Sheet method), 96
[columns\(\)](#) (pyexcel.Sheet method), 97
[content](#) (pyexcel.Sheet attribute), 95
[csv](#) (pyexcel.Book attribute), 85
[csv](#) (pyexcel.Sheet attribute), 105
[csvz](#) (pyexcel.Book attribute), 86
[csvz](#) (pyexcel.Sheet attribute), 106
[cut\(\)](#) (pyexcel.Sheet method), 110

D

[delete_columns\(\)](#) (pyexcel.Sheet method), 101
[delete_named_column_at\(\)](#) (pyexcel.Sheet method), 102
[delete_named_row_at\(\)](#) (pyexcel.Sheet method), 103
[delete_rows\(\)](#) (pyexcel.Sheet method), 100

[dict](#) (pyexcel.Sheet attribute), 104

E

[enumerate\(\)](#) (pyexcel.Sheet method), 98
[extend_columns\(\)](#) (pyexcel.Sheet method), 101
[extend_rows\(\)](#) (pyexcel.Sheet method), 100
[extract_a_sheet_from_a_book\(\)](#) (in module pyexcel), 80

F

[filter\(\)](#) (pyexcel.Sheet method), 109
[format\(\)](#) (pyexcel.Sheet method), 108
[free_resources\(\)](#) (in module pyexcel), 70

G

[get_array\(\)](#) (in module pyexcel), 53
[get_book\(\)](#) (in module pyexcel), 61
[get_book_dict\(\)](#) (in module pyexcel), 60
[get_dict\(\)](#) (in module pyexcel), 56
[get_records\(\)](#) (in module pyexcel), 58
[get_sheet\(\)](#) (in module pyexcel), 63

I

[iget_array\(\)](#) (in module pyexcel), 65
[iget_records\(\)](#) (in module pyexcel), 67
[isave_as\(\)](#) (in module pyexcel), 74
[isave_book_as\(\)](#) (in module pyexcel), 77

M

[map\(\)](#) (pyexcel.Sheet method), 109
[Matrix](#) (class in pyexcel.internal.sheets), 113
[merge_all_to_a_book\(\)](#) (in module pyexcel), 80
[merge_csv_to_a_book\(\)](#) (in module pyexcel), 79

N

[name_columns_by_row\(\)](#) (pyexcel.Sheet method), 102
[name_rows_by_column\(\)](#) (pyexcel.Sheet method), 103
[named_column_at\(\)](#) (pyexcel.Sheet method), 102
[named_row_at\(\)](#) (pyexcel.Sheet method), 103
[number_of_columns\(\)](#) (pyexcel.Sheet method), 96

number_of_rows() (pyexcel.Sheet method), 96
number_of_sheets() (pyexcel.Book method), 84

O

ods (pyexcel.Book attribute), 88
ods (pyexcel.Sheet attribute), 107

P

paste() (pyexcel.Sheet method), 110

R

rcolumns() (pyexcel.Sheet method), 97
records (pyexcel.Sheet attribute), 104
region() (pyexcel.Sheet method), 110
reverse() (pyexcel.Sheet method), 98
Row (class in pyexcel.internal.sheets), 118
row_at() (pyexcel.Sheet method), 100
row_range() (pyexcel.Sheet method), 96
rownames (pyexcel.Sheet attribute), 102
rows() (pyexcel.Sheet method), 96
rrows() (pyexcel.Sheet method), 97
rvertical() (pyexcel.Sheet method), 99

S

save_as() (in module pyexcel), 70
save_as() (pyexcel.Book method), 89
save_as() (pyexcel.Sheet method), 112
save_book_as() (in module pyexcel), 73
save_to_database() (pyexcel.Book method), 90
save_to_database() (pyexcel.Sheet method), 112
save_to_django_model() (pyexcel.Sheet method), 113
save_to_django_models() (pyexcel.Book method), 90
save_to_memory() (pyexcel.Book method), 89
save_to_memory() (pyexcel.Sheet method), 112
set_column_at() (pyexcel.Sheet method), 101
set_named_column_at() (pyexcel.Sheet method), 102
set_named_row_at() (pyexcel.Sheet method), 103
set_row_at() (pyexcel.Sheet method), 100
Sheet (class in pyexcel), 91
sheet_names() (pyexcel.Book method), 84
SheetStream (class in pyexcel.internal.generators), 117
split_a_book() (in module pyexcel), 80
stream (pyexcel.Book attribute), 88
stream (pyexcel.Sheet attribute), 108

T

transpose() (pyexcel.Sheet method), 109
tsv (pyexcel.Book attribute), 86
tsv (pyexcel.Sheet attribute), 105
tsvz (pyexcel.Book attribute), 86
tsvz (pyexcel.Sheet attribute), 106

U

url (pyexcel.Book attribute), 85

url (pyexcel.Sheet attribute), 105

V

vertical() (pyexcel.Sheet method), 99

X

xls (pyexcel.Book attribute), 87
xls (pyexcel.Sheet attribute), 106
xlsm (pyexcel.Book attribute), 87
xlsm (pyexcel.Sheet attribute), 107
xlsx (pyexcel.Book attribute), 87
xlsx (pyexcel.Sheet attribute), 107